

Appendix D1-1 - Pad Seismic Analysis Files

| | |
|--|---|
| REFUND Soil Profile.xlsx | Spreadsheet with soil properties for each different layer in subgrade model for input to REFUND program |
| REFUND vpad.out REFUND hpad.out | Output listing of REFUND analysis which generates frequency dependent impedance functions - 6x6 stiffness matrices calculated at each surface node over pad model rectangular area, for a given range of frequencies - used in characterizing soil behavior in a subsequent time history dynamic analysis of a mass-stiffness model of a representative portion of a vertical storage pad. |
| FRIDAY vpad.out FRIDAY hpad.out | Output listing of FRIDAY time history dynamic analysis of a representative portion of a vertical storage pad. Geometry, material properties, mass properties, damping, and boundary conditions of pad input in STRUDL format. Pad dynamic model coupled to soil impedance functions generated in REFUND analysis. Time history accelerations in 3D applied at pad/soil interface. Solution yields displacement and acceleration time histories for 0.25G earthquake, from which maximum values extracted and output. |
| Vpad Accelerations.xlsx Hpad Accelerations.xlsx | Spreadsheet used to multiply max accelerations from 0.25G FRIDAY analysis by pad nodal masses to generate static forces to be applied to pad model for static structural integrity evaluation. Forces for 0.25G seismic evaluation are increased by factor of 3 for 0.75F analysis. |
| Pad Beam Properties.xlsx | Spreadsheet to calculate pad stick model beam properties and masses for input to structural integrity calculation. |
| V Pad Structure-0.25G.gto H Pad Structure-0.25G.gto V Pad Structure-0.75G.gto H Pad Structure-0.75G.gto | GTSTRUDL analyses of pad stick models used to evaluate pads for structural integrity. Vertical soil spring boundary conditions coded at base of pad to allow bending moments to develop. Deadweight and X, Y, and Z direction seismic loads solved individually. Seismic spatial results combined by SRSS, and absolutely summed with deadweight results to yield Extreme combination. Forces and moments in pad and at base of casks output for subsequent pad and seismic restraint sizing. Reactions at tabulated for soil bearing pressure evaluations. |
| Vpad Seismic Restraints.xlsx | Spreadsheet to size base restraint for vertical casks to resist turnover moments for lateral and uplift accelerations associated with 0.75G EQ. Complete inventory of Pilot ISF vertical casks considered. |
| Pad Seismic Results.xlsx | Spreadsheet to design vertical and horizontal pad reinforcing for bending moment demands for both 0.25G and 0.75G earthquakes. Also, verify vertical and horizontal soil bearing pressures against allowable values, and design micropiles as required. |

Appendix D1-2 - Vault Seismic Analysis Files

| | |
|--|---|
| REFUND Soil Profile.xlsx | Spreadsheet with soil properties for each different layer in subgrade model for input to REFUND program |
| REFUND vault.out | Output listing of REFUND analysis which generates frequency dependent impedance used in characterizing soil behavior in a subsequent time history dynamic analysis of a mass-stiffness model of a representative portion of the above grade vault. |
| MODEL VAULT.pdf | Simplified stick model of vault generated using FRIDAY geometry and connectivity data. |
| FRIDAY vault.out | Output listing of FRIDAY time history dynamic analysis of model of a representative portion of the above ground vault. Geometry, material properties, mass properties, damping, and boundary conditions of vault input in STRUDL format. Vault dynamic model coupled to soil impedance functions generated in REFUND analysis. Time history accelerations in 3D applied at vault/soil interface. Solution yields displacement and acceleration time histories for 0.25G earthquake, from which maximum values extracted and output. |
| Vault Accelerations.xlsx | Spreadsheet used to multiply max accelerations from 0.25G FRIDAY analysis by vault nodal masses to generate static forces to be applied to vault model for static structural integrity evaluation. |
| Vault Beam Properties.xlsx | Spreadsheet to calculate vault stick model beam properties and masses for input to structural integrity calculation. |
| Vault Structure-0.25G.gto | GTSTRUDL analyses of vault stick model used to evaluate vault for structural integrity. Vertical soil spring boundary conditions coded at base of pad to allow bending moments to develop. Deadweight and X, Y, and Z direction seismic loads solved individually. Seismic spatial results combined by SRSS, and absolutely summed with deadweight results to yield Extreme combination. Forces and moments in pad and at base of casks output for subsequent pad and seismic restraint sizing. Reactions at tabulated for soil bearing pressure evaluations. |
| Vault Concrete Results.xlsx | Spreadsheet to calculate max shear and bending moment demands in stack and operating floor for 0.75G EQ based on 0.25G EQ results. |
| Vault Op Floor Results.xls | Spreadsheet to design reinforcing for one-way slab "beams" between shield plug perforations in vault operating floor based on 0.25G and 0.75G maximum shear and bending moment demands. |
| Vault Stack Calcs – 0.25G.xls Vault Stack Calcs – 0.75G.xls | Hand calculations of maximum capacities of vault stack cross-section at operating floor interface. |
| Vault Soil Results.xls | Spreadsheet to verify soil bearing pressures in vertical and horizontal directions. Includes bearing capacity calc using Meyerhof method and comparison between MOX and vault. Also includes micropile design parameters for 0.75G AGV lateral and longitudinal directions. |

HOLTEC INTERNATIONAL

DOCUMENT ISSUANCE AND REVISION STATUS¹

DOCUMENT NAME:

DOCUMENT NO.:

CATEGORY: GENERIC

PROJECT NO.:

PROJECT SPECIFIC

Rev.
No. ²

Date
Approved

Author's
Initials

VIR #

DOCUMENT CATEGORIZATION

In accordance with the Holtec Quality Assurance Manual and associated Holtec Quality Procedures (HQPs), this document is categorized as a:

- Calculation Package³ (Per HQP 3.2) Technical Report (Per HQP 3.2)
 (Such as a Licensing Report)
- Design Criterion Document (Per HQP 3.4) Design Specification (Per HQP 3.4)
- Other (Specify):

DOCUMENT FORMATTING

The formatting of the contents of this document is in accordance with the instructions of HQP 3.2 or 3.4 except as noted below:

DECLARATION OF PROPRIETARY STATUS

- Nonproprietary Holtec Proprietary Privileged Intellectual Property (PIP)

Notes



Holtec Center, One Holtec Drive, Marlton, NJ 08053

Telephone (856) 797- 0900

Fax (856) 797 - 0909

***PRELIMINARY USED NUCLEAR FUEL
STORAGE DESIGN CONCEPT
- ABOVEGROUND VERTICAL -
SCOPING THERMAL ANALYSIS***

FOR

CB&I FEDERAL SERVICES

Holtec Report No: HI-2156437

Holtec Project No: 2427

Sponsoring Holtec Division: NPD

Report Class : SAFETY RELATED

COMPANY PRIVATE

This document is proprietary and the property of Holtec International. It is to be used only in connection with the performance of work by Holtec International or its designated subcontractors or Holtec's Client. Reproduction, publication or representation, in whole or in part, for any other purpose by any other party other than the Client or its designated contractors, that are bound by a corporate or individual non-disclosure and non-use agreement with the Client, is expressly forbidden.

TABLE OF CONTENTS

| <u>Sec.</u> | <u>Title</u> | <u>Page #</u> |
|-------------|--|---------------|
| 1.0 | Introduction..... | 1 |
| 2.0 | Analysis Methodology and Acceptance Criteria | 2 |
| 3.0 | Input Data and Assumptions..... | 3 |
| 4.0 | Calculations and Results..... | 5 |
| 5.0 | References..... | 6 |

Tables (2 tables on 4 pages)

Figures (13 figures on 13 pages)

Appendix A: Canister Surface Heat Flux Calculations (2 pages)

Appendix B: Original CB&I Thermal Study Description (4 pages)

Appendix C: Modifications to Preliminary Design for Thermal Analysis (3 pages)

SUMMARY OF REVISION

Revision 0: Original issue.

.

1.0 INTRODUCTION

On 4 April 2014, CB&I Federal Services, along with subcontractors including Holtec, submitted a proposal to the U.S. Department of Energy to provide services requested by the so-called Task Order 16. In support of Task Order 16, CB&I developed a preliminary design concept for an aboveground ventilated storage building where sealed canisters of used nuclear fuel would be stored in a vertical orientation. The preliminary design concept (see Figure 1) called for a structure with canisters of used nuclear fuel placed in a large storage “hall” in parallel rows of eight canisters per row. Air is drawn into the storage hall, via natural draft, through a missile-protected and radiation-shielded inlet at one end of the storage hall and exhausted back to the atmosphere through a tall chimney at the other end. Air flow through the storage hall removes the decay heat from the outer surfaces of the canisters of used nuclear fuel.

Working together with Holtec, the preliminary design was modified to improve its canister cooling performance and to protect the concrete structure of the storage building from excessively-high temperatures, which would complicate the design of the building’s reinforced concrete. The analysis described in this report is performed as a scoping study to demonstrate the following:

1. Substantial air will be drawn into and through the storage hall via natural draft alone, to provide a completely passive heat removal mechanism.
2. Canister surface temperatures will be low enough to provide confidence that acceptable canister and contained used nuclear fuel temperatures will be likely.
3. Building structure temperatures will be low enough to provide confidence that reinforced concrete design can be accomplished without recourse to extraordinary measures.

Due to the preliminary nature of the design concept and the significant assumptions needed to enable this scoping thermal analysis to be performed, this document is not suited to support nuclear safety related activities. Thus, this document is classified as “not safety related” and has not been subject to all the controls of Holtec’s nuclear quality assurance program.

2.0 ANALYSIS METHODOLOGY AND ACCEPTANCE CRITERIA

Quantification of the coupled flow and temperature fields in the storage building is accomplished through the use of a Computational Fluid Dynamics (CFD) analysis. The CFD analysis is performed utilizing the Fluent [1] fluid flow and heat transfer modeling program. Navier-Stokes equations of fluid motion, including full buoyancy effects, along with the energy conservation equation are solved to obtain the steady-state flow and temperature fields in the building.

A three-dimensional model of a section through the storage hall is made using Fluent. The width of the model encompasses one row of canisters. The sides of the model are symmetry planes. The model explicitly includes the geometry of the air inlet and the outlet chimney within the modeled section. The floor and ceiling of the storage hall are also explicitly included, including shield plugs in the ceiling above each canister), with appropriate heat transfer boundary conditions on the top of the ceiling (natural convection) and on the bottom of the floor (conduction to constant temperature soil). Radiation shields on the undersides of the shield plugs are modeled as conduction walls with the thermal conductivity of air and the emissivity of aluminum. The used fuel canisters are modeled as right-circular cylinders sitting on the storage hall floor. The canister internals are not modeled and the decay heat generated by the used fuel is modeled as constant heat fluxes out of the canister surfaces. The cylindrical side and flat top surfaces of the canisters are modeled as shell conduction walls.

Air flow within the building is in the turbulent regime, so turbulence is included and is modeled using the $k-\omega$ model in Fluent. Radiation heat transfer between canisters and between the canisters and the building structure is included and is modeled using the Discrete Ordinates model in Fluent. The temperature dependence of the density of air is modeled using the ideal gas law.

The analyses performed in this report are intended only to estimate the thermal performance of the design concept so its overall viability can be evaluated. As such, no acceptance criteria are applied and no conclusions are drawn.

3.0 INPUT DATA AND ASSUMPTIONS

The input data used to perform the analysis are presented in Table 1. Additionally, the following necessary assumptions are made in performing the analysis:

- The decay heat inside each canister is emitted from the top and sides of the canisters, with 15% being emitted from the top and 85% emitted from the sides. This distribution is based on engineering judgment from our experience designing dry storage cask systems.
- The air inlet flow straightener is modeled by restricting air flow to be in a horizontal plane only. Given the preliminary nature of the design it is not possible to model in a more realistic manner. The pressure drop through the flow straightener is not expected to be a large portion of the total, so this assumption is expected to be negligible.
- The natural convection heat transfer coefficient on the top surface of the storage hall ceiling is set to $1 \text{ W}/(\text{m}^2 \times \text{K})$. This coefficient is based on engineering judgment from our experience designing dry storage cask systems.
- The majority of surfaces outside the storage hall (i.e., in the air inlet, air outlet and chimney) are modeled as adiabatic. The heat transfer through these surfaces is not expected to significantly affect the maximum temperatures, which will occur in the storage hall.
- The shield plugs above each canister are modeled as the same diameter as the canisters. The plugs would have to have a diameter larger than that of the canisters so the canisters could pass through the holes in the ceiling during load/unloading of the storage hall, but this geometric simplification is not expected to significantly affect the results.
- The thermal shields on the underside of the shield plugs above each canister are modeled as a thin sheet of aluminum backed by a one-inch air gap. This is consistent with mounting an aluminum sheet hanging below the underside of each plug. Similar thermal

THIS REPORT HAS NOT BEEN QA VALIDATED

shields have been used by us in a dry storage cask system. The emissivity of the aluminum is assumed to be 0.05. Given the preliminary nature of the design, and therefore without knowledge of the surface condition (i.e., polished, dull, anodized, etc.) it is not possible to model in a more realistic manner.

4.0 CALCULATIONS AND RESULTS

Using the input data and assumptions in Section 5.0, the CFD model is constructed with the features described in Section 2.0. Figures 2 and 3 present views of the model geometry. To ensure the granularity of the model is fine enough to properly capture both the large-scale and small-scale effects, both of which are important to the accuracy of the solution, a relatively large model with 3,163,300 hexahedral cells and 3,264,123 nodes is built. A single scenario with each of the eight canisters containing used fuel with a decay heat load of 25 kW (200 kW total for the row) is evaluated. The canister top and side heat fluxes are computed in Appendix A. The following computer files are created in the performance of the CFD analysis:

```
Directory of G:\Projects\2427\REPORTS\Thermal Reports\HI-2156437\Rev0\cfd
```

```
12/02/2014  10:25 AM          311,427,072  va196.dbs  
12/05/2014  10:37 AM          331,852,192  va196-a.cas  
12/05/2014  10:37 AM          4,422,360,814  va196-a.dat
```

The results of the calculations are summarized in Table 2 and in Figures 4 through 13. As stated in Section 3.0, no acceptance criteria are applied to these results.

5.0 REFERENCES¹

- [1] Fluent v14.5, Ansys Inc., Copyright 2012 SAS IP Inc.
- [2] “Final Safety analysis Report on the HI-STORM UMAX Canister Storage System,” Holtec Report HI-2115090, Revision 2, Subsection 4.2.

¹ This revision status of Holtec documents cited above is subject to updates as the project progresses. This document will be revised if a revision to any of the above-referenced Holtec work products materially affects the instructions, results, conclusions or analyses contained in this document. Otherwise, a revision to this document will not be made and the latest revision of the referenced Holtec documents shall be assumed to supersede the revision numbers cited above. The Holtec Project Manager bears the undivided responsibility to ensure that there is no intra-document conflict with respect to the information contained in all Holtec-generated documents on a *safety-significant* project. The latest revision number of all documents produced by Holtec International in a *safety-significant* project is readily available from the company’s Document Transmittal Form (DTF) database.

THIS REPORT HAS NOT BEEN QA VALIDATED

| Table 1 – Input Data Summary | | |
|--|------------------|----------------------------|
| Input Parameter | Value | Source(s) |
| Storage Hall Height | 16' 4" + 2' 8" | Appendix B + Appendix C |
| Length from Ends of Storage Hall to Center of: First Canister from Inlet (Canister 8) Last Canister From Outlet (Canister 1) | 10' 0" 10' 0" | Figure 1 |
| Canister Center-to-Center Pitch | 12' 0" | Figure 1 |
| Storage Hall Ceiling Thickness | 5' 0" | Appendix C |
| Storage Hall Floor Thickness | 5' 0" | Appendix C |
| Shield Plug Thickness | 4' 0" | Appendix C |
| Air Inlet Height | 12' 0" | Appendix B |
| Air Inlet Flow Straightener Height | 14' 0" | Appendix B |
| Air Inlet Flow Straightener Length | 4' 0" | Appendix B |
| Air Inlet Shield Wall Height | 15' 0" | Appendix B |
| Air Inlet Shield Wall Thickness | 3' 0" | Appendix B |
| Air Inlet Flow Path Around Shield Wall Width | 3' 0" | Appendix B |
| Exit from Storage Hall Height | 14' 0" | Appendix B |
| Chimney Height | 87' 0" | Appendix B |
| Chimney Length | 5' 0" | Appendix B |
| Canister Diameter | 70" | Appendix B |
| Canister Maximum Height | 16' 4" | Appendix B |
| Canister Decay Heat Load | 25 kW | Appendix C |
| Number of Canisters per Row | 8 | Figure 1 |
| Ambient Air Temperature | 120°F | Appendix B |
| Soil Temperature Below Floor | 55°F | Appendix C |
| (continued on next page) | | |

THIS REPORT HAS NOT BEEN QA VALIDATED

| Table 1 – Input Data Summary (continued from previous page) | | |
|---|---|------------------|
| Input Parameter | Value | Source(s) |
| Thermal Conductivity of Concrete | 1.05 Btu/(hr×ft×°F) | [2] |
| Emissivity of Concrete | 0.88 | [2] |
| Thermal Conductivity of Stainless Steel | 8.4 Btu/(hr×ft×°F) | [2] |
| Emissivity of Stainless Steel | 0.36 | [2] |
| Emissivity of Aluminum | 0.05 | Assumed |
| Molecular Weight of Air | 28.966 g/mol | Fluent Default |
| Thermal Conductivity of Air at 32°F at 200°F at 450°F at 700°F at 1000°F | 0.0139 Btu/(hr×ft×°F) 0.0173 Btu/(hr×ft×°F) 0.0225 Btu/(hr×ft×°F) 0.0272 Btu/(hr×ft×°F) 0.0336 Btu/(hr×ft×°F) | [2] |
| Viscosity of Air at 32°F at 70.5°F at 338.4°F at 567.1°F at 701.6°F at 1078.2°F | 172.0 μP 182.4 μP 229.4 μP 246.3 μP 316.7 μP 377.6 μP | [2] |
| Specific Heat Capacity of Air | 0.24 Btu/lb×°F | [2] |

THIS REPORT HAS NOT BEEN QA VALIDATED

| Table 2 – Numeric Results | |
|---|------------------------------------|
| Result Parameter | Value |
| Air Flow Through Storage Hall | |
| Air Inlet Temperature | 120°F |
| Average Air Outlet Temperature | 160°F |
| Air Mass Flow Rate | 68,175 lb/hr |
| Canister 1 Surface Temperatures and Heat Transfer Coefficients | |
| Lid Maximum Temperature | 517°F |
| Lid Average Heat Transfer Coefficient | 0.994 Btu/(hr×ft ² ×°F) |
| Side Maximum Temperature | 470°F |
| Side Average Heat Transfer Coefficient | 0.949 Btu/(hr×ft ² ×°F) |
| Whole-Surface Average Temperature | 339°F |
| Canister 2 Surface Temperatures and Heat Transfer Coefficients | |
| Lid Maximum Temperature | 523°F |
| Lid Average Heat Transfer Coefficient | 0.979 Btu/(hr×ft ² ×°F) |
| Side Maximum Temperature | 473°F |
| Side Average Heat Transfer Coefficient | 0.936 Btu/(hr×ft ² ×°F) |
| Whole-Surface Average Temperature | 343°F |
| Canister 3 Surface Temperatures and Heat Transfer Coefficients | |
| Lid Maximum Temperature | 525°F |
| Lid Average Heat Transfer Coefficient | 0.976 Btu/(hr×ft ² ×°F) |
| Side Maximum Temperature | 474°F |
| Side Average Heat Transfer Coefficient | 0.943 Btu/(hr×ft ² ×°F) |
| Whole-Surface Average Temperature | 342°F |
| Canister 4 Surface Temperatures and Heat Transfer Coefficients | |
| Lid Maximum Temperature | 525°F |
| Lid Average Heat Transfer Coefficient | 0.977 Btu/(hr×ft ² ×°F) |
| Side Maximum Temperature | 473°F |
| Side Average Heat Transfer Coefficient | 0.959 Btu/(hr×ft ² ×°F) |
| Whole-Surface Average Temperature | 339°F |
| (continued on next page) | |

THIS REPORT HAS NOT BEEN QA VALIDATED

| Table 2 – Numeric Results (continued from previous page) | |
|---|------------------------------------|
| Result Parameter | Value |
| Canister 5 Surface Temperatures and Heat Transfer Coefficients | |
| Lid Maximum Temperature | 521°F |
| Lid Average Heat Transfer Coefficient | 0.980 Btu/(hr×ft ² ×°F) |
| Side Maximum Temperature | 471°F |
| Side Average Heat Transfer Coefficient | 0.982 Btu/(hr×ft ² ×°F) |
| Whole-Surface Average Temperature | 334°F |
| Canister 6 Surface Temperatures and Heat Transfer Coefficients | |
| Lid Maximum Temperature | 519°F |
| Lid Average Heat Transfer Coefficient | 0.985 Btu/(hr×ft ² ×°F) |
| Side Maximum Temperature | 466°F |
| Side Average Heat Transfer Coefficient | 1.014 Btu/(hr×ft ² ×°F) |
| Whole-Surface Average Temperature | 328°F |
| Canister 7 Surface Temperatures and Heat Transfer Coefficients | |
| Lid Maximum Temperature | 516°F |
| Lid Average Heat Transfer Coefficient | 0.993 Btu/(hr×ft ² ×°F) |
| Side Maximum Temperature | 460°F |
| Side Average Heat Transfer Coefficient | 1.048 Btu/(hr×ft ² ×°F) |
| Whole-Surface Average Temperature | 319°F |
| Canister 8 Surface Temperatures and Heat Transfer Coefficients | |
| Lid Maximum Temperature | 505°F |
| Lid Average Heat Transfer Coefficient | 1.015 Btu/(hr×ft ² ×°F) |
| Side Maximum Temperature | 456°F |
| Side Average Heat Transfer Coefficient | 1.118 Btu/(hr×ft ² ×°F) |
| Whole-Surface Average Temperature | 305°F |
| Structure Temperatures | |
| Ceiling Maximum Temperature | 330°F |
| Ceiling Plugs Maximum Temperature | 303°F |
| Floor Maximum Temperature | 278°F |

THIS REPORT HAS NOT BEEN QA VALIDATED






Figure 1 – Original CB&I Design Concept



| | |
|------|--|
| Mesh | Dec 05, 2014 ANSYS Fluent 14.5 (3d, dp, pbns, sstk) |
|------|--|

Figure 2 – Model Geometry – Symmetry Planes Hidden



Mesh

Dec 05, 2014
ANSYS Fluent 14.5 (3d, dp, pbns, sstk)

Figure 3 – Model Geometry – Symmetry Planes and Ceiling Hidden

THIS REPORT HAS NOT BEEN QA VALIDATED




Figure 4 – Canisters Surface Temperature Contours

THIS REPORT HAS NOT BEEN QA VALIDATED





Figure 5 – Ceiling Temperature Contours


THIS REPORT HAS NOT BEEN QA VALIDATED



Contours of Static Temperature (f) Dec 05, 2014
ANSYS Fluent 14.5 (3d, dp, pbns, sstk)

Figure 6 – Floor Temperature Contours


THIS REPORT HAS NOT BEEN QA VALIDATED



Contours of Static Temperature (f) Dec 05, 2014
ANSYS Fluent 14.5 (3d, dp, pbns, sstk)

Figure 7 – Chimney Temperature Contours


THIS REPORT HAS NOT BEEN QA VALIDATED



Velocity Vectors Colored By Static Temperature (f)


Dec 05, 2014
ANSYS Fluent 14.5 (3d, dp, pbns, sstk)

Figure 8 – Horizontal Velocity Vectors (colored by temperature) at Canisters Mid-Height



Velocity Vectors Colored By Static Temperature (f) Jan 27, 2015
ANSYS Fluent 14.5 (3d, dp, pbns, sstk)

Figure 9 – Horizontal Velocity Vectors (colored by temperature) One Foot Above Canisters



Velocity Vectors Colored By Static Temperature (f)

Dec 05, 2014
ANSYS Fluent 14.5 (3d, dp, pbns, sstk)

Figure 10 – Vertical Velocity Vectors (colored by temperature)

THIS REPORT HAS NOT BEEN QA VALIDATED




Figure 11 – Canisters Surface Heat Transfer Coefficient Contours

THIS REPORT HAS NOT BEEN QA VALIDATED





Figure 12 – Canisters Total Heat Flux Contours

THIS REPORT HAS NOT BEEN QA VALIDATED



Contours of Radiation Heat Flux (w/m²)

Dec 05, 2014
ANSYS Fluent 14.5 (3d, dp, pbns, sstk)

Figure 13 – Canisters Radiation Heat Flux Contours

Appendix A
Canister Surface Heat Flux Calculations

INTRODUCTION

The calculations presented in this worksheet are performed to determine heat fluxes from the top and side surfaces of the canisters of used fuel in the storage hall.

WORKSHEET-SPECIFIC INPUT DATA

| | |
|---------------------------|--|
| OD := 70·in | Canister Diameter, from Table 1 |
| H _{can} := 196in | Canister Height, from Table 1 |
| Q _{can} := 25·kW | Total Heat per Canister, from Table 1 |
| F _{side} := 85·% | Fraction of Heat Emitted by Side, from Section 3.0 |
| F _{top} := 15·% | Fraction of Heat Emitted by Top, from Section 3.0 |

CALCULATIONS

$$Q_{\text{side}} := Q_{\text{can}} \cdot F_{\text{side}} = 21.25 \text{ kW}$$

$$Q_{\text{top}} := Q_{\text{can}} \cdot F_{\text{top}} = 3.75 \text{ kW}$$

$$A_{\text{side}} := \pi \cdot \text{OD} \cdot H_{\text{can}} = 299.324 \cdot \text{ft}^2$$

$$A_{\text{top}} := \frac{\pi}{4} \cdot \text{OD}^2 = 26.725 \cdot \text{ft}^2$$

$$q_{\text{side}} := \frac{Q_{\text{side}}}{A_{\text{side}}} = 764.166 \cdot \frac{\text{W}}{\text{m}^2}$$

$$q_{\text{top}} := \frac{Q_{\text{top}}}{A_{\text{top}}} = 1510.351 \cdot \frac{\text{W}}{\text{m}^2}$$

Appendix B
Original CB&I Thermal Study Description

Vertical DSC Vault Thermal Study Description

Purpose: To validate whether or not a vault module with up to 40 vertical dry storage canisters will be able to maintain the external surface temperature(s) of the canisters below a maximum temperature limit using passive cooling.

Vault Models: For vertical DSC's, either a 2D or a 3D vault module model may be used, as follows:
2D – vertical-transverse section through the vault with a single row of up to (8) 70" diameter canisters at 12' c-c spacing. Flow area in vault (between inlet and outlet vanes) is 16.33' high x 104' long x 8.67' wide. Stack flue is 70' high (above vault ceiling) x 5' deep x 8.67' wide. Air inlet is shown in Sketch 1. Air outlet is shown in Sketch 2.

3D – vault module with up to (5) rows of up to (8) 70" diameter canisters at 12' c-c spacing, both ways. Flow area in vault (between inlet and outlet vanes) is 17.00' high x 104' long x 58' wide. Stack flue is 70' high (above vault ceiling) x 5' deep x 48' wide. Air inlet is shown in Sketch 1. Air outlet is shown in Sketch 2.

Ref Drwg: Vault Building – Option 4A-D, 5A-D – Vertical Storage Area Elevation

Thermal Boundary

Conditions: Vault floor* – conduction down through 6' of concrete with exterior temperature = 55°F
 Vault walls and ceiling; stack flue surfaces – adiabatic
 Ambient Air - 120°F; 14.7 psia; dry; calm (no velocity)
 *trial basis. If effect minimal, use adiabatic.

Canister

Parameters: O.D. – 70"
 Height – (2) cases: 16.33' max, 9.5' min
 Thermal output – (2) cases: 15 kW, 25 kW
 Maximum Surface Temperature - 300°F
 Film coefficients** - cylindrical surface, natural convection, $h_{CYL-NC} = 0.18 (\Delta T)^{0.33}$
 - top surface, natural convection, $h_{TOP-NC} = 0.22 (\Delta T)^{0.33}$
 - cylindrical surface, forced convection, in-line tubes,
 $h_{CYL-FC} = (K/D) 0.26 (\rho V D / \mu)^{0.6} (\mu C_p / K)^{0.33}$
 ** or equivalent.


Analysis


Parameters: Calculate steady-state air flow, air temperature distributions throughout vault and stack, and maximum surface temperatures of canisters (if possible)***, based on the following thermal inputs:

- (1) Fully loaded vault with 25 kW canisters
- (2) Fully loaded vault with 15 kW canisters
- (3) Single 15 kW canister, centered on last row (adjacent to stack)

*** if not possible, calculate max air temperature adjacent to canister.

THIS REPORT HAS NOT BEEN QA VALIDATED





Appendix C
Modifications to Preliminary Design for Thermal Analysis

THIS REPORT HAS NOT BEEN QA VALIDATED

Evan Rosenbaum

From: Brunson, Bruce [Bruce.Brunson@CBIFederalServices.com]
Sent: Wednesday, November 19, 2014 12:29 PM
To: Steve Wright
Cc: Debu Majumdar; Evan Rosenbaum; Lewis, Donald Wayne (DEN); Clemmens, Jack
Subject: Holtec Thermal Study of Vault

Hi Steve:

The project has decided to proceed with modifying the CFD model of the vault as we discussed yesterday and re-running the analysis. We'd like to see the following changes incorporated:

- Increase the clearance between the top of the canisters and the underside of the operating floor from 8" to 2'-8"
- Include an insulating layer equivalent to a 2" air gap with a surface emissivity equal to a thin sheet of aluminum on the underside of the operating floor over the projected area of each canister
- Include surface conduction over the sides and top surfaces of each canister
- Delete the modeling of the flow straightener on the vault outlet

After making the changes above, please run the (8) canister, 25 kW per canister model to determine the steady state temperature distribution and produce the same table of maximum temperatures and the same temperature contour plots and velocity vector plots as were generated previously. If there is a way to have FLUENT automatically calculate effective surface film coefficients averaged over the canister lids and sides, we'd like to document those as well (suggest using a reference temperature of 120F for all canisters).

Your team is authorized to spend an additional 80 hours to make the modeling changes, re-run the (1) case, and generate the output plots. If at all possible, we'd like to have the results by December 5th, but we recognize that your computer resources are in high demand. Please contact me if you have any questions or issues.

Best Regards,

Bruce Brunson
PPL Mechanical Engineer III
Federal Services
MOX Offsite Support Services

Tel: +1 303 486 2566

Fax: +1 303 486 2570
bruce.brunson@CBIFederalServices.com
CB&I
6380 S. Fiddler's Green Circle, Suite 300
Greenwood Village, CO 80111
www.CBI.com

This e-mail and any attached files may contain CB&I Federal Services LLC (or its affiliates) confidential and privileged information. This information is protected by law and/or agreements between CB&I Federal Services LLC (or its affiliates) and either you, your employer or any contract provider with which you or your employer are associated. If you are not an intended recipient, please contact the sender by reply e-mail and delete all copies of this e-mail; further, you are notified that disclosing, copying, distributing or taking any action in reliance on the contents of this information is strictly prohibited.

Evan Rosenbaum

From: Steve Wright
Sent: Tuesday, November 04, 2014 8:29 PM
To: Debu Majumdar; Evan Rosenbaum
Subject: Fw: Discuss Preliminary Results of Vault Thermal Model

Please see email below and let's talk soon.

Sent from my BlackBerry 10 smartphone on the Verizon Wireless 4G LTE network.

From: Brunson, Bruce <Bruce.Brunson@CBIFederalServices.com>
Sent: Tuesday, November 4, 2014 6:39 PM
To: Steve Wright
Subject: RE: Discuss Preliminary Results of Vault Thermal Model

Steve –

I haven't forgotten you. The seismic and thermal models both provided results at the same time, and neither one of them worked as is. We are modifying the stack geometry (increasing the flue width) to try and resist the rocking accelerations associated with 0.75G horizontal earthquake. We will let you know the final dimension when we settle on something that we can design rebar for. In the mean time, Evan can get going incorporating the following changes to the CFD model(s):

- Raise the concrete ceiling by 2 feet
- Eliminate the flow straightener at the exit
- Reduce the height of the missile shield wall in the inlet to ½ of its current value and double the thickness of the air passages at the inlet
- Stagger every other canister, ensuring that the canister nearest the stack is split
- Allow conduction heat transfer on the canister surfaces
- Code a layer of insulator/reflector in the ceiling above each canister with a diameter of 74" to knock down the radiation load on the concrete (the shield plugs are 4' thick; the ceiling is 5' thick, leaving a 1' recess for insulation)
- On the floor, code a 6' thick layer of concrete with a 55° constant temperature boundary condition on the lower surface to conduct away the radiation heat load from the upper surface (every little bit helps).

We're still working on the acceptance criteria and will forward you the results when ready. Please call Wayne to let him know about how many hours these changes will take, but don't hold up Evan waiting for a reply.

Thanks, Steve.

Bruce Brunson
PPL Mechanical Engineer III
Federal Services
MOX Offsite Support Services


Tel: +1 303 486 2566

Fax: +1 303 486 2570


bruce.brunson@CBIFederalServices.com

CB&I


1 - C-PAD, Current Commercial Storage on Concrete Pad (Assuming all Vertical Case)




Throughput: 20 DPCs placed every four weeks, or an average of 5 DPC per week.










1 - C-PAD, Current Commercial Storage on Concrete Pad (Assuming all Horizontal Case)




1 - C-PAD, Current Commercial Storage on Concrete Pad (Base Case)




Throughput: 20 DPCs placed every four weeks, or an average of 5 DPCs per week.

| Legend | |
|---|--------------------------------------|
|  | No Heavy Equipment |
|  | 200T OTB Crane |
|  | Jib Crane/Stick Crane |
|  | Self-Powered Transfer Cart |
|  | Shielded Transfer Cart |
|  | Vertical/Horizontal Cask Transporter |
|  | Railyard Tug |





A - C-STDa, Pad Storage Using a Vertical Standard Storage Overpack




Throughput: 20 DPCs placed every four weeks, or an average of 5 per week




B - C-STDb, Pad Storage Using Single Vertical Standard Storage Overpack



Throughput: 20 DPCs placed every four weeks, or an average of 5 DPCs per week.




2C - C-STDc, Pad Storage Using a Horizontal Standard Storage Overpack




Throughput: 20 DSCs placed every four weeks, or an average of 5 per week

| Legend | |
|--------|-----------------------------|
| | No Heavy Equipment |
| | 200T OTB Crane |
| | Jib Crane |
| | Self-Powered Transfer Cart |
| | Shielded Transfer Cart |
| | Horizontal Cask Transporter |
| | Stick Crane |



3 - C-UGS, Underground Storage





Throughput: 20 DPCs placed every four weeks, or an average of 5 DPCs per week.




4A, 5A - BGCa/AGVa, Below/Above Ground Vault with Integral CHB - Vertical (only) Storage







OR



Throughput: 10 DPCs placed every four weeks, or an average of 2.5 DPCs per week.







4B, 5B - BGCb/AGVb, Below/Above Ground Vault with Integral CHB - Vertical/Horizontal Storage




Throughput: 10 DPCs placed every four weeks, or 2 1/2 DPCs placed per week.







4C, 5C - BGVc/AGVc, Below/Above Ground Vault with Separate CHB - Vertical (only) Storage



Throughput: 20 DPCs placed in four weeks, or an average of 5 per week.




4D, 5D - BGVd/AGVd, Below/Above Ground Vault with Separate CHB - Vertical and Horizontal Storage



Throughput: 20 DPCs placed every four weeks, or 5 DPCs per week




1a - C-OP5a, Current Horizontal Canister Processing Operations



Throughput 20 every four weeks assuming 4 HCT machines, i.e., 5 per week average.

- No Heavy Equipment
- 200 Ton Stick Crane
- 10 Ton Stick Crane
- Horizontal Cask Transporter


1b - C-OP5b, Current Vertical Canister Processing Operations (Base Case Vertical)



Throughput 20 every four weeks assuming 2 OTB cranes and 4 VCTs. (5 DPCs per week)

- No Heavy Equipment
- 200 Ton OTB Crane
- Jib Crane
- Vertical Cask Transporter

2 - A-OPS, Automated Canister Transfer Operations




Throughput Four every week assuming only 2 VCT machines.


- No Heavy Equipment
- 200 Ton OTB Crane
- Jib Crane
- Vertical Cask Transporter

3 - R-OPS, Remote Canister Transfer Operations


Vertical DSCs - DSCs in storage casks on pad



Vertical DSCs - DSCs in storage casks on pad



S-OPS, Commercial Operations without CHB





Throughput Five every four weeks assuming one Gantry Crane and VCT.




Notes

- The rail bays need to accommodate two railcars with transportation casks on them
- The facility needs two VCTs operational at all times.
- The railbays are serviced by two OTB Cranes on the same rails.
- Streamlining the unloading process improves the utilization of the VCTs but the availability of the Railbay limits throughput.



1 - S-PAD, Current Commercial Storage on Concrete Pad (Small STADs)




Throughput: 20 DSCs placed every four weeks, or an average of 5 DSCs per week.

For small STADs, the transporter moves the overpack to the pad after every eighth STAD


Legend

- No Heavy Equipment
- 200T OTB Crane
- Jib Crane
- Self-Powered Transfer Cart
- Shielded Transfer Cart
- Vertical Cask Transporter


3 - S-UGS, Underground Storage




Throughput: 20 STADs placed every four weeks, or an average of 5 per week.




3 - BGV Below Grade Vault with Standalone CHB - Vertical (only) Storage




Throughput: 20 STADs placed every four weeks, or an average of 5 per week.



S-BGV/AGVc, Below/Above Ground Vault with Integral CHB - Vertical (only) Storage



Throughput: 10 STADs placed every four weeks, or an average of 2.5 per week. (Note: If one rail becomes inoperative, the throughput drops to 2 per week with the acceleration of the repackaging effort)



NOTES AND ASSUMPTIONS:

1. The data in these spreadsheets are approximate intended to support occupational exposure estimates only. They are neither definitive nor precise enough to support detailed operational decision.
2. The occupational exposure calculations only consider the scope of activities required to place SNF shipments into storage. Ongoing site monitoring activities are not included.
3. These crew sizes and durations are based on commercial nuclear plant ISFSI operations. Durations are based on real world experience, thus include real world worker efficiencies. Work scope is consistent with C-OPS and has been extrapolated to address the other alternates.
4. Duration fractions incorporate both the number of workers of each category performing the activity and the percentage of time that each worker is occupying the radiation zone.
5. Mechanics are responsible for bolting and unbolting connections to the various SNF containers, other than rigging.
6. Riggers are responsible for attaching and removing rigging to and from the various SNF containers. They are also responsible for observing and guiding heavy lift operations.
7. Health physicists are responsible for measuring the radiation fields and contamination associated with the SNF containers. They are also responsible for decontamination activities and for certifying equipment that enters the radiation zone for release.
8. Operators have overall responsibility for the entire facility. Their activities with respect to SNF processing include opening and closing facility doors, operating the machinery used in SNF container processing, and overseeing the acceptance of the SNF container into the facility.
9. Security personnel are responsible for keeping the facility secure while the CHB railbay doors are open and for verifying that no contraband is introduced to the facility inside of SNF containers.
10. Quality Assurance/Control personnel are responsible to assure that the chain of custody paperwork is properly filled out and for observing hold points in the process to assure proper fitment and placement of SNF containers.
11. Mechanics, riggers, and health physicists (i.e. radiation protection technicians, or radiation control technicians) are assumed to work in pairs. They typically are only near the waste package when needed. If remote monitoring is utilized, the number of health physicists can be reduced in the work area.
12. Duration fractions are only assigned to workers who are in the radiation zone adjacent to the SNF container. Other people may be in the vicinity, but they will remain outside of the radiation zone in accordance with ALARA principles.
13. Although all personnel in the vicinity are accumulating dose, the dose rate for the general area is low and accumulated doses to personnel in the vicinity are insignificant when determined on an individual DPC basis.

1 - C-PAD, Current Commercial storage on Concrete pad (Base Case)

| Vertical DPCs - DPCs in storage casks on pad | | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | | | |
|--|--|--|-----------------------|-------|-------------------|-----|-----|---|---|-----|-----------|---|---|---|---|---|--|-----|-----|
| | | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | | | |
| 0) Plan of the Day and Safety Meeting | | | 30 | | | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | | 15 | - | | | | | | | | | | | | | | | |
| b) | Safety briefing | | 10 | - | | | | | | | | | | | | | | | |
| c) | Transportation to work site | | 5 | - | | | | | | | | | | | | | | | |
| 1) Receive transport cask on railcar at Cask Handling Building | | | 145 | | | | | | | | | | | | | | | | |
| a) | Identify SNF shipment brought from yard | | 5 | - | | | | | | | | | | | | | | | |
| b) | Security team sent to railbay door | | 15 | - | | | | | | | | | | | | | | | |
| c) | Send operators to railbay door | | 15 | - | | | | | | | | | | | | | | | |
| d) | Stage work team to railbay | | 15 | - | | | | | | | | | | | | | | | |
| e) | Open railbay door | | 5 | - | | | | | | | | | | | | | | | |
| f) | Position SNF shipment in the railbay | | 15 | - | | | | | | | | | | | | | | | |
| g) | Security inspection of the SNF shipment and tug | | 15 | 3 VT | | | | | | 0.5 | | | | | | | | 5.5 | 0 |
| h) | HP survey of SNF shipment | | 15 | 3 VT | | | 0.5 | | | | | | | | | | | | |
| i) | Inspection of tamper proof Seals | | 10 | 3 VT | | | | | | 0.1 | | | | | | | | | 0.7 |
| j) | Acceptance of SNF shipment | | 5 | - | | | | | | | | | | | | | | | |
| k) | Decoupling of railcar and removal of the tug from the railbay | | 10 | - | | | | | | | | | | | | | | | |
| l) | Secure the railbay doors | | 5 | - | | | | | | | | | | | | | | | |
| m) | Security team leaves | | 5 | - | | | | | | | | | | | | | | | |
| n) | Operator leaves | | 5 | - | | | | | | | | | | | | | | | |
| o) | Completes paperwork for step #1 | | 5 | - | | | | | | | | | | | | | | | |
| 2) Remove impact limiters and place in temporary storage | | | 195 | | | | | | | | | | | | | | | | |
| a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | | 5 | - | | | | | | | | | | | | | | | |
| b) | Select and inspect rigging for impact limiters on the transport cask | | 5 | - | | | | | | | | | | | | | | | |
| c) | Rig the lifting devices to the first impact limiter | | 5 | 1A VT | | 2 | 2 | | | | | | | | | | | | |
| d) | Position man lifts and temporary scaffolding near transport cask | | 5 | 1A VT | | 2 | | | | | | | | | | | | | |
| e) | Remove and store bolts holding on the first impact limiter | | 30 | 1A VT | | 2 | | | | | | | | | | | | | |
| f) | Remove first impact limiter and place on storage stand | | 10 | 1A VT | | 1 | | | | | | | | | | | | | |
| g) | Remove rigging and reposition on second impact limiter | | 5 | 1A VT | | 1 | | | | | | | | | | | | | |
| h) | Reposition manlift and scaffolding | | 5 | 1A VT | | | | | | | | | | | | | | | |
| i) | Remove and store bolts holding on the second impact limiter | | 30 | 1A VT | | 2 | | | | | | | | | | | | | |
| j) | Remove second impact limiter and place on storage stand | | 10 | 1A VT | | 1 | | | | | | | | | | | | | |
| k) | Remove and store bolts for personnel barrier | | 30 | 3 VT | | 0.2 | | | | | | | | | | | | | |
| l) | Rig the personnel barrier | | 15 | 3 VT | | 1 | 1 | | | | | | | | | | | | |
| m) | Lift personnel barrier and move to storage location | | 10 | 3 VT | | | | | | | | | | | | | | | |
| n) | Remove tie-down straps from transport cask | | 10 | 3A VT | | 0.4 | | | | | | | | | | | | | |
| o) | Rig tie-down straps and move to storage location | | 5 | 3A VT | | 1 | | | | | | | | | | | | | |
| p) | Inspect transport cask for damage and conduct HP survey | | 15 | 3 VT | | | 2 | | | | | | | | | | | | |
| 3) Upend and lift transport cask off of railcar and place on unloading cell transfer cart | | | 120 | | | | | | | | | | | | | | | | |
| a) | Select the appropriate lifting block for the transport cask | | 5 | - | | | | | | | | | | | | | | | |
| b) | Secure lifting block to transport cask Trunnions | | 10 | 2A VT | | 2 | | | | | | | | | | | | | |
| c) | Upend transport cask | | 30 | - | | | | | | | | | | | | | | | |
| d) | Lift transport cask off railcar | | 30 | - | | | | | | | | | | | | | | | |
| e) | Reposition transport cask | | 30 | - | | | | | | | | | | | | | | | |
| f) | Place transport cask on unloading cell transfer cart | | 15 | - | | | | | | | | | | | | | | | |
| 3a) Remove railcar from railbay | | | 60 | | | | | | | | | | | | | | | | |
| a) | Open railbay door | | 5 | - | | | | | | | | | | | | | | | |
| b) | Railyard tug connects to railcar | | 10 | - | | | | | | | | | | | | | | | |
| c) | Railyard tug removes railcar from railbay | | 10 | - | | | | | | | | | | | | | | | |
| d) | Railyard tug connects to next railcar | | 15 | - | | | | | | | | | | | | | | | |
| e) | Railyard tug repositions next railcar in railbay | | 10 | - | | | | | | | | | | | | | | | |
| f) | Railyard tug leaves railbay and railbay door is closed | | 10 | - | | | | | | | | | | | | | | | |
| 4) Unbolt and remove transport cask lid using jib crane | | | 85 | | | | | | | | | | | | | | | | |
| a) | Move tools to work platform | | 5 | - | | | | | | | | | | | | | | | |
| b) | HP survey of lid Including gas sampling | | 15 | 2A VT | | | 1 | | | | | | | | | | | | |
| c) | Remove and store nuts | | 30 | 2A VT | | 1 | | | | | | | | | | | | | |
| d) | Rig the lid for lifting using the local jib crane | | 15 | 2A VT | | 1.5 | | | | | | | | | | | | | |
| e) | Lift the transport cask lid and move it to the storage stand | | 10 | - | | | | | | | | | | | | | | | |
| f) | Security inspection of the interior of the transport cask | | 10 | 2 VT | | | | | | 0.2 | | | | | | | | | 5 |
| 4a) Secure transport cask and transfer cart seismically | | | 40 | | | | | | | | | | | | | | | | |
| a) | Reposition transfer cart near seismic restraint system | | 15 | - | | | | | | | | | | | | | | | |
| b) | Secure transport cask and transfer cart | | 15 | - | | | | | | | | | | | | | | | |
| c) | QC Hold Point Inspection | | 10 | - | | | | | | | | | | | | | | | |
| 4b) Plan of the Day and Safety Meeting | | | 30 | | | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | | 15 | - | | | | | | | | | | | | | | | |
| b) | Safety briefing | | 10 | - | | | | | | | | | | | | | | | |
| c) | Transportation to work site | | 5 | - | | | | | | | | | | | | | | | |
| 5) Attach lifting lug to top of DPC | | | 70 | | | | | | | | | | | | | | | | |
| a) | Rig lifting lug on storage rack | | 15 | - | | | | | | | | | | | | | | | |
| b) | Use Jib crane to lift lifting lug into position | | 15 | 2A VT | | 0.5 | | | | | | | | | | | | | |
| c) | Bolt Lifting lug to canister | | 20 | 2 VT | | 0.5 | | | | | | | | | | | | | |
| d) | QC Hold Point Inspection | | 10 | 2 VT | | | | | | 0.1 | | | | | | | | | 2.5 |
| e) | Clear workspace and remove all tools | | 10 | - | | | | | | | | | | | | | | | |
| 6) Position transport cask transfer cart in unloading cell and close shield doors | | | 60 | | | | | | | | | | | | | | | | |
| a) | Move transport cask cart into the unloading cell | | 50 | - | | | | | | | | | | | | | | | |
| b) | Close the shield doors | | 10 | - | | | | | | | | | | | | | | | |
| 7) Stage empty storage cask on receiving cell transfer cart | | | 90 | | | | | | | | | | | | | | | | |
| a) | Prepare an empty storage cask for use | | 15 | - | | | | | | | | | | | | | | | |
| b) | Place the empty storage cask on the transfer cart using VCT | | 15 | - | | | | | | | | | | | | | | | |
| c) | Stage tools on top of the storage cask | | 10 | - | | | | | | | | | | | | | | | |
| d) | Unbolt storage cask lid | | 30 | - | | | | | | | | | | | | | | | |
| e) | Rig the cask lid to the VCT hoist | | 10 | - | | | | | | | | | | | | | | | |
| f) | Hoist lid and retain on VCT | | 10 | - | | | | | | | | | | | | | | | |
| 8) Position empty storage cask in receiving cell using motorized cart | | | 45 | | | | | | | | | | | | | | | | |
| a) | Open receiving cellshield doors | | 15 | - | | | | | | | | | | | | | | | |
| b) | Transfer empty storage cask into receiving cell using motorized cart | | 15 | - | | | | | | | | | | | | | | | |
| c) | Close the shield doors | | 10 | - | | | | | | | | | | | | | | | |
| d) | QC Hold Point Inspection | | 5 | - | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|-------------|--|--|-------------|----------|-----|---|-----|--|-----|-----|-----|-----|---|-----|-----|
| | i) | Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| | j) | Remove second impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| | k) | Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| | l) | Rig the personnel barrier | 15 | 3 VT | | 1 | 1 | | | 0 | 11 | 11 | 0 | 0 | 0 |
| | m) | Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) | Remove tie-down straps from SNF shipment | 10 | 3A VT | 0.4 | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| | o) | Rig Tie-Down straps and move to storage location | 5 | 3A VT | | 1 | | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| | p) | Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | | 2 | | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) | Stage Horizontal Cask Transporter (HCT) in truck bay | | 60 | | | | | | | | | | | | |
| | a) | Open truck bay door | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position HCT in truck bay | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close truck bay door | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Upend and lift transport cask off of railcar and downend on HCT | | 75 | | | | | | | | | | | | |
| | a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure lifting block to transport cask trunnions | 5 | 2A VT | | 2 | | | | 0 | 3.3 | 0 | 0 | 0 | 0 |
| | c) | Upend transport cask | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift transport cask off railcar | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Move transport cask to HCT | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Downend transport cask on HCT | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4a) | Remove railcar from railbay | | 60 | | | | | | | | | | | | |
| | a) | Open railbay door | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Railyard tug connects to railcar | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Railyard tug removes railcar from railbay | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Railyard tug connects to next railcar | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Railyard tug repositions next railcar in railbay | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) | Secure transport cask on HCT | | 40 | | | | | | | | | | | | |
| | a) | Position HCT near seismic restraint tie-downs | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Install seismic restraint tie-downs | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4c) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | Transfer transport cask to HSM on pad via HCT | | 120 | | | | | | | | | | | | |
| | a) | QC Hold Point Inspection | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open the truck bay door | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer the transport cask to HSM on the pad via HCT | 90 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5a) | Preparation of Horizontal Storage Module (HSM) | | 120 | | | | | | | | | | | | |
| | a) | Stage equipment near HSM | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Place and align Theodolite heads | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig crane to HSM port cover | 15 | 2CH TL | | 2 | | | | 0 | 0.8 | 0 | 0 | 0 | 0 |
| | d) | Use manlift to remove nuts on mounting studs | 15 | 1A HT L | | 2 | | | | 9.2 | 0 | 0 | 0 | 0 | 0 |
| | e) | Post radiation zone signs and barriers | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove HSM port cover and place in storage location | 20 | 1A HT L | | 1 | | | | 0 | 6.1 | 0 | 0 | 0 | 0 |
| | g) | HP survey to verify dose rates | 15 | 1A HT L | | | 1.5 | | | 0 | 0 | 6.9 | 0 | 0 | 0 |
| 6) | Remove transport cask lid | | 90 | | | | | | | | | | | | |
| | a) | Move tools to work platform | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid including gas sampling | 10 | 1A HT L | | 2 | | | | 0 | 0 | 6.1 | 0 | 0 | 0 |
| | c) | Position stick crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local stick crane | 15 | 1A HT L | | 2 | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| | e) | Remove and store nuts | 20 | 1A HT L | | 2 | | | | 12 | 0 | 0 | 0 | 0 | 0 |
| | f) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Security inspection of the interior of the transport cask | 5 | 1A HT NL | | | 0.5 | | | 0 | 0 | 0 | 0 | 6.8 | 0 |
| 7) | Dock HCT with HSM and push DPC into module | | 145 | | | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move HCT into position | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Check alignment | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock HCT to HSM | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove pushing port in base of transport cask | 15 | 5 HH | | 2 | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | f) | Engage ram and push DPC into module | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Withdraw the ram | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Back the HCT away from the module | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | QC Hold Point Inspection | 10 | 1A HT NL | | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 5.4 |
| 8) | Install seismic restraints and HSM port cover | | 90 | | | | | | | | | | | | |
| | a) | Retrieve the seismic restraints from HCT | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reach into module and install the seismic restraints | 5 | 1A HT NL | | 1 | | | | 14 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 5 | 1A HT NL | | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 2.7 |
| | d) | Pick the HSM port cover still attached to the lifting rig | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position the HSM port cover over the port in the module | 15 | 5 HH | | 1 | | | | 0 | 2.1 | 0 | 0 | 0 | 0 |
| | f) | Install the nuts on the studs and torque to spec | 15 | 5 HH | | 2 | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | g) | HP survey of area | 15 | 5 HH | | | 0.5 | | | 0 | 0 | 1.1 | 0 | 0 | 0 |
| | h) | Remove radiation zone markers and remove all materials | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | Install transport cask lid | | 70 | | | | | | | | | | | | |
| | a) | Security inspection of transport cask to verify lack of contraband | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Pick the transport cask cover from the still attached to the lifting rig | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the transport cask cover on the transport cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Install the nuts on the studs and torque to spec | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of Canister Handling Operations | | 21.2 | | | | | | | | | | | | |
| 9a) | Turnover to Operations | | 1440 | | | | | | | | | | | | |
| 10) | Return transport cask to Cask Handling Building via HCT | | 120 | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10a) | Plan of the Day and Safety Meeting | | 30 | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | Lift transport cask and transfer to maintenance | | 60 | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11a) | survey and wipedown transport cask | | 60 | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11b) | Reposition empty railcar | | 60 | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | Lift transport cask and place on railcar | | 60 | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | Install impact limiters on transport cask | | 120 | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Release railcar for shipment | | 60 | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of All Cask Handling Operations | | 54.7 | | | | | | | 80 | 47 | 51 | 0 | 11 | 8.2 |

| | | | | | | | | | | | | | | | | |
|-------------|----|--|-------------|--------|-----|-----|-----|-----|--|-----|-----|----|---|----|-----|-----|
| | a) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower shield sleeve hoist and grapple DPC lifting lug | 50 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | | Raise DPC into shield sleeve | 60 | | | | | | | | | | | | | |
| | a) | Raise DPC into shield sleeve | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Position shielded transfer sleeve cart over standardized overpack in receiving cell | 70 | | | | | | | | | | | | | |
| | a) | Position shielded transfer sleeve over standardized overpack in receiving cell | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | | Lower DPC into empty standardized overpack, release grapple, and retract hoist | 60 | | | | | | | | | | | | | |
| | a) | Lower DPC into empty standardized overpack, release grapple, and retract hoist | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Remove lifting lug from DPC | 35 | | | | | | | | | | | | | |
| | a) | HP survey | 10 | 2 V T | | | 0.2 | | | 0 | 0 | 5 | 0 | 0 | 0 | 0 |
| | b) | Stage tools on top of the standardized overpack | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove bolts and rig lifting lug | 10 | 2 V T | 0.3 | 0.2 | | | | 7.5 | 5 | 0 | 0 | 0 | 0 | 0 |
| | d) | Remove the lifting lug from the DPC using the jib crane | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Open receiving cell shield doors and transfer standardized overpack out of receiving cell | 35 | | | | | | | | | | | | | |
| | a) | HP survey | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open receiving cell shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer standardized overpack out of receiving cell using motorized cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | | Install standardized overpack lid | 60 | | | | | | | | | | | | | |
| | a) | Position VCT with standardized overpack lid at standardized overpack | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower standardized overpack lid into position | 10 | - | | | | | | | | | | | | |
| | c) | Install bolts and torque | 20 | 2A V T | 1.5 | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | 2A V T | | | | 0.1 | | 0 | 0 | 0 | 0 | 0 | 0 | 0.3 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17a) | | Secure seismic restraints | 40 | | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | | Pick up standardized overpack and transfer to pad using VCT | 120 | | | | | | | | | | | | | |
| | a) | Rig VCT to lift standardized overpack | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | b) | Drive to storage pad location | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the DPC on the pad | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | De-rig standardized overpack from VCT | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | e) | Bolt DPC to the pad | 20 | 4 V S | 1 | | | | | 37 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 26.1 | | | | | | | | | | | | | |
| 18a) | | Turnover to Operations | 1440 | | | | | | | | | | | | | |
| 19) | | Return VCT to CHB | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | | Open unloading cell shield doors and position transfer cart under jib crane | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 21) | | Install transport cask lid | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | | Lift transport cask and transfer to maintenance | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 22a) | | Reposition the railcar to the railway | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 22b) | | Survey and wipedown transport cask | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | | Lift transport cask and place on railcar | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | | Install impact limiters on transport cask | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | | Release railcar for shipment | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of All Cask Handling Operations | 61.1 | | | | | | | 126 | 60 | 51 | 0 | 11 | 2.8 | |

| Horizontal DPCs - DPCs in vertical standardized overpacks on pad | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | |
|--|---|-----------------------|--------|-------------------|---|-----|-----|---|---|-----------|-----|-----|---|-----|---|---|
| | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | |
| 0) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | | |
| | a) Identify SNF shipment brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Security team sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Send operators to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Position SNF shipment in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) Security inspection of the SNF shipment and tug | 15 | 3 V T | | | | 0.5 | | | 0 | 0 | 0 | 0 | 5.5 | 0 | 0 |
| | h) HP survey of SNF shipment | 15 | 3 V T | | | 0.5 | | | | 0 | 0 | 5.5 | 0 | 0 | 0 | 0 |
| | i) Inspection of tamper proof seals | 10 | 3 V T | | | | 0.1 | | | 0 | 0 | 0 | 0 | 0.7 | 0 | 0 |
| | j) Acceptance of SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | m) Security team leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) Operator leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| | a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Rig the lifting devices to the first impact limiter | 5 | 1A V T | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 | 0 |
| | d) Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A V T | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | e) Remove and store bolts holding on the first impact limiter | 30 | 1A V T | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Remove first impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | g) Remove rigging and reposition on second impact limiter | 5 | 1A V T | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| | h) Reposition manlift and scaffolding | 5 | 1A V T | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) Remove and store bolts holding on the second impact limiter | 30 | 1A V T | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| | j) Remove second impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | k) Remove and store bolts for personnel barrier | 30 | 3 V T | 0.2 | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) Rig the personnel barrier | 15 | 3 V T | 1 | 1 | | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| | m) Lift personnel barrier and move to storage location | 10 | 3 V T | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) Remove tie-down straps from SNF shipment | 10 | 3A V T | 0.4 | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) Rig tie-down straps and move to storage location | 5 | 3A V T | 1 | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| | p) Inspect transport cask for damage and conduct HP survey | 15 | 3 V T | | 2 | | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) | Upend and lift transport cask off of railcar and place on transfer fixture | 120 | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | | |
|-------------|----|---|------------|------------|-----|--|--|-----|--|-----|-----|-----|---|---|-----|---|
| | a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure lifting block to transport cask trunnions | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | c) | Upend transport cask | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift transport cask off railcar | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Move transport cask to transfer fixture | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Downend transport cask on transfer fixture | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 3a) | | Remove railcar from railbay | 120 | | | | | | | | | | | | | |
| | a) | Open railbay door | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Railyard tug connects to railcar | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Railyard tug removes railcar from railbay | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Railyard tug connects to next railcar | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Railyard tug repositions next railcar in railbay | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | | Stage standardized overpack on upender using VCT | 180 | | | | | | | | | | | | | |
| | a) | Move the VCT into position | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Grapple the standardized overpack | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Pick the standardized overpack | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Reposition the VCT at the upender in the transfer cell | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Place the standardized overpack on the upender | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | | Unbolt and hoist overpack lid and retain on VCT | 60 | | | | | | | | | | | | | |
| | a) | Stage tools on top of the standardized overpack | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Unbolt overpack lid | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig the overpack lid to the VCT hoist | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift lid to the storage position of the VCT | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove grapples and back the VCT out of the transfer cell | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) | | Downend standardized overpack on upender | 60 | | | | | | | | | | | | | |
| | a) | Secure standardized overpack to upender | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Hoist docking collar to top of standardized overpack and bolt in place | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Downend the standardized overpack to the horizontal position | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) | | Remove transport cask lid | 95 | | | | | | | | | | | | | |
| | a) | Move tools to work platform | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid including gas sampling | 15 | 1A H T L | 2 | | | | | 0 | 0 | 9.2 | 0 | 0 | 0 | 0 |
| | c) | Position jib crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local jib crane | 15 | 1A H T L | 2 | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove and store Nuts | 20 | 1A H T L | 2 | | | | | 12 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Security inspection of the interior of the transport cask | 5 | 1A H T N L | | | | 0.5 | | 0 | 0 | 0 | 0 | 0 | 6.8 | 0 |
| 7a) | | Secure transport cask and transfer fixture seismically | 40 | | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) | | Dock transfer sleeve on horizontal transfer cart with transport cask | 75 | | | | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move horizontal transfer cart into position | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Align transport cask with transfer sleeve | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock transfer sleeve to transport cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Install retaining straps on transport cask trunnions | 15 | 2A H T | 1.5 | | | | | 0 | 12 | 0 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | | Push DPC into transfer sleeve | 60 | | | | | | | | | | | | | |
| | a) | Remove pushing port in base of transport cask | 15 | 5 H H | 2 | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into the transfer sleeve | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) | | Decouple horizontal transfer cart from transport cask and close shield door | 20 | | | | | | | | | | | | | |
| | a) | Remove retaining straps from transfer sleeve | 10 | 2A H T | 0.2 | | | | | 0 | 1.1 | 0 | 0 | 0 | 0 | 0 |
| | b) | Undock transfer sleeve from transport cask | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | | Roll horizontal transfer cart onto turntable and rotate 180° | 30 | | | | | | | | | | | | | |
| | a) | Roll horizontal transfer cart to turntable and lock wheels | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rotate turntable 180° | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | | Roll horizontal transfer cart to upending cell and dock with standardized overpack | 45 | | | | | | | | | | | | | |
| | a) | Unlock wheels and roll horizontal transfer cart to upending cell | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Dock transfer sleeve to standardized overpack on upender | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Attach retaining straps to transfer sleeve trunnions | 15 | 2A H T | 0.5 | | | | | 0 | 4 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Push DPC from transfer sleeve into standardized overpack | 65 | | | | | | | | | | | | | |
| | a) | Plug in hydraulic power pack on horizontal transfer cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into the standardized overpack | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | | Undock horizontal transfer cart | 50 | | | | | | | | | | | | | |
| | a) | Remove retaining straps from standardized overpack | 15 | 2A H T | 0.2 | | | | | 0 | 1.6 | 0 | 0 | 0 | 0 | 0 |
| | b) | Unplug hydraulic power pack on horizontal transfer cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Undock transfer sleeve from standardized overpack | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Upend standardized overpack | 30 | | | | | | | | | | | | | |
| | a) | Close shield door to upender cell | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Upend the standardized overpack | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Set locking mechanism on upender | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Install lid on standardized overpack | 60 | | | | | | | | | | | | | |
| | a) | Open outer shield doors to upender cell | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position VCT at standardized overpack on upender | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower standardized overpack lid into place using the VCT | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Stage tools on manlift | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Install bolts and torque | 20 | 2A H T | 1.5 | | | | | 16 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Move manlift away | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16a) | | Secure transport cask and transfer fixture seismically | 40 | | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | |
|-------------|--|--|-------------|---|--|--|--|--|--|--|----|----|----|---|----|---|
| | b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | Pick up standardized overpack and transfer to pad using VCT | | 130 | | | | | | | | | | | | | |
| | a) | Rig VCT to lift standardized overpack | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open CHB Doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Back the VCT out of the receiving cell | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Drive to storage pad location | 80 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position the DPC on the pad | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of Canister Handling Operations | | 30.7 | | | | | | | | | | | | | |
| 17a) | Turnover to Operations | | 1440 | | | | | | | | | | | | | |
| 18) | Return VCT to CHB | | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | Install transport cask lid | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | Lift transport cask and transfer to maintenance | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20a) | Survey and wipedown transport cask | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20b) | Reposition empty railcar | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 21) | Lift transport cask and place on railcar | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | Install impact limiters on transport cask | | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | Release railcar for shipment | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of All Cask Handling Operations | | 54.5 | | | | | | | | 69 | 60 | 50 | 0 | 13 | 0 |

2B - C-STDb, Pad Storage Using Standard Storage Overpacks

| | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | |
|--|-----------------------|-------|-------------------|---|-----|---|---|-----|-----------|-----|-----|-----|---|-----|-----|
| | | | M | R | H | O | S | Q | M | R | H | O | S | Q | |
| 0) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | | |
| a) Identify SNF shipment brought from yard | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Security team sent to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Send operators to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Stage work team to railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Open railbay door | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Position SNF shipment in the railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 |
| h) HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 |
| i) Inspection of tamper proof Seals | 10 | 3 VT | | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| j) Acceptance of SNF shipment | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Secure the railbay doors | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| m) Security team leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Operator leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Completes paperwork for step #1 | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Select and inspect rigging for impact limiters on the transport cask | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | 2 | 2 | | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| d) Position manlifts and temporary scaffolding near transport cask | 5 | 1A VT | 2 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| f) Remove first impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | 1 | | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 |
| h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| j) Remove second impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| k) Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| l) Rig the personnel barrier | 15 | 3 VT | 1 | 1 | | | | | | 0 | 11 | 11 | 0 | 0 | 0 |
| m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Remove tie-down straps from transport cask | 10 | 3A VT | 0.4 | | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| o) Rig tie-down straps and move to storage location | 5 | 3A VT | 1 | | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | 2 | | | | | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) Upend and lift transport cask off of railcar and place on unloading cell transfer cart | 120 | | | | | | | | | | | | | | |
| a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure lifting block to transport cask Trunnions | 10 | 2A VT | 2 | | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| c) Upend transport cask | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Lift transport cask off railcar | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Reposition transport cask | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Place transport cask on unloading cell transfer cart | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 3a) Remove railcar from railbay | 60 | | | | | | | | | | | | | | |
| a) Open railbay door | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Railyard tug connects to railcar | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Railyard tug removes railcar from railbay | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Railyard tug connects to next railcar | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) Unbolt and remove transport cask lid using jib crane | 85 | | | | | | | | | | | | | | |
| a) Move tools to work platform | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) HP survey of lid Including gas sampling | 15 | 2A VT | | 1 | | | | | | 0 | 0 | 5 | 0 | 0 | 0 |
| c) Remove and store nuts | 30 | 2A VT | 1 | | | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| d) Rig the lid for lifting using the local jib crane | 15 | 2A VT | 1.5 | | | | | | | 0 | 7.5 | 0 | 0 | 0 | 0 |
| e) Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Security inspection of the interior of the transport cask | 10 | 2 VT | | | | | | 0.2 | | 0 | 0 | 0 | 0 | 5 | 0 |
| 4a) Secure transport cask and transfer cart seismically | 40 | | | | | | | | | | | | | | |
| a) Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure transport cask and transfer cart | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) Attach lifting lug to top of DPC | 70 | | | | | | | | | | | | | | |
| a) Rig lifting lug on storage rack | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Use jib crane to lift lifting lug into position | 15 | 2A VT | 0.5 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| c) Bolt lifting lug to canister | 20 | 2 VT | 0.5 | | | | | | | 25 | 0 | 0 | 0 | 0 | 0 |
| d) QC Hold Point Inspection | 10 | 2 VT | | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0 | 2.5 |
| e) Clear workspace and remove all tools | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) Position transport cask transfer cart in unloading cell and close shield doors | 60 | | | | | | | | | | | | | | |
| a) Move transport cask into the unloading cell | 50 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Close the shield doors | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) Stage empty vertical standardized overpack on receiving cell transfer cart | 90 | | | | | | | | | | | | | | |
| a) Prepare an empty standardized overpack for use | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Place the empty standardized overpack on the transfer cart using VCT | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Stage tools on top of the standardized overpack | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Unbolt standardized overpack lid | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Rig the cask lid to the VCT hoist | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Hoist lid and retain on VCT | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) Position empty standardized overpack in receiving cell using motorized cart | 45 | | | | | | | | | | | | | | |
| a) Open receiving cell shield doors | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Transfer empty standardized overpack into receiving cell using motorized cart | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Close the shield doors | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) QC Hold Point Inspection | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) Position shielded transfer sleeve cart over unloading cell | 35 | | | | | | | | | | | | | | |
| a) Inspect transfer sleeve cart | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) Lower shield sleeve hoist and grapple DPC lifting lug | 50 | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | | |
|-------------|--|--|-------------|--------|-----|-----|-----|--|-----|-----|-----|----|---|----|-----|-----|
| | a) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower shield sleeve hoist and grapple DPC lifting lug | 50 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | Raise DPC into shield sleeve | | 60 | | | | | | | | | | | | | |
| | a) | Raise DPC into shield sleeve | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | Position shielded transfer sleeve cart over standardized overpack in receiving cell | | 70 | | | | | | | | | | | | | |
| | a) | Position shielded transfer sleeve over standardized overpack in receiving cell | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Lower DPC into empty standardized overpack, release grapple, and retract hoist | | 60 | | | | | | | | | | | | | |
| | a) | Lower DPC into empty standardized overpack, release grapple, and retract hoist | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | Remove lifting lug from DPC | | 35 | | | | | | | | | | | | | |
| | a) | HP survey | 10 | 2 V T | | | 0.2 | | | 0 | 0 | 5 | 0 | 0 | 0 | 0 |
| | b) | Stage tools on top of the standardized overpack | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove bolts and rig lifting lug | 10 | 2 V T | 0.3 | 0.2 | | | | 7.5 | 5 | 0 | 0 | 0 | 0 | 0 |
| | d) | Remove the lifting lug from the DPC using the jib crane | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | Open receiving cell shield doors and transfer standardized overpack out of receiving cell | | 35 | | | | | | | | | | | | | |
| | a) | HP survey | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open receiving cell shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer standardized overpack out of receiving cell using motorized cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | Install standardized overpack lid | | 60 | | | | | | | | | | | | | |
| | a) | Position VCT with standardized overpack lid at standardized overpack | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower standardized overpack lid into position | 10 | - | | | | | | | | | | | | |
| | c) | Install bolts and torque | 20 | 2A V T | 1.5 | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | 2A V T | | | | | 0.1 | 0 | 0 | 0 | 0 | 0 | 0 | 0.3 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17a) | Secure seismic restraints | | 40 | | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17b) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | Pick up standardized overpack and transfer to pad using VCT | | 120 | | | | | | | | | | | | | |
| | a) | Rig VCT to lift standardized overpack | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | b) | Drive to storage pad location | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the DPC on the pad | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | De-rig standardized overpack from VCT | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | e) | Bolt DPC to the pad | 20 | 4 V S | 1 | | | | | 37 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 26.1 | | | | | | | | | | | | | |
| 18a) | Turnover to Operations | | 1440 | | | | | | | | | | | | | |
| 19) | Return VCT to CHB | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | Open unloading cell shield doors and position transfer cart under jib crane | | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 21) | Install transport cask lid | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | Lift transport cask and transfer to maintenance | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 22a) | Reposition the railcar to the railway | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 22b) | Survey and wipedown transport cask | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | Lift transport cask and place on railcar | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | Install impact limiters on transport cask | | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | Release railcar for shipment | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of All Cask Handling Operations | 61.1 | | | | | | | 126 | 60 | 51 | 0 | 11 | 2.8 | |

| Horizontal DPCs - DPCs in Horizontal Standardized Overpacks on pad | Duration (Minutes) | Dose | Duration Fraction | | | | | | | Task Dose | | | | | | |
|---|--------------------|--------|-------------------|---|---|-----|-----|---|---|-----------|-----|-----|---|---|-----|---|
| | | | M | R | H | O | S | Q | M | R | H | O | S | Q | | |
| 0) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | | | |
| a) Identify SNF shipment brought from yard | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Security team sent to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Send operators to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Stage work team to railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Open railbay door | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Position SNF shipment in the railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| g) Security inspection of the SNF shipment and tug | 15 | 3 V T | | | | | 0.5 | | | 0 | 0 | 0 | 0 | 0 | 3.7 | 0 |
| h) HP survey of SNF shipment | 15 | 3 V T | | | | 0.5 | | | | 0 | 0 | 1.8 | 0 | 0 | 0 | 0 |
| i) Inspection of tamper proof seals | 10 | 3 V T | | | | | 0.1 | | | 0 | 0 | 0 | 0 | 0 | 0.7 | 0 |
| j) Acceptance of SNF shipment | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Secure the railbay doors | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| m) Security team leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Operator leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Completes paperwork for step #1 | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | | |
| a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig the lifting devices to the first impact limiter | 5 | 1A V T | 2 | 2 | | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 | 0 |
| d) Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A V T | 2 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| e) Remove and store bolts holding on the first impact limiter | 30 | 1A V T | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Remove first impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| g) Remove rigging and reposition on second impact limiter | 5 | 1A V T | 1 | | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| h) Reposition manlift and scaffolding | 5 | 1A V T | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| i) Remove and store bolts holding on the second impact limiter | 30 | 1A V T | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| j) Remove second impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| k) Remove and store bolts for personnel barrier | 30 | 3 V T | 0.2 | | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Rig the personnel barrier | 15 | 3 V T | 1 | 1 | | | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| m) Lift personnel barrier and move to storage location | 10 | 3 V T | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Remove tie-down straps from SNF shipment | 10 | 3A V T | 0.4 | | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Rig Tie-Down straps and move to storage location | 5 | 3A V T | 1 | | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| p) Inspect transport cask for damage and conduct HP survey | 15 | 3 V T | | 2 | | | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) Stage Horizontal Cask Transporter (HCT) in truck bay | 60 | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|-------------|--|--|-------------|-----------|-----|--|-----|-----|--|-----|-----|-----|---|-----|-----|
| | a) | Open truck bay door | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position HCT in truck bay | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close truck bay door | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Upend and lift transport cask off of railcar and downend on HCT | | 75 | | | | | | | | | | | | |
| | a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure lifting block to transport cask trunnions | 5 | 2A V T | 2 | | | | | 0 | 3.3 | 0 | 0 | 0 | 0 |
| | c) | Upend transport cask | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift transport cask off railcar | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Move transport cask to HCT | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Downend transport cask on HCT | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4a) | Remove railcar from railbay | | 60 | | | | | | | | | | | | |
| | a) | Open railbay door | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Railyard tug connects to railcar | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Railyard tug removes railcar from railbay | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Railyard tug connects to next railcar | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Railyard tug repositions next railcar in railbay | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) | Secure transport cask on HCT | | 40 | | | | | | | | | | | | |
| | a) | Position HCT near seismic restraint tie-downs | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Install seismic restraint tie-downs | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4c) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | Transfer transport cask to HSM on pad via HCT | | 120 | | | | | | | | | | | | |
| | a) | QC Hold Point Inspection | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open the truck bay door | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer the transport cask to HSM on the pad via HCT | 90 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5a) | Preparation of Horizontal Storage Module (HSM) | | 120 | | | | | | | | | | | | |
| | a) | Stage equipment near HSM | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Place and align Theodolite heads | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig crane to HSM port cover | 15 | 2C H T L | 2 | | | | | 0 | 0.8 | 0 | 0 | 0 | 0 |
| | d) | Use manlift to remove nuts on mounting studs | 15 | 1A H T L | 2 | | | | | 9.2 | 0 | 0 | 0 | 0 | 0 |
| | e) | Post radiation zone signs and barriers | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove HSM port cover and place in storage location | 20 | 1A H T L | 1 | | | | | 0 | 6.1 | 0 | 0 | 0 | 0 |
| | g) | HP survey to verify dose rates | 15 | 1A H T L | 1.5 | | | | | 0 | 0 | 6.9 | 0 | 0 | 0 |
| 6) | Remove transport cask lid | | 90 | | | | | | | | | | | | |
| | a) | Move tools to work platform | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid including gas sampling | 10 | 1A H T L | 2 | | | | | 0 | 0 | 6.1 | 0 | 0 | 0 |
| | c) | Position stick crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local stick crane | 15 | 1A H T L | 2 | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| | e) | Remove and store nuts | 20 | 1A H T L | 2 | | | | | 12 | 0 | 0 | 0 | 0 | 0 |
| | f) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Security inspection of the interior of the transport cask | 5 | 1A H T NL | | | | 0.5 | | 0 | 0 | 0 | 0 | 6.8 | 0 |
| 7) | Dock HCT with HSM and push DPC into module | | 145 | | | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move HCT into position | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Check alignment | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock HCT to HSM | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove pushing port in base of transport cask | 15 | 5 H H | 2 | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | f) | Engage ram and push DPC into module | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Withdraw the ram | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Back the HCT away from the module | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | QC Hold Point Inspection | 10 | 1A H T NL | | | | 0.2 | | 0 | 0 | 0 | 0 | 0 | 5.4 |
| 8) | Install seismic restraints and HSM port cover | | 90 | | | | | | | | | | | | |
| | a) | Retrieve the seismic restraints from HCT | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reach into module and install the seismic restraints | 5 | 1A H T NL | 1 | | | | | 14 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 5 | 1A H T NL | | | | 0.2 | | 0 | 0 | 0 | 0 | 0 | 2.7 |
| | d) | Pick the HSM port cover still attached to the lifting rig | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position the HSM port cover over the port in the module | 15 | 5 H H | 1 | | | | | 0 | 2.1 | 0 | 0 | 0 | 0 |
| | f) | Install the nuts on the studs and torque to spec | 15 | 5 H H | 2 | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | g) | HP survey of area | 15 | 5 H H | | | 0.5 | | | 0 | 0 | 1.1 | 0 | 0 | 0 |
| | h) | Remove radiation zone markers and remove all materials | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | Install transport cask lid | | 70 | | | | | | | | | | | | |
| | a) | Security inspection of transport cask to verify lack of contraband | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Pick the transport cask cover from the still attached to the lifting rig | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the transport cask cover on the transport cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Install the nuts on the studs and torque to spec | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of Canister Handling Operations | | 21.2 | | | | | | | | | | | | |
| 9a) | Turnover to Operations | | 1440 | | | | | | | | | | | | |
| 10) | Return transport cask to Cask Handling Building via HCT | | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10a) | Plan of the Day and Safety Meeting | | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | Lift transport cask and transfer to maintenance | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11a) | survey and wipedown transport cask | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11b) | Reposition empty railcar | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | Lift transport cask and place on railcar | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | Install impact limiters on transport cask | | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Release railcar for shipment | | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of All Cask Handling Operations | | 54.7 | | | | | | | 80 | 47 | 51 | 0 | 11 | 8.2 |

2C - C-STDC, pad Storage using a Horizontal Standard Storage overpack

| Vertical DPCs - DPCs in horizontal standardized overpacks on pad | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | | | |
|--|---|-----------------------|-------|-------------------|---|-----|---|---|---|-----------|---|-----|-----|-----|---|-----|-----|---|
| | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | | | |
| 0) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Safety briefing | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Transportation to work site | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | | | | |
| | a) Identify SNF shipment brought from yard | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Security team sent to railbay door | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Send operators to railbay door | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Stage work team to railbay | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Open railbay door | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Position SNF shipment in the railbay | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 | 0 |
| | h) HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 | 0 |
| | i) Inspection of tamper proof seals | 10 | 3 VT | | | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 | 0 |
| | j) Acceptance of SNF shipment | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) Secure the railbay doors | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | m) Security team leaves | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) Operator leaves | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) Completes paperwork for step #1 | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | | | |
| | a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | | 2 | 2 | | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 | 0 |
| | d) Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A VT | | 2 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Remove first impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | 1 | | | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| | h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| | j) Remove second impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | k) Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) Rig the personnel barrier | 15 | 3 VT | 1 | 1 | | | | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| | m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) Remove tie-down straps from SNF shipment | 10 | 3A VT | 0.4 | | | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) Rig tie-down straps and move to storage location | 5 | 3A VT | 1 | | | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| | p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | 2 | | | | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) | Upend and lift transport cask off of railcar and place on unloading cell transfer cart | 120 | | | | | | | | | | | | | | | | |
| | a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Secure lifting block to transport cask trunnions | 10 | 2A VT | 2 | | | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | c) Upend transport cask | 30 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Lift transport cask off railcar | 30 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Reposition transport cask | 30 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Place transport cask on unloading cell transfer cart | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Remove railcar from railbay | 60 | | | | | | | | | | | | | | | | |
| | a) Open railbay door | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Railyard tug connects to railcar | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Railyard tug removes railcar from railbay | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Railyard tug connects to next railcar | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | Unbolt and remove transport cask lid using jib crane | 85 | | | | | | | | | | | | | | | | |
| | a) Move tools to work platform | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) HP survey of lid Including leak detection | 15 | 2A VT | | 1 | | | | | | | 0 | 0 | 5 | 0 | 0 | 0 | 0 |
| | c) Remove and store nuts | 30 | 2A VT | 1 | | | | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Rig the lid for lifting using the local jib crane | 15 | 2A VT | 1.5 | | | | | | | | 0 | 7.5 | 0 | 0 | 0 | 0 | 0 |
| | e) Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Security inspection of the interior of the transport cask | 10 | 2 VT | | | | | | | 0.2 | | 0 | 0 | 0 | 0 | 5 | 0 | 0 |
| 6) | Receive adaptor frame from overpack fabrication yard | 60 | | | | | | | | | | | | | | | | |
| 7) | Unpack and inspect adaptor frame | 60 | | | | | | | | | | | | | | | | |
| 8) | Pick transfer cask from HCT and stage on CHB crane bay floor near upender cell | 60 | | | | | | | | | | | | | | | | |
| 9) | Remove transfer cask lid with jib crane | 60 | | | | | | | | | | | | | | | | |
| 10) | Install adaptor frame into transfer cask with cask handling bridge crane | 60 | | | | | | | | | | | | | | | | |
| 11) | Hoist transfer cask with adaptor frame and downend onto horizontal transport cart | 30 | | | | | | | | | | | | | | | | |
| 12) | Strap docking collar to end of transfer cask | 15 | | | | | | | | | | | | | | | | |
| 12a) | Secure transport cask and transfer cart seismically | 40 | | | | | | | | | | | | | | | | |
| | a) Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Secure transport cask and transfer cart | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) QC Hold Point Inspection | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12b) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Safety briefing | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Transportation to work site | 5 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | Attach lifting lug to top of DPC | 70 | | | | | | | | | | | | | | | | |
| | a) Rig lifting lug on storage rack | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Use jib crane to lift lifting lug into position | 15 | 2A VT | 0.5 | | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | c) Bolt lifting lug to DPC | 20 | 2 VT | 0.5 | | | | | | | | 25 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) QC Hold Point Inspection | 10 | 2 VT | | | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0 | 2.5 | 0 |
| | e) Clear workspace and remove all tools | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Position transport cask transfer cart in unloading cell and close shield doors | 60 | | | | | | | | | | | | | | | | |
| | a) Move transport cask transfer cart into the unloading cell | 50 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Close the shield doors | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | Position shielded transfer sleeve cart over unloading cell | 35 | | | | | | | | | | | | | | | | |
| | a) Inspect transfer sleeve cart | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) QC Hold Point Inspection | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | Lower shield sleeve hoist and grapple DPC lifting lug | 60 | | | | | | | | | | | | | | | | |
| | a) HP survey | 10 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Lower shield sleeve hoist and grapple DPC lifting lug | 50 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | Raise DPC into shield sleeve | 85 | | | | | | | | | | | | | | | | |
| | a) Raise DPC into shield Sleeve | 60 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) HP survey | 15 | - | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | |
|--|---|---|-------------|----------|-----|-----|--|--|-----|-----|-----|-----|-----|---|-----|-----|
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | Position shielded transfer sleeve cart over intermediate transfer cask in upender cell | | 70 | | | | | | | | | | | | | |
| | a) | Position shielded transfer sleeve cart over intermediate transfer cask on upender | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | Lower DPC into intermediate transfer cask, release grapple, and retract hoist | | 70 | | | | | | | | | | | | | |
| | a) | Lower DPC into intermediate transfer cask, release grapple, and retract hoist | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | Remove lifting lug from DPC and bolt grapple ring to top of DPC | | 65 | | | | | | | | | | | | | |
| | a) | HP survey | 10 | 2 VT | | 0.2 | | | | | 0 | 0 | 5 | 0 | 0 | 0 |
| | b) | Stage tools on top of the intermediate transfer cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove bolts and rig lifting lug for hoisting | 10 | 2 VT | 0.3 | 0.2 | | | | | 7.5 | 5 | 0 | 0 | 0 | 0 |
| | d) | Remove the lifting lug from the DPC using the jib crane | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Hoist grapple ring lug to top of DPC | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Bolt grapple ring lug to top of DPC | 20 | 2 VT | 0.5 | | | | | | 25 | 0 | 0 | 0 | 0 | 0 |
| 21) | Downend intermediate transfer cask | | 5 | | | | | | | | | | | | | |
| | a) | Downend intermediate transfer cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | Dock upender to horizontal transfer cart | | 45 | | | | | | | | | | | | | |
| | a) | Align and dock horizontal transfer cart with upender | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Install retaining straps | 15 | 2A VT | | 1 | | | | | 0 | 5 | 0 | 0 | 0 | 0 |
| | c) | Extend ram and engage grapple ring on canister | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | Transfer DPC into transfer cask on horizontal transfer cart | | 55 | | | | | | | | | | | | | |
| | a) | Pull DPC into transfer cask on horizontal cart | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Disengage ram from grapple ring and fully retract | 15 | 1C VC | | 0.2 | | | | | 5.9 | 0 | 0 | 0 | 0 | 0 |
| | c) | Install port cover in base of transfer cask | 10 | 1B VC | | 0.2 | | | | | 4.5 | 0 | 0 | 0 | 0 | 0 |
| 23) | Undock upender from horizontal transfer cart | | 15 | | | | | | | | | | | | | |
| | a) | Unstrap docking collar from transfer cask on horizontal transfer cart | 10 | 4 V X | | 0.5 | | | | | 0 | 15 | 0 | 0 | 0 | 0 |
| | b) | Undock horizontal transfer cart from upender | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | Install transfer cask lid | | 45 | | | | | | | | | | | | | |
| | a) | Hoist and position transfer cask lid using the jib crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Install bolts and torque | 20 | 5 HH | | 2 | | | | | 5.7 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | 5 HH | | | | | | | 0.5 | 0 | 0 | 0 | 0 | 0.7 |
| 24a) | Secure seismic restraints | | 40 | | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 24b) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | Hoist transfer cask from horizontal transfer cart and place on HCT | | 70 | | | | | | | | | | | | | |
| | a) | Rig transfer cask for lifting | 10 | 4 HT | | 2 | | | | | 0 | 11 | 0 | 0 | 0 | 0 |
| | b) | Hoist transfer cask with cask handling bridge crane and place on HCT | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 26) | Move transfer cask to the pad using the HCT | | 70 | | | | | | | | | | | | | |
| | a) | Open CHB truck bay doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move transfer cask to pad using HCT | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 27) | Preparation of Horizontal Storage Module (HSM) | | 135 | | | | | | | | | | | | | |
| | a) | Stage equipment near HSM | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Place and align Theodolite heads | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig stick crane to HSM port cover | 20 | 2C HTL | | 2 | | | | | 0 | 1 | 0 | 0 | 0 | 0 |
| | d) | Use manlift to remove nuts on mounting studs | 20 | 1A HTL | | 2 | | | | | 12 | 0 | 0 | 0 | 0 | 0 |
| | e) | Post radiation zone signs and barriers | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove HSM port cover and place in storage location | 20 | 1A HTL | | 1 | | | | | 0 | 6.1 | 0 | 0 | 0 | 0 |
| | g) | HP survey to verify dose rates | 15 | 1A HTL | | 1.5 | | | | | 0 | 0 | 6.9 | 0 | 0 | 0 |
| 28) | Remove transfer cask lid | | 95 | | | | | | | | | | | | | |
| | a) | Move tools to work platform | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid | 15 | 1A HTL | | 1 | | | | | 0 | 0 | 4.6 | 0 | 0 | 0 |
| | c) | Position stick crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local stick crane | 15 | 1A HTL | | 1 | | | | | 0 | 4.6 | 0 | 0 | 0 | 0 |
| | e) | Remove and store nuts | 20 | 1A HTL | | 2 | | | | | 12 | 0 | 0 | 0 | 0 | 0 |
| | f) | Lift the transfer cask lid and move it to the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Security inspection of the interior of the transfer cask | 5 | 1A HT NL | | | | | 0.5 | | 0 | 0 | 0 | 0 | 6.8 | 0 |
| 29) | Dock HCT with HSM and push DPC into module | | 145 | | | | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move HCT into position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Check alignment | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock HCT to HSM | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove pushing port in base of transport cask | 15 | 5 HH | | 2 | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | f) | Engage ram and push DPC into module | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Withdraw the ram | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Back the HCT away from the module | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | QC Hold Point Inspection | 10 | 1A HT NL | | | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 5.4 |
| 30) | Install seismic restraints and HSM port cover | | 90 | | | | | | | | | | | | | |
| | a) | Retrieve the seismic restraints from HCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reach into module and install the seismic restraints | 5 | 1A HT NL | | 1 | | | | | 14 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 5 | 1A HT NL | | | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 2.7 |
| | d) | Pick the HSM port cover still attached to the lifting rig | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position the HSM port cover over the port in the module | 15 | 5 HH | | 1 | | | | | 0 | 2.1 | 0 | 0 | 0 | 0 |
| | f) | Install the nuts on the studs and torque to spec | 15 | 5 HH | | 2 | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | g) | HP survey of area | 15 | 5 HH | | 0.5 | | | | | 0 | 0 | 1.1 | 0 | 0 | 0 |
| | h) | Remove radiation zone markers and remove all materials | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 31) | Install transfer cask lid | | 70 | | | | | | | | | | | | | |
| | a) | Security inspection of transport cask to verify lack of contraband | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Pick the transport cask cover from the still attached to the lifting rig | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the transport cask cover on the transport cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Install the nuts on the studs and torque to spec | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Hours of Canister Handling Operations | | | 36.5 | | | | | | | | | | | | | |
| 31a) | Turnover to Operations | | 1440 | | | | | | | | | | | | | |
| 32) | Return transfer cask to Cask Handling Building via HCT | | 120 | | | | | | | | | | | | | |
| 33) | Open unloading cell shield doors and position transport cask under jib crane | | 30 | | | | | | | | | | | | | |
| 34) | Install transport cask lid | | 60 | | | | | | | | | | | | | |
| 35) | Lift transport cask and transfer to maintenance | | 60 | | | | | | | | | | | | | |
| 36) | Survey and wipedown transport cask | | 60 | | | | | | | | | | | | | |
| 37) | Lift transport cask and place on railcar | | 60 | | | | | | | | | | | | | |
| 38) | Install impact limiters on transport cask | | 120 | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|-----|--|-------------|---|--|--|--|--|--|--|-----|----|----|---|----|----|
| 39) | Release railcar for shipment | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of All Cask Handling Operations | 70.0 | | | | | | | | 167 | 91 | 64 | 0 | 18 | 11 |

| Horizontal DPCs - DPCs in Horizontal Standardized Overpacks on pad | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | |
|---|-----------------------|----------|-------------------|---|-----|---|-----|---|-----------|-----|-----|---|-----|---|---|
| | | | M | R | H | O | S | Q | M | R | H | O | S | Q | |
| 0) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | | |
| a) Identify SNF shipment brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Security team sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Send operators to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Position SNF shipment in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | 0 | 0 | 0 | 0 | 3.7 | 0 | 0 |
| h) HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | 0 | 0 | 1.8 | 0 | 0 | 0 | 0 |
| i) Inspection of tamper proof seals | 10 | 3 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 | 0 |
| j) Acceptance of SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| m) Security team leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Operator leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | | 2 | 2 | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 | 0 |
| d) Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A VT | | 2 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Remove first impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | | 1 | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| j) Remove second impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| k) Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Rig the personnel barrier | 15 | 3 VT | | 1 | 1 | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Remove tie-down straps from SNF shipment | 10 | 3A VT | 0.4 | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Rig Tie-Down straps and move to storage location | 5 | 3A VT | | 1 | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | | 2 | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) Stage Horizontal Cask Transporter (HCT) in truck bay | 60 | | | | | | | | | | | | | | |
| a) Open truck bay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Position HCT in truck bay | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Close truck bay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) Upend and lift transport cask off of railcar and downend on HCT | 75 | | | | | | | | | | | | | | |
| a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure lifting block to transport cask trunnions | 5 | 2A VT | | 2 | | | | | 0 | 3.3 | 0 | 0 | 0 | 0 | 0 |
| c) Upend transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Lift transport cask off railcar | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Move transport cask to HCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Downend transport cask on HCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4a) Remove railcar from railbay | 60 | | | | | | | | | | | | | | |
| a) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Railyard tug connects to railcar | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Railyard tug removes railcar from railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Railyard tug connects to next railcar | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) Secure transport cask on HCT | 40 | | | | | | | | | | | | | | |
| a) Position HCT near seismic restraint tie-downs | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Install seismic restraint tie-downs | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4c) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) Transfer transport cask to HSM on pad via HCT | 120 | | | | | | | | | | | | | | |
| a) QC Hold Point Inspection | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Open the truck bay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transfer the transport cask to HSM on the pad via HCT | 90 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5a) Preparation of Horizontal Storage Module (HSM) | 120 | | | | | | | | | | | | | | |
| a) Stage equipment near HSM | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Place and align Theodolite heads | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig crane to HSM port cover | 15 | 2C HTL | | 2 | | | | | 0 | 0.8 | 0 | 0 | 0 | 0 | 0 |
| d) Use manlift to remove nuts on mounting studs | 15 | 1A HTL | 2 | | | | | | 9.2 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Post radiation zone signs and barriers | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Remove HSM port cover and place in storage location | 20 | 1A HTL | | 1 | | | | | 0 | 6.1 | 0 | 0 | 0 | 0 | 0 |
| g) HP survey to verify dose rates | 15 | 1A HTL | | | 1.5 | | | | 0 | 0 | 6.9 | 0 | 0 | 0 | 0 |
| 6) Remove transport cask lid | 90 | | | | | | | | | | | | | | |
| a) Move tools to work platform | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) HP survey of lid including gas sampling | 10 | 1A HTL | | | 2 | | | | 0 | 0 | 6.1 | 0 | 0 | 0 | 0 |
| c) Position stick crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Rig the lid for lifting using the local stick crane | 15 | 1A HTL | | 2 | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 | 0 |
| e) Remove and store nuts | 20 | 1A HTL | 2 | | | | | | 12 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| g) Security inspection of the interior of the transport cask | 5 | 1A HT NL | | | | | 0.5 | | 0 | 0 | 0 | 0 | 6.8 | 0 | 0 |
| 7) Dock HCT with HSM and push DPC into module | 145 | | | | | | | | | | | | | | |
| a) Position spotters | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Move HCT into position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Check alignment | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Dock HCT to HSM | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Remove pushing port in base of transport cask | 15 | 5 HH | 2 | | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | |
|-------------|--|--|-------------|-----------|---|-----|--|--|--|-----|-----|-----|-----|---|----|-----|
| | f) | Engage ram and push DPC into module | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Withdraw the ram | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Back the HCT away from the module | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | QC Hold Point Inspection | 10 | 1A H T NL | | | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 5.4 |
| 8) | Install seismic restraints and HSM port cover | | 90 | | | | | | | | | | | | | |
| | a) | Retrieve the seismic restraints from HCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reach into module and install the seismic restraints | 5 | 1A H T NL | 1 | | | | | | 14 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 5 | 1A H T NL | | | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 2.7 |
| | d) | Pick the HSM port cover still attached to the lifting rig | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position the HSM port cover over the port in the module | 15 | 5 H H | 1 | | | | | | 0 | 2.1 | 0 | 0 | 0 | 0 |
| | f) | Install the nuts on the studs and torque to spec | 15 | 5 H H | 2 | | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | g) | HP survey of area | 15 | 5 H H | | 0.5 | | | | | 0 | 0 | 1.1 | 0 | 0 | 0 |
| | h) | Remove radiation zone markers and remove all materials | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | Install transport cask lid | | 70 | | | | | | | | | | | | | |
| | a) | Security inspection of transport cask to verify lack of contraband | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Pick the transport cask cover from the still attached to the lifting rig | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the transport cask cover on the transport cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Install the nuts on the studs and torque to spec | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of Canister Handling Operations | | 21.2 | | | | | | | | | | | | | |
| 9a) | Turnover to Operations | | 1440 | | | | | | | | | | | | | |
| 10) | Return transport cask to Cask Handling Building via HCT | | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10a) | Plan of the Day and Safety Meeting | | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | Lift transport cask and transfer to maintenance | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11a) | survey and wipedown transport cask | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11b) | Reposition empty railcar | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | Lift transport cask and place on railcar | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | Install impact limiters on transport cask | | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Release railcar for shipment | | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of All Cask Handling Operations | | 54.7 | | | | | | | | 80 | 47 | 51 | 0 | 11 | 8.2 |

| | | | | | | | | | | | | | | | | |
|-------------|----|---|-------------|----------|-----|-----|--|--|-----|-----|-----|-----|---|---|---|-----|
| | a) | Lower shield sleeve hoist and grapple DPC Lifting Lug | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | | Raise DPC into shield sleeve | 75 | | | | | | | | | | | | | |
| | a) | Raise DPC into shield sleeve | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | | Position shielded transfer sleeve cart over transfer cask in receiving cell | 35 | | | | | | | | | | | | | |
| | a) | Position shielded transfer sleeve cart over transfer cask in receiving cell | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Lower DPC into empty transfer cask, release grapple, and retract hoist | 45 | | | | | | | | | | | | | |
| | a) | Lower DPC into empty transfer cask, release grapple and retract hoist | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 15 | 1D V C | | 0.2 | | | | 0 | 0 | 3.1 | 0 | 0 | 0 | 0 |
| 14) | | Remove lifting lug from DPC | 35 | | | | | | | | | | | | | |
| | a) | HP survey | 10 | 2 V T | | 0.2 | | | | 0 | 0 | 5 | 0 | 0 | 0 | 0 |
| | b) | Stage tools on top of the transfer cask | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove bolts and rig lifting lug | 10 | 2 V T | 0.3 | 0.2 | | | | 7.5 | 5 | 0 | 0 | 0 | 0 | 0 |
| | d) | Remove the lifting lug from the DPC | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 14a) | | Secure the DPC and the transfer cask seismically | 40 | | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 14b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Pick up transfer cask and transfer to underground storage cell using VCT | 30 | | | | | | | | | | | | | |
| | a) | HP survey | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open receiving cell shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer transfer cask out of receiving cell using motorized cart | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Install transfer cask lid | 60 | | | | | | | | | | | | | |
| | a) | Position VCT with transfer cask lid at transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower transfer cask lid into position | 10 | - | | | | | | | | | | | | |
| | c) | Install bolts and torque | 20 | 2A V T | 1.5 | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | 2A V T | | | | | 0.1 | 0 | 0 | 0 | 0 | 0 | 0 | 0.3 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | | Pick up transfer cask and transfer to pad using VCT | 80 | | | | | | | | | | | | | |
| | a) | Rig VCT to lift transfer cask | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | d) | Drive to storage pad location | 70 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | | Install mating device on Cavity Enclosure Container (CEC) | 230 | | | | | | | | | | | | | |
| | a) | Position crane and rig to the underground storage cell cover | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move cover to the storage stand | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transport the docking collar and mating device to the site. | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Inspect CEC | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Rig the docking collar to the crane | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Position the docking collar on CEC | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Attach docking collar to the CEC | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Rig the mating device to the crane | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | Position the mating device on CEC | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | j) | Attach mating device to the CEC | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | k) | Test mechanism | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | | Dock transfer cask to underground storage cell and remove rigging | 25 | | | | | | | | | | | | | |
| | a) | Position VCT at vault | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Dock transfer cask with underground storage cell | 10 | 4 V S | 2 | | | | | 37 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove rigging | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 21) | | Rig DPC to VCT for vertical lift | 45 | | | | | | | | | | | | | |
| | a) | HP survey | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Bolt lifting cleats to DPC | 15 | 1B V C | 1 | | | | | 34 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Attach rigging to DPC | 15 | 1C V C | 0.5 | | | | | 0 | 15 | 0 | 0 | 0 | 0 | 0 |
| 22) | | Remove transfer cask base using docking collar | 30 | | | | | | | | | | | | | |
| | a) | Remove transfer cask base | 30 | 4 V S | 0.3 | | | | | 17 | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | | Lower DPC into underground storage cell | 70 | | | | | | | | | | | | | |
| | a) | Lower DPC into empty storage cell | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | | Access top of DPC (by ladder inside transfer cask) and remove rigging | 60 | | | | | | | | | | | | | |
| | a) | HP survey | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Stage tools on top of the DPC inside of the transfer cask | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove rigging from DPC | 15 | 1B V C | 0.3 | | | | | 0 | 10 | 0 | 0 | 0 | 0 | 0 |
| | d) | Remove lifting cleats | 15 | 1B V C | 1 | | | | | 34 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | | Withdraw DPC rigging and replace transfer cask base | 30 | | | | | | | | | | | | | |
| | a) | Withdraw DPC rigging | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Replace transfer cask base | 15 | 2C H T L | 2 | | | | | 0.8 | 0 | 0 | 0 | 0 | 0 | 0 |
| 26) | | Re-Rig transfer cask to VCT and undock from underground storage cell | 45 | | | | | | | | | | | | | |
| | a) | Re-rig the transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Undock from underground storage cell | 15 | 2C H T L | 2 | | | | | 0.8 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Back the VCT away from the underground storage cell | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 27) | | Install underground storage cell cover | 85 | | | | | | | | | | | | | |
| | a) | Rig the storage cell cover | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Pick with crane and place on underground storage cell | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Bolt the cover down | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Remove rigging and reposition crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | HP survey | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 35.1 | | | | | | | | | | | | | |
| 27a) | | Turnover to Operations | 1440 | | | | | | | | | | | | | |
| 27b) | | Plan of the Day and Safety Meeting | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 28) | | Return VCT to CHB | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 29) | | Open unloading cell shield doors and position transport cask under jib crane | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 27) | | Install transport cask lid | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 30) | | Lift transport cask and transfer to maintenance | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 30a) | | Survey and wipedown transport cask | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 30b) | | Reposition empty railcar | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 31) | | Lift transport cask and place on railcar | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 32) | | Install impact limiters on transport cask | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | |
|-----|--|-------------|---|--|--|--|--|--|-----|----|----|---|----|-----|---|
| 33) | Release railcar for shipment | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of All Cask Handling Operations | 70.6 | | | | | | | 176 | 68 | 54 | 0 | 11 | 2.8 | |

| Horizontal DPCs - DPCs in lifting frames in underground silos | | Duration (Min) | Dose | Du | | | | | | Tas | | | | | |
|---|---|----------------|---------|-----|---|-----|---|-----|---|-----|-----|-----|---|-----|---|
| | | | | M | R | H | O | S | Q | M | R | H | O | S | Q |
| 0) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | |
| | a) Identify SNF shipment brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Security team sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Send operators to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Position SNF shipment in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 |
| | h) HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | 0 | 0 | 5.5 | 0 | 0 | 0 |
| | i) Inspection of tamper proof seals | 10 | 3 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| | j) Acceptance of SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | m) Security team leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) Operator leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | |
| | a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| | d) Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A VT | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| | e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| | f) Remove first impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| | g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 |
| | h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| | j) Remove second impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| | k) Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| | l) Rig the personnel barrier | 15 | 3 VT | 1 | 1 | | | | | 0 | 11 | 11 | 0 | 0 | 0 |
| | m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) Remove tie-down straps from SNF shipment | 10 | 3A VT | 0.4 | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| | o) Rig tie-down straps and move to storage location | 5 | 3A VT | 1 | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| | p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | 2 | | | | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) | Upend and lift transport cask off of railcar and place on transfer fixture | 120 | | | | | | | | | | | | | |
| | a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Secure lifting block to transport cask trunnions | 10 | 2A VT | 2 | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | c) Upend transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Lift transport cask off railcar | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Move transport cask to transfer fixture | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Downend transport cask on transfer fixture | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 3a) | Remove railcar from railbay | 60 | | | | | | | | | | | | | |
| | a) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Railyard tug connects to railcar | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Railyard tug removes railcar from railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Railyard tug connects to next railcar | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Stage transfer cask on upender using VCT | 50 | | | | | | | | | | | | | |
| | a) Move the VCT into position | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Grapple the transfer cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Pick the transfer cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Reposition the VCT at the upender in the transfer cell | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Place the transfer cask on the upender | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | Unbolt and hoist transfer cask lid and retain on VCT | 70 | | | | | | | | | | | | | |
| | a) Stage tools on top of the transfer cask | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Unbolt transfer cask lid | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Rig lid to the VCT hoist | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Lift lid to the storage position of the VCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Remove grapples and back VCT out of the transfer cell | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5a) | Secure transport cask and transfer cart seismically | 40 | | | | | | | | | | | | | |
| | a) Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Secure transport cask and transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5b) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5c) | Load lifting frame into transfer cask using jib crane | 85 | | | | | | | | | | | | | |
| | a) Move lifting frame into position using a transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Rig the lifting frame onto the jib crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Hoist the lifting frame and load it into the transfer cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Lift docking collar and place on top of transfer cask | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Strap docking collar to top of transfer cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Remove the rigging and secure the jib crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) | Downend transfer cask on upender | 30 | | | | | | | | | | | | | |
| | a) Secure transfer cask to upender | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Downend the transfer cask to the horizontal position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) | Remove transport cask lid | 100 | | | | | | | | | | | | | |
| | a) Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) HP survey of lid including gas sampling | 15 | 1A HT L | | 2 | | | | | 0 | 0 | 9.2 | 0 | 0 | 0 |
| | c) Position jib crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Rig the lid for lifting using the local jib crane | 15 | 1A HT L | 2 | | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| | e) Remove and store nuts | 30 | 1A HT L | 2 | | | | | | 18 | 0 | 0 | 0 | 0 | 0 |
| | f) Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | |
|-------------|--|--|------------|-----------|-----|--|-----|-----|-----|---|---|-----|---|
| | g) | Security inspection of the interior of the transport cask | 10 | 1A H T NL | | | 0.2 | 0 | 0 | 0 | 0 | 5.4 | 0 |
| 7a) | Secure transport cask and Transfer Fixture seismically | | 40 | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7b) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) | Dock transfer sleeve on horizontal transfer cart with transport cask | | 75 | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move transfer sleeve into position | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Align transport cask with transfer sleeve | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock transfer sleeve to transport cask | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Install retaining straps on transport cask trunnions | 15 | 2A H T | 1.5 | | | 0 | 12 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | Push DPC into lift frame inside transfer cask | | 75 | | | | | | | | | | |
| | a) | Remove pushing port in base of transport cask | 15 | 5 H H | 2 | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into transfer sleeve | 30 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 20 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) | Undock horizontal transfer cart from transport cask | | 30 | | | | | | | | | | |
| | a) | Remove retaining straps from transfer sleeve | 10 | 2A H T | 0.2 | | | 0 | 1.1 | 0 | 0 | 0 | 0 |
| | b) | Pull horizontal transfer cart back | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close shield door on transfer sleeve | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | Roll horizontal transfer cart onto turntable and rotate 180° | | 30 | | | | | | | | | | |
| | a) | Roll transfer cart to turntable lock wheels | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rotate turntable 180° | 20 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | Roll horizontal transfer cart to upending cell and dock with transfer cask on upender | | 45 | | | | | | | | | | |
| | a) | Unlock wheels and roll transfer cart to upending cell | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Dock transfer sleeve to transfer cask on upender | 20 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Attach retaining straps to transfer sleeve trunnions | 15 | 2A H T | 0.5 | | | 0 | 4 | 0 | 0 | 0 | 0 |
| 13) | Push DPC from transfer sleeve into lift frame in transfer cask | | 65 | | | | | | | | | | |
| | a) | Plug in hydraulic power pack on transfer cart | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into the lift frame in the transfer cask | 30 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Undock horizontal transfer cart | | 50 | | | | | | | | | | |
| | a) | Remove retaining straps from transfer cask | 15 | 2A H T | 0.2 | | | 0 | 1.6 | 0 | 0 | 0 | 0 |
| | b) | Unplug hydraulic power pack on transfer cart | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Undock transfer cart and remove | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | Upend transfer cask | | 30 | | | | | | | | | | |
| | a) | Close shield door to upender cell | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Upend the transfer cask | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Set locking mechanism on upender | 5 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | Install lid on transfer cask | | 85 | | | | | | | | | | |
| | a) | Open outer shield doors to upender cell | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position VCT at transfer cask on upender | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower transfer cask lid into place using the VCT | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Stage tools on manlift | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Install bolts and torque | 20 | 2A H T | 1.5 | | | 16 | 0 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Move manlift away | 5 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16a) | Secure transport cask and Transfer Fixture seismically | | 40 | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16b) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | Pick up transfer cask and transfer to underground storage cell using VCT | | 90 | | | | | | | | | | |
| | a) | Rig VCT to lift transfer cask | 10 | 2A V T | 2 | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | b) | Open CHB doors | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Back the VCT out of the receiving cell | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Drive to storage pad location | 60 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | Install mating device on Cavity Enclosure Container (CEC) | | 230 | | | | | | | | | | |
| | a) | Position crane and rig to the underground storage cell cover | 30 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move cover to the storage stand | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transport the docking collar and mating device to the site. | 30 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Inspect CEC | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Rig the docking collar to the crane | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Position the docking collar on CEC | 30 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Attach docking collar to the CEC | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Rig the mating device to the crane | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | Position the mating device on CEC | 30 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | j) | Attach mating device to the CEC | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | k) | Test mechanism | 20 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | Dock transfer cask to underground storage cell and remove rigging | | 25 | | | | | | | | | | |
| | a) | Position VCT at underground storage cell | 5 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Dock transfer cask with underground storage cell | 10 | 4 V S | 2 | | | 37 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove rigging | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | Rig DPC to VCT for vertical lift and hoist | | 45 | | | | | | | | | | |
| | a) | HP survey | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Bolt lifting cleats to DPC | 15 | 1B V C | 1 | | | 34 | 0 | 0 | 0 | 0 | 0 |
| | c) | Attach rigging to DPC | 15 | 1C V C | 0.5 | | | 0 | 15 | 0 | 0 | 0 | 0 |
| 21) | Remove transfer cask base using docking collar | | 30 | | | | | | | | | | |
| | a) | Remove transfer cask base | 30 | 4 V S | 0.3 | | | 17 | 0 | 0 | 0 | 0 | 0 |
| 22) | Lower DPC into underground storage cell | | 70 | | | | | | | | | | |
| | a) | Lower DPC into empty storage cell | 60 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | QC Hold Point Inspection | 10 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | Access top of DPC (by ladder inside transfer cask) and remove rigging | | 60 | | | | | | | | | | |
| | a) | HP survey | 15 | - | | | | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | |
|-------------|----|---|-------------|----------|-----|--|--|--|--|-----|----|----|---|----|---|
| | b) | Stage tools on top of the DPC inside of the transfer cask | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove rigging from DPC | 15 | 1B V C | 0.3 | | | | | 0 | 10 | 0 | 0 | 0 | 0 |
| | d) | Remove lifting cleats | 15 | 1B V C | 1 | | | | | 34 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | | Withdraw DPC rigging and replace transfer cask base | 30 | | | | | | | | | | | | |
| | a) | Withdraw DPC rigging | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Replace transfer cask base | 15 | 2C H T L | 2 | | | | | 0.8 | 0 | 0 | 0 | 0 | 0 |
| 25) | | Re-Rig transfer cask to VCT and undock from underground storage cell | 45 | | | | | | | | | | | | |
| | a) | Re Rig the transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Undock from underground storage cell | 15 | 2C H T L | 2 | | | | | 0.8 | 0 | 0 | 0 | 0 | 0 |
| | c) | Back the VCT away from the underground storage cell | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 26) | | Install underground storage cell cover | 80 | | | | | | | | | | | | |
| | a) | Rig the storage cell cover | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Pick with crane and place on underground storage cell | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Bolt the cover Down | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Remove rigging and reposition crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | HP survey | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 38.1 | | | | | | | | | | | | |
| 27a) | | Turnover to Operations | 1440 | | | | | | | | | | | | |
| 27b) | | Plan of the Day and Safety Meeting | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 28) | | Return VCT to CHB | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 29) | | Open unloading cell shield doors and position transport cask under jib crane | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 30) | | Install transport cask lid | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 31) | | Lift transport cask and transfer to maintenance | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 31a) | | Reposition empty railcar | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 31b) | | Survey and wipedown transport cask | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 32) | | Lift transport cask and place on railcar | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 33) | | Install impact limiters on transport cask | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 34) | | Release railcar for shipment | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of All Cask Handling Operations | 73.6 | | | | | | | 197 | 91 | 50 | 0 | 12 | 0 |

4A, 5A - C-BGVA/AGVa, Below/Above Ground Vault with Integral CHB - Vertical (only) Storage

| DPCs stored vertically in vault floor | | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | | |
|---------------------------------------|---|--|-----------------------|-------|-------------------|---|-----|-----|-----|---|-----------|-----|-----|-----|---|-----|-----|---|
| | | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | | |
| 0) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at vault | | 145 | | | | | | | | | | | | | | | |
| | a) | Identify SNF shipment brought from yard | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Security team sent to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Send operators to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Stage work team to railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Open railbay door | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Position SNF shipment in the railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | | 0 | 0 | 0 | 0 | 5.5 | 0 | 0 |
| | h) | HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 | 0 |
| | i) | Inspection of tamper proof Seals | 10 | 3 VT | | | | | 0.1 | | | 0 | 0 | 0 | 0 | 0.7 | 0 | 0 |
| | j) | Acceptance of SNF shipment | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | k) | Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) | Secure the railbay doors | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | m) | Security team leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) | Operator leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) | Completes paperwork for step #1 | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | | 195 | | | | | | | | | | | | | | | |
| | a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Select and inspect rigging for impact limiters on the transport cask | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig the lifting devices to the first impact limiter | 5 | 1A VT | 2 | 2 | | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 | 0 |
| | d) | Position man lifts and temporary scaffolding near transport cask | 5 | 1A VT | 2 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove first impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | g) | Remove rigging and reposition on second impact limiter | 5 | 1A VT | 1 | | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| | h) | Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| | j) | Remove second impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | k) | Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) | Rig the personnel barrier | 15 | 3 VT | 1 | 1 | | | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| | m) | Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) | Remove tie-down straps from transport cask | 10 | 3A VT | 0.4 | | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) | Rig tie-down straps and move to storage location | 5 | 3A VT | 1 | | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| | p) | Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | 2 | | | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) | Upend and lift transport cask off of railcar and place on unloading cell transfer cart | | 120 | | | | | | | | | | | | | | | |
| | a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure lifting block to transport cask trunnions | 10 | 2A VT | 2 | | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | c) | Upend transport cask | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift transport cask off railcar | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Reposition transport cask | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Place transport cask on unloading cell transfer cart | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Unbolt and remove transport cask lid using jib crane | | 85 | | | | | | | | | | | | | | | |
| | a) | Move tools to work platform | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid including gas sampling | 15 | 2A VT | | 1 | | | | | | 0 | 0 | 5 | 0 | 0 | 0 | 0 |
| | c) | Remove and store nuts | 30 | 2A VT | 1 | | | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local jib crane | 15 | 2A VT | 1.5 | | | | | | | 0 | 7.5 | 0 | 0 | 0 | 0 | 0 |
| | e) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Security inspection of the interior of the transport cask | 10 | 2 VT | | | | 0.2 | | | | 0 | 0 | 0 | 0 | 5 | 0 | 0 |
| 4a) | Secure transport cask and transfer cart seismically | | 40 | | | | | | | | | | | | | | | |
| | a) | Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure transport cask and transfer cart | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | Attach lifting lug to top of DPC | | 70 | | | | | | | | | | | | | | | |
| | a) | Rig lifting lug on storage rack | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Use jib crane to lift lifting lug into position | 15 | 2A VT | 0.5 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | c) | Bolt lifting lug to canister | 20 | 2 VT | 0.5 | | | | | | | 25 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | 2 VT | | | | | 0.1 | | | 0 | 0 | 0 | 0 | 0 | 2.5 | 0 |
| | e) | Clear workspace and remove all tools | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) | Position transport cask transfer cart in unloading cell and close shield doors | | 60 | | | | | | | | | | | | | | | |
| | a) | Move transport cask cart into the unloading cell | 50 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Close the shield doors | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) | Position shielded transfer sleeve on bridge crane above transfer cell | | 30 | | | | | | | | | | | | | | | |
| | a) | Inspect shielded transfer sleeve | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) | Lower hoist, grapple lifting lug, and raise DPC into shield sleeve | | 100 | | | | | | | | | | | | | | | |
| | a) | Lower shield sleeve hoist and grapple DPC lifting lug | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Raise DPC into shield sleeve | 60 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | HP survey | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | Transfer DPC to vault storage location | | 120 | | | | | | | | | | | | | | | |
| | a) | Transfer DPC to vault storage location | 120 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) | Remove shield plug above vault storage location | | 60 | | | | | | | | | | | | | | | |
| | a) | Position crane over storage location in vault | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rig the shield plug | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lift shield plug and place on storage stand | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | Lower DPC into storage position on vault floor | | 70 | | | | | | | | | | | | | | | |
| | a) | Align DPC over storage position | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower DPC into vault | 45 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | Replace shield plug above vault storage location | | 85 | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | | |
|--|---|-------------|---|--|--|--|--|--|--|--|----|----|----|---|----|-----|
| a) | Rig the shield plug to the crane | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Reposition the shield plug | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Lower the shield plug into the operating floor recess | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Secure the shield plug and remove rigging | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | HP survey | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Hours of Canister Handling Operations | | 20.7 | | | | | | | | | | | | | | |
| 12a) | Turnover to Operations | 1440 | | | | | | | | | | | | | | |
| 13) | Return crane to operating floor | 60 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Remove transport cask from transfer cell | 60 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | Install transport cask lid | 60 | | | | | | | | | | | | | | |
| 16) | Lift transport cask and transfer to maintenance | 60 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16a) | Survey and wipedown transport cask | 60 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | Lift transport cask, place on railcar, and downend | 60 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17a) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| 18) | Install impact limiters on transport cask | 120 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | Release railcar for shipment | 60 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Hours of All Cask Handling Operations | | 54.2 | | | | | | | | | 72 | 42 | 46 | 0 | 11 | 2.5 |

| DPCs in lift frames stored vertically in vault floor | | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | |
|--|---|------------|-----------------------|------|-------------------|-----|---|-----|---|---|-----------|-----|-----|---|-----|---|
| | | | | | M | R | H | O | S | Q | M | R | H | O | S | Q |
| 0) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Safety briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at vault | 145 | | | | | | | | | | | | | | |
| a) | Identify SNF shipment brought from yard | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Security team sent to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Send operators to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Stage work team to railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Open railbay door | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Position SNF shipment in the railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) | Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | | 0 | 0 | 0 | 0 | 5.5 | 0 |
| h) | HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 |
| i) | Inspection of tamper proof seals | 10 | 3 VT | | | | | 0.1 | | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| j) | Acceptance of SNF shipment | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| k) | Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| l) | Secure the railbay doors | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| m) | Security team leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) | Operator leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| o) | Completes paperwork for step #1 | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Rig the lifting devices to the first impact limiter | 5 | 1A VT | | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| d) | Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A VT | | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| e) | Remove and store bolts holding on the first impact limiter | 30 | 1A VT | | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| f) | Remove first impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| g) | Remove rigging and reposition on second impact limiter | 5 | 1A VT | | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 |
| h) | Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| i) | Remove and store bolts holding on the second impact limiter | 30 | 1A VT | | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| j) | Remove second impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| k) | Remove and store bolts for personnel barrier | 30 | 3 VT | | 0.2 | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| l) | Rig the personnel barrier | 15 | 3 VT | | 1 | 1 | | | | | 0 | 11 | 11 | 0 | 0 | 0 |
| m) | Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) | Remove tie-down straps from SNF shipment | 10 | 3A VT | | 0.4 | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| o) | Rig tie-down straps and move to storage location | 5 | 3A VT | | 1 | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| p) | Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | | 2 | | | | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) | Upend and lift transport cask off of railcar and place on transfer fixture | 120 | | | | | | | | | | | | | | |
| a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Secure lifting block to transport cask trunnions | 10 | 2A VT | | 2 | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| c) | Upend transport cask | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Lift transport cask off railcar | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Move transport cask to transfer fixture | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Downend transport cask on transfer fixture | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Remove transport cask lid | 80 | | | | | | | | | | | | | | |
| a) | Move tools to work platform | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | HP survey of lid including gas sampling | 15 | 1A HT L | | | 2 | | | | | 0 | 0 | 9.2 | 0 | 0 | 0 |
| d) | Rig the lid for lifting using the local jib crane | 15 | 1A HT L | | 2 | | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| e) | Remove and store nuts | 20 | 1A HT L | | 2 | | | | | | 12 | 0 | 0 | 0 | 0 | 0 |
| f) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) | Security inspection of the interior of the transport cask | 5 | 1A HT NL | | | | | 0.2 | | | 0 | 0 | 0 | 0 | 2.7 | 0 |
| 4a) | Secure transport cask and transfer cart seismically | 40 | | | | | | | | | | | | | | |
| a) | Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Secure transport cask and transfer cart | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Safety briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | Load lift frame into upender using jib crane | 85 | | | | | | | | | | | | | | |
| a) | Move lifting frame into position using a transfer cart | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Rig the lifting frame onto the jib crane | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Hoist the lifting frame and load it into the transfer sleeve on the upender | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Lift docking collar and place on top of transfer sleeve | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Strap docking collar to top of transfer sleeve | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Remove the rigging and secure the jib crane | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) | Downend transfer sleeve with lift frame and dock with transport cask | 45 | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | | |
|-------------|----|---|-------------|-------|-----|--|--|--|--|--|-----|-----|----|---|---|---|
| | a) | Secure transfer cask to upender | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Downend the transfer sleeve to the horizontal position | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) | | Dock transfer sleeve on horizontal transfer cart with transport cask | 75 | | | | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move transfer sleeve into position | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Align transport cask with transfer sleeve | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock transfer sleeve to transport cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Install retaining straps on transport cask trunnions | 15 | 2A HT | 1.5 | | | | | | 0 | 12 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) | | Push DPC into transfer sleeve | 75 | | | | | | | | | | | | | |
| | a) | Remove pushing port in base of transport cask | 15 | 5 H H | 2 | | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into transfer sleeve | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | | Undock horizontal transfer cart from transport cask and close shield door | 30 | | | | | | | | | | | | | |
| | a) | Remove retaining straps from transfer sleeve | 10 | 2A HT | 0.2 | | | | | | 0 | 1.1 | 0 | 0 | 0 | 0 |
| | b) | Pull horizontal transfer cart back | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close shield door on transfer sleeve | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) | | Roll horizontal transfer cart onto turntable and rotate 180° | 30 | | | | | | | | | | | | | |
| | a) | Roll transfer cart to turntable Lock wheels | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rotate turntable 180° | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | | Roll horizontal transfer cart to upending cell and dock transfer cart with upender | 40 | | | | | | | | | | | | | |
| | a) | Unlock wheels and roll transfer cart to upending cell | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock transfer cart with upender | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Strap docking collar to transfer sleeve on transfer cart | 10 | 2A HT | 2 | | | | | | 0 | 11 | 0 | 0 | 0 | 0 |
| 12) | | Push DPC into lift frame inside transfer cask | 65 | | | | | | | | | | | | | |
| | a) | plug in hydraulic power pack on transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into the lift frame in the upender transfer sleeve | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Undock transport cask | 50 | | | | | | | | | | | | | |
| | a) | Remove retaining straps from transfer sleeve on upender | 15 | 2A HT | 0.2 | | | | | | 0 | 1.6 | 0 | 0 | 0 | 0 |
| | b) | Unplug hydraulic power pack on transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Undock transfer cart and remove | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | | Upend transfer sleeve with lift frame | 30 | | | | | | | | | | | | | |
| | a) | Close shield door to upender cell | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Upend the transfer sleeve | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Set locking mechanism on upender | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Position shielded transfer sleeve above transfer cell | 70 | | | | | | | | | | | | | |
| | a) | Inspect shielded transfer sleeve | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Secure in position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15a) | | Secure shielded transfer sleeve and DPC seismically | 40 | | | | | | | | | | | | | |
| | a) | Reposition seismic restraint system | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure shielded transfer sleeve | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Lower hoist, grapple lifting lug, and raise DPC into shield sleeve | 90 | | | | | | | | | | | | | |
| | a) | Lower shield sleeve hoist and grapple lift frame | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Raise DPC into shield sleeve | 45 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close shield sleeve lower doors | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | | Transfer DPC to vault storage location | 120 | | | | | | | | | | | | | |
| | a) | Transfer DPC to vault storage location | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | | Remove shield plug above vault storage location | 105 | | | | | | | | | | | | | |
| | a) | Stage tools in storage vault location | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position crane in vault | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift shield plug and place on storage stand | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Disconnect rigging and return crane to cask handling area | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | | Lower DPC and lift frame into storage position on vault floor | 85 | | | | | | | | | | | | | |
| | a) | Align DPC over storage position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower DPC into vault | 45 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | | Replace shield plug above vault storage location | 85 | | | | | | | | | | | | | |
| | a) | Rig the shield plug to the crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reposition the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower the shield plug into the vault | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Secure the shield plug and remove rigging | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 29.8 | | | | | | | | | | | | | |
| 20a) | | Turnover to Operations | 1440 | | | | | | | | | | | | | |
| 21) | | Return crane to Operating Floor | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | | Install transport cask lid | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | | Lift transport cask and transfer to maintenance | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 23a) | | Survey and wipedown transport cask | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | | Lift transport cask and place on railcar | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | | Install impact limiters on transport cask | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 26) | | Release railcar for shipment | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of All Cask Handling Operations | 61.8 | | | | | | | | 53 | 66 | 50 | 0 | 9 | 0 |

4B, 5B - C-BGVb/AGVb, Below/Above Ground Vault with Integral CHB - Vertical and Horizontal Storage

| DPCs stored vertically in vault floor | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | |
|--|-----------------------|-------|-------------------|-----|-----|---|-----|-----|-----------|-----|-----|---|-----|-----|
| | | | M | R | H | O | S | Q | M | R | H | O | S | Q |
| 0) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) Receive transport cask on railcar at vault | 145 | | | | | | | | | | | | | |
| a) Identify SNF shipment brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Security team sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Send operators to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Position SNF shipment in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 |
| h) HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | 0 | 0 | 5.5 | 0 | 0 | 0 |
| i) Inspection of tamper proof Seals | 10 | 3 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| j) Acceptance of SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| m) Security team leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Operator leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | |
| a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Select and inspect rigging for impact limiters on the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | | 2 | 2 | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| d) Position manlifts and temporary scaffolding near transport cask | 5 | 1A VT | | 2 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Remove first impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | 1 | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| j) Remove second impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| k) Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Rig the personnel barrier | 15 | 3 VT | 1 | 1 | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Remove tie-down straps from transport cask | 10 | 3A VT | 0.4 | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Rig tie-down straps and move to storage location | 5 | 3A VT | 1 | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | 2 | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) Upend and lift transport cask off of railcar and place on unloading cell transfer cart | 120 | | | | | | | | | | | | | |
| a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure lifting block to transport cask trunnions | 10 | 2A VT | | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| c) Upend transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Lift transport cask off railcar | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Reposition transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Place transport cask on unloading cell transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) Unbolt and remove transport cask lid using jib crane | 85 | | | | | | | | | | | | | |
| a) Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) HP survey of lid including gas sampling | 15 | 2A VT | | | 1 | | | | 0 | 0 | 5 | 0 | 0 | 0 |
| c) Remove and store nuts | 30 | 2A VT | 1 | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Rig the lid for lifting using the local jib crane | 15 | 2A VT | | 1.5 | | | | | 0 | 7.5 | 0 | 0 | 0 | 0 |
| e) Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Security inspection of the interior of the transport cask | 10 | 2 VT | | | | | 0.2 | | 0 | 0 | 0 | 0 | 5 | 0 |
| 4a) Secure transport cask and transfer cart seismically | 40 | | | | | | | | | | | | | |
| a) Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure transport cask and transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) Attach lifting lug to top of DPC | 70 | | | | | | | | | | | | | |
| a) Rig lifting lug on storage rack | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Use jib crane to lift lifting lug into position | 15 | 2A VT | | 0.5 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| c) Bolt lifting lug to canister | 20 | 2 VT | 0.5 | | | | | 25 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) QC Hold Point Inspection | 10 | 2 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0 | 2.5 |
| e) Clear workspace and remove all tools | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) Position transport cask transfer cart in unloading cell and close shield doors | 60 | | | | | | | | | | | | | |
| a) Move transport cask cart into the unloading cell | 50 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Close the shield doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) Position shielded transfer sleeve on bridge crane above transfer cell | 30 | | | | | | | | | | | | | |
| a) Inspect shielded transfer sleeve | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) Lower hoist, grapple lifting lug, and raise DPC into shield sleeve | 100 | | | | | | | | | | | | | |
| a) Lower shield sleeve hoist and grapple DPC lifting lug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Raise DPC into shield sleeve | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) Transfer DPC to vault storage location | 120 | | | | | | | | | | | | | |
| a) Transfer DPC to vault storage location | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) Remove shield plug above vault storage location | 60 | | | | | | | | | | | | | |
| a) Position crane over storage location in vault | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Rig the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Lift shield plug and place on storage stand | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) Lower DPC into storage position on vault floor | 70 | | | | | | | | | | | | | |
| a) Align DPC over storage position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Lower DPC into vault | 45 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) Replace shield plug above vault storage location | 85 | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|--|---|-------------|---|--|--|--|--|--|--|----|----|----|---|----|-----|
| a) | Rig the shield plug to the crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Reposition the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Lower the shield plug into the operating floor recess | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Secure the shield plug and remove rigging | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Hours of Canister Handling Operations | | 20.7 | | | | | | | | | | | | | |
| 12a) | Turnover to Operations | 1440 | | | | | | | | | | | | | |
| 13) | Return crane to operating floor | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Remove transport cask from transfer cell | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | Install transport cask lid | 60 | | | | | | | | | | | | | |
| 16) | Lift transport cask and transfer to maintenance | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16a) | survey and wipedown transport cask | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | Lift transport cask, place on railcar, and downend | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17a) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| 18) | Install impact limiters on transport cask | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | Release railcar for shipment | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Hours of All Cask Handling Operations | | 54.2 | | | | | | | | 72 | 42 | 46 | 0 | 11 | 2.5 |

| DPCs in lift frames stored horizontal in concrete pedestals in vault | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | |
|--|--------------------|------------|-------------------|---|-----|---|-----|---|-----------|-----|-----|-----|---|-----|-----|
| | | | M | R | H | O | S | Q | M | R | H | O | S | Q | |
| 0) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) Receive transport cask on railcar at vault | 145 | | | | | | | | | | | | | | |
| a) Identify SNF shipment brought from yard | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Security team sent to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Send operators to railbay door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Stage work team to railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Open railbay door | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Position SNF shipment in the railbay | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | | 0 | 0 | 0 | 0 | 5.5 | 0 |
| h) HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 |
| i) Inspection of tamper proof seals | 10 | 3 VT | | | | | 0.1 | | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| j) Acceptance of SNF shipment | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Secure the railbay doors | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| m) Security team leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Operator leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Completes paperwork for step #1 | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| d) Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A VT | | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| f) Remove first impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 |
| h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| j) Remove second impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| k) Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| l) Rig the personnel barrier | 15 | 3 VT | | 1 | 1 | | | | | 0 | 11 | 11 | 0 | 0 | 0 |
| m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Remove tie-down straps from SNF shipment | 10 | 3A VT | 0.4 | | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| o) Rig tie-down straps and move to storage location | 5 | 3A VT | | 1 | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | | 2 | | | | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) Upend and lift transport cask off of railcar and place on transfer fixture | 120 | | | | | | | | | | | | | | |
| a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure lifting block to transport cask trunnions | 10 | 2A VT | | 2 | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| c) Upend transport cask | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Lift transport cask off railcar | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Move transport cask to transfer fixture | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Downend transport cask on transfer fixture | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) Remove transport cask lid | 80 | | | | | | | | | | | | | | |
| a) Move tools to work platform | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) HP survey of lid including gas sampling | 15 | 1A H T L | | | 2 | | | | | 0 | 0 | 9.2 | 0 | 0 | 0 |
| d) Rig the lid for lifting using the local jib crane | 15 | 1A H T L | | 2 | | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| e) Remove and store nuts | 20 | 1A H T L | 2 | | | | | | | 12 | 0 | 0 | 0 | 0 | 0 |
| f) Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) Security inspection of the interior of the transport cask | 5 | 1A H T N L | | | | | 0.2 | | | 0 | 0 | 0 | 0 | 2.7 | 0 |
| 5) Dock transport cask with port for transfer cart inside horizontal canister handling area | 70 | | | | | | | | | | | | | | |
| a) Position spotters | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Check alignment | 20 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Dock transport cask with port for transfer cart inside horizontal vault | 30 | 2A H T | 0.2 | | | | | | | 3.2 | 0 | 0 | 0 | 0 | 0 |
| d) QC Hold Point Inspection | 10 | 2C H T L | | | | | | 1 | | 0 | 0 | 0 | 0 | 0 | 0.3 |
| 6) Open port and push DPC through onto vault horizontal transfer cart | 80 | | | | | | | | | | | | | | |
| a) Remove pushing port in base of transport cask | 15 | 5 H H | 2 | | | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| b) Open vault port door | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Engage ram and push DPC onto vault horizontal transfer cart | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Withdraw the ram | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) QC Hold Point Inspection | 10 | 2C H T N L | | | | | | 1 | | 0 | 0 | 0 | 0 | 0 | 1.2 |
| 7) Close vault port door | 45 | | | | | | | | | | | | | | |
| a) HP survey | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Close vault port door | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) Transfer DPC to horizontal vault storage location | 135 | | | | | | | | | | | | | | |
| a) Open vault inner shield door | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Transfer DPC to vault storage location | 120 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) Lower transfer cart carriage to place DPC onto horizontal storage rack | 35 | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | | |
|------|----|--|-------------|---|--|--|--|--|--|--|----|----|----|---|-----|-----|
| | a) | Check alignment | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower transfer cart carriage | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 15.6 | | | | | | | | | | | | | |
| 9) | | Turnover to Operations | 1440 | | | | | | | | | | | | | |
| 10) | | Return transfer cart to Transfer Port and Realign | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | | Undock transport cask | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | | Install transport cask lid | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Lift transport cask and transfer to maintenance | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13a) | | Survey and wipedown transport cask | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13b) | | Reposition empty railcar | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | | Lift transport cask and place on railcar | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Install impact limiters on transport cask | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Release railcar for shipment | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of All Cask Handling Operations | 49.1 | | | | | | | | 56 | 38 | 42 | 0 | 2.7 | 1.4 |

4C, 5C - C-BGVc/AGVc, Below/Above Ground vault with Separate CHB - Vertical (only) storage

| Vertical DPCs stored vertically in vault floor | | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | | | |
|--|---|--|-----------------------|-------|-------------------|-----|-----|---|-----|---|-----------|---|---|---|---|-----|-----|-----|-----|
| | | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | | | |
| 0) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | | | | | | | | | |
| | b) | Safety briefing | 10 | - | | | | | | | | | | | | | | | |
| | c) | Transportation to work site | 5 | - | | | | | | | | | | | | | | | |
| 1) | Receive transport cask on railcar at Cask Handling Building | | 145 | | | | | | | | | | | | | | | | |
| | a) | Identify SNF shipment brought from yard | 5 | - | | | | | | | | | | | | | | | |
| | b) | Security team sent to railbay door | 15 | - | | | | | | | | | | | | | | | |
| | c) | Send operators to railbay door | 15 | - | | | | | | | | | | | | | | | |
| | d) | Stage work team to railbay | 15 | - | | | | | | | | | | | | | | | |
| | e) | Open railbay door | 5 | - | | | | | | | | | | | | | | | |
| | f) | Position SNF shipment in the railbay | 15 | - | | | | | | | | | | | | | | | |
| | g) | Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | | | | | | | 5.5 | | |
| | h) | HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | | | | | | 5.5 | | | |
| | i) | Inspection of tamper proof Seals | 10 | 3 VT | | | | | 0.1 | | | | | | | | | 0.7 | |
| | j) | Acceptance of SNF shipment | 5 | - | | | | | | | | | | | | | | | |
| | k) | Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | | | | | | | | |
| | l) | Secure the railbay doors | 5 | - | | | | | | | | | | | | | | | |
| | m) | Security team leaves | 5 | - | | | | | | | | | | | | | | | |
| | n) | Operator leaves | 5 | - | | | | | | | | | | | | | | | |
| | o) | Completes paperwork for step #1 | 5 | - | | | | | | | | | | | | | | | |
| 2) | Remove impact limiters and place in temporary storage | | 195 | | | | | | | | | | | | | | | | |
| | a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | | | | | | | | |
| | b) | Select and inspect rigging for impact limiters on the transport cask | 5 | - | | | | | | | | | | | | | | | |
| | c) | Rig the lifting devices to the first impact limiter | 5 | 1A VT | | 2 | 2 | | | | | | | | | | | | |
| | d) | Position man lifts and temporary scaffolding near transport cask | 5 | 1A VT | | 2 | | | | | | | | | | | | | |
| | e) | Remove and store bolts holding on the first impact limiter | 30 | 1A VT | | 2 | | | | | | | | | | | | | |
| | f) | Remove first impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | | | | | | | | | |
| | g) | Remove rigging and reposition on second impact limiter | 5 | 1A VT | | 1 | | | | | | | | | | | | | |
| | h) | Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | | | | | | | | | |
| | i) | Remove and store bolts holding on the second impact limiter | 30 | 1A VT | | 2 | | | | | | | | | | | | | |
| | j) | Remove second impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | | | | | | | | | |
| | k) | Remove and store bolts for personnel barrier | 30 | 3 VT | | 0.2 | | | | | | | | | | | | | |
| | l) | Rig the personnel barrier | 15 | 3 VT | | 1 | 1 | | | | | | | | | | | | |
| | m) | Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | | | | | | | | |
| | n) | Remove tie-down straps from transport cask | 10 | 3A VT | | 0.4 | | | | | | | | | | | | | |
| | o) | Rig tie-down straps and move to storage location | 5 | 3A VT | | 1 | | | | | | | | | | | | | |
| | p) | Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | | 2 | | | | | | | | | | | | |
| 3) | Upend and lift transport cask off of railcar and place on unloading cell transfer cart | | 120 | | | | | | | | | | | | | | | | |
| | a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | | | | | | | | | |
| | b) | Secure lifting block to transport cask Trunnions | 10 | 2A VT | | 2 | | | | | | | | | | | | | |
| | c) | Upend transport cask | 30 | - | | | | | | | | | | | | | | | |
| | d) | Lift transport cask off railcar | 30 | - | | | | | | | | | | | | | | | |
| | e) | Reposition transport cask | 30 | - | | | | | | | | | | | | | | | |
| | f) | Place transport cask on unloading cell transfer cart | 15 | - | | | | | | | | | | | | | | | |
| 3a) | Remove railcar from railbay | | 60 | | | | | | | | | | | | | | | | |
| | a) | Open railbay door | 5 | - | | | | | | | | | | | | | | | |
| | b) | Railyard tug connects to railcar | 10 | - | | | | | | | | | | | | | | | |
| | c) | Railyard tug removes railcar from railbay | 10 | - | | | | | | | | | | | | | | | |
| | d) | Railyard tug connects to next railcar | 15 | - | | | | | | | | | | | | | | | |
| | e) | Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | | | | | | | | | |
| | f) | Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | | | | | | | | | |
| 4) | Unbolt and remove transport cask lid using jib crane | | 85 | | | | | | | | | | | | | | | | |
| | a) | Move tools to work platform | 5 | - | | | | | | | | | | | | | | | |
| | b) | HP survey of lid Including gas sampling | 15 | 2A VT | | | 1 | | | | | | | | | | | | |
| | c) | Remove and store nuts | 30 | 2A VT | | 1 | | | | | | | | | | | | | |
| | d) | Rig the lid for lifting using the local jib crane | 15 | 2A VT | | 1.5 | | | | | | | | | | | | | |
| | e) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | | | | | | | | | |
| | f) | Security inspection of the interior of the transport cask | 10 | 2 VT | | | | | 0.2 | | | | | | | | | | |
| 4a) | Secure transport cask and transfer cart seismically | | 40 | | | | | | | | | | | | | | | | |
| | a) | Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | | | | | | | | | |
| | b) | Secure transport cask and transfer cart | 15 | - | | | | | | | | | | | | | | | |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | | | | | | | | | |
| 4b) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | | | | | | | | | |
| | b) | Safety briefing | 10 | - | | | | | | | | | | | | | | | |
| | c) | Transportation to work site | 5 | - | | | | | | | | | | | | | | | |
| 5) | Attach lifting lug to top of DPC | | 70 | | | | | | | | | | | | | | | | |
| | a) | Rig lifting lug on storage rack | 15 | - | | | | | | | | | | | | | | | |
| | b) | Use jib crane to lift lifting lug into position | 15 | 2A VT | | 0.5 | | | | | | | | | | | | | |
| | c) | Bolt lifting lug to canister | 20 | 2 VT | | 0.5 | | | | | | | | | | | | | |
| | d) | QC Hold Point Inspection | 10 | 2 VT | | | | | 0.1 | | | | | | | | | | 2.5 |
| | e) | Clear workspace and remove all tools | 10 | - | | | | | | | | | | | | | | | |
| 6) | Position transport cask transfer cart in unloading cell and close shield doors | | 60 | | | | | | | | | | | | | | | | |
| | a) | Move transport cask cart into the unloading cell | 50 | - | | | | | | | | | | | | | | | |
| | b) | Close the shield doors | 10 | - | | | | | | | | | | | | | | | |
| 7) | Stage empty transfer cask on receiving cell transfer cart | | 90 | | | | | | | | | | | | | | | | |
| | a) | Prepare an empty transfer cask for use | 15 | - | | | | | | | | | | | | | | | |
| | b) | Place the empty transfer cask on the transfer cart using VCT | 15 | - | | | | | | | | | | | | | | | |
| | c) | Stage tools on top of the transfer cask | 10 | - | | | | | | | | | | | | | | | |
| | d) | Unbolt transfer cask lid | 30 | - | | | | | | | | | | | | | | | |
| | e) | Rig the cask lid to the VCT hoist | 10 | - | | | | | | | | | | | | | | | |
| | f) | Hoist lid and retain on VCT | 10 | - | | | | | | | | | | | | | | | |
| 8) | Position empty transfer cask in receiving cell using motorized cart | | 45 | | | | | | | | | | | | | | | | |
| | a) | Open receiving cell shield doors | 15 | - | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | | |
|-------------|----|--|------------|--------|-----|--|--|--|--|--|----|-----|----|---|---|---|
| | b) | Transfer empty transfer cask into receiving cell using motorized cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close the shield doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | | Position shielded transfer sleeve cart over unloading cell | 35 | | | | | | | | | | | | | |
| | a) | Inspect transfer sleeve cart | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) | | Lower shield sleeve hoist and grapple DPC lifting lug | 50 | | | | | | | | | | | | | |
| | a) | HP survey | 0 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower shield sleeve hoist and grapple DPC lifting lug | 50 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | | Raise DPC into shield sleeve | 60 | | | | | | | | | | | | | |
| | a) | Raise DPC into shield sleeve | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | | Position shielded transfer sleeve cart over transfer cask in receiving cell | 70 | | | | | | | | | | | | | |
| | a) | Position shielded transfer sleeve cart over transfer cask in receiving cell | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Lower DPC into empty transfer cask, release grapple, and retract hoist | 60 | | | | | | | | | | | | | |
| | a) | Lower DPC into empty transfer cask, release grapple, and retract hoist | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | | Open receiving cell shield doors and transfer transfer cask out of receiving cell | 35 | | | | | | | | | | | | | |
| | a) | HP survey | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open receiving cell shield doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer transfer cask out of receiving cell using motorized cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Install transfer cask lid | 60 | | | | | | | | | | | | | |
| | a) | Position VCT with transfer cask lid at transfer cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower transfer cask lid into position | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Install bolts and torque | 20 | 2A V T | 1.5 | | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15a) | | Secure seismic restraints | 40 | | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Pick up transport cask and transfer to vault using VCT | 55 | | | | | | | | | | | | | |
| | a) | Rig VCT to lift transfer cask | 10 | 2A V T | 2 | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | b) | Grapple the transport cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Move the transfer cask to the vault | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | | Place transfer cask on transfer cart | 15 | | | | | | | | | | | | | |
| | a) | Place transfer cask on unloading cell transfer cart in vault | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | | Remove transfer cask lid | 75 | | | | | | | | | | | | | |
| | a) | Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid | 15 | 2A V T | 2 | | | | | | 0 | 0 | 10 | 0 | 0 | 0 |
| | c) | Remove and store nuts | 30 | 2A V T | 1 | | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local jib crane | 15 | 2A V T | 2 | | | | | | 0 | 10 | 0 | 0 | 0 | 0 |
| | e) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | | Position transport cask transfer cart in unloading cell and close shield doors | 60 | | | | | | | | | | | | | |
| | a) | Move transport cask cart into the unloading cell | 50 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Close the shield doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | | Position shielded transfer sleeve on bridge crane above transfer cell | 30 | | | | | | | | | | | | | |
| | a) | Inspect shielded transfer sleeve | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20a) | | Secure transfer sleeve seismically | 40 | | | | | | | | | | | | | |
| | a) | Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure transport cask and transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 21) | | Lower hoist, grapple lifting lug, and raise DPC into shield sleeve | 100 | | | | | | | | | | | | | |
| | a) | Lower shield sleeve hoist and grapple DPC lifting lug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Raise DPC into shield sleeve | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | | Transfer DPC to vault storage location | 120 | | | | | | | | | | | | | |
| | a) | Transfer DPC to vault storage location | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | | Remove shield plug above vault storage location | 60 | | | | | | | | | | | | | |
| | a) | Position crane over storage location in vault | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rig the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lift shield plug and place on storage stand | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | | Lower DPC into storage position on vault floor | 70 | | | | | | | | | | | | | |
| | a) | Align DPC over storage position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower DPC into vault | 45 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | | Replace shield plug above vault storage location | 85 | | | | | | | | | | | | | |
| | a) | Rig the shield plug to the crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reposition the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower the shield plug into the vault | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Secure the shield plug and remove rigging | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |

| | | Total Hours of Canister Handling Operations | 35.8 | | | | | | | | | | | | |
|------|--|---|------|---|--|--|--|--|----|----|----|---|----|-----|---|
| 25a) | Turnover to Operations | | 1440 | | | | | | | | | | | | |
| 26) | Return crane to operating floor | | 120 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 27) | Remove transport cask from transfer cell | | 60 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 28) | Install transport cask lid | | 60 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 29) | Lift transport cask and transfer to maintenance | | 60 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 29a) | Survey and wipedown transport cask | | 60 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 29b) | Reposition empty railcar to railbay | | 60 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 30) | Lift transport cask, place on railcar, and downend | | 60 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 31) | Install impact limiters on transport cask | | 120 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 32) | Release railcar for shipment | | 30 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of All Cask Handling Operations | 70.3 | | | | | | 92 | 58 | 56 | 0 | 11 | 2.5 | |

| DPCs in lift frames stored vertically in vault floor | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | |
|--|--|-----------------------|-------|-------------------|---|---|---|---|---|-----------|---|---|---|-----|---|--|
| | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | |
| 0) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | | | | | | | |
| | b) Safety briefing | 10 | - | | | | | | | | | | | | | |
| | c) Transportation to work site | 5 | - | | | | | | | | | | | | | |
| 1) | Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | | |
| | a) Identify SNF shipment brought from yard | 5 | - | | | | | | | | | | | | | |
| | b) Security team sent to railbay door | 15 | - | | | | | | | | | | | | | |
| | c) Send operators to railbay door | 15 | - | | | | | | | | | | | | | |
| | d) Stage work team to railbay | 15 | - | | | | | | | | | | | | | |
| | e) Open railbay door | 5 | - | | | | | | | | | | | | | |
| | f) Position SNF shipment in the railbay | 15 | - | | | | | | | | | | | | | |
| | g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | | | | | | | 0.5 | | |
| | h) HP survey of SNF shipment | 15 | 3 VT | | | | | | | | | | | 0.5 | | |
| | i) Inspection of tamper proof seals | 10 | 3 VT | | | | | | | | | | | 0.1 | | |
| | j) Acceptance of SNF shipment | 5 | - | | | | | | | | | | | | | |
| | k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | | | | | | |
| | l) Secure the railbay doors | 5 | - | | | | | | | | | | | | | |
| | m) Security team leaves | 5 | - | | | | | | | | | | | | | |
| | n) Operator leaves | 5 | - | | | | | | | | | | | | | |
| | o) Completes paperwork for step #1 | 5 | - | | | | | | | | | | | | | |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| | a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | | | | | | |
| | b) Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | | | | | | | |
| | c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | 2 | 2 | | | | | | | | | | | |
| | d) Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A VT | 2 | | | | | | | | | | | | |
| | e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | | | | | | | |
| | f) Remove first impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | | | | | | | |
| | g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | 1 | | | | | | | | | | | | |
| | h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | | | | | | | |
| | i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | | | | | | | |
| | j) Remove second impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | | | | | | | |
| | k) Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | | | | | | | |
| | l) Rig the personnel barrier | 15 | 3 VT | 1 | 1 | | | | | | | | | | | |
| | m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | | | | | | |
| | n) Remove tie-down straps from SNF shipment | 10 | 3A VT | 0.4 | | | | | | | | | | | | |
| | o) Rig tie-down straps and move to storage location | 5 | 3A VT | 1 | | | | | | | | | | | | |
| | p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | 2 | | | | | | | | | | | |
| 3) | Upend and lift transport cask off of railcar and place on transfer fixture | 120 | | | | | | | | | | | | | | |
| | a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | | | | | | | |
| | b) Secure lifting block to transport cask trunnions | 10 | 2A VT | 2 | | | | | | | | | | | | |
| | c) Upend transport cask | 30 | - | | | | | | | | | | | | | |
| | d) Lift transport cask off railcar | 30 | - | | | | | | | | | | | | | |
| | e) Move transport cask to transfer fixture | 30 | - | | | | | | | | | | | | | |
| | f) Downend transport cask on transfer fixture | 15 | - | | | | | | | | | | | | | |
| 3a) | Remove railcar from railbay | 60 | | | | | | | | | | | | | | |
| | a) Open railbay door | 5 | - | | | | | | | | | | | | | |
| | b) Railyard tug connects to railcar | 10 | - | | | | | | | | | | | | | |
| | c) Railyard tug removes railcar from railbay | 10 | - | | | | | | | | | | | | | |
| | d) Railyard tug connects to next railcar | 15 | - | | | | | | | | | | | | | |
| | e) Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | | | | | | | |
| | f) Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | | | | | | | |
| 4) | Stage transfer cask on upender using VCT | 50 | | | | | | | | | | | | | | |
| | a) Move the VCT into position | 5 | - | | | | | | | | | | | | | |
| | b) Grapple the transfer cask | 5 | - | | | | | | | | | | | | | |
| | c) Pick the transfer cask | 15 | - | | | | | | | | | | | | | |
| | d) Reposition the VCT at the upender in the transfer cell | 15 | - | | | | | | | | | | | | | |
| | e) Place the transfer cask on the upender | 10 | - | | | | | | | | | | | | | |
| 5) | Unbolt and hoist transfer cask lid and retain on VCT | 70 | | | | | | | | | | | | | | |
| | a) Stage tools on top of the transfer cask | 10 | - | | | | | | | | | | | | | |
| | b) Unbolt transfer cask lid | 30 | - | | | | | | | | | | | | | |
| | c) Rig lid to the VCT hoist | 10 | - | | | | | | | | | | | | | |
| | d) Lift lid to the storage position of the VCT | 10 | - | | | | | | | | | | | | | |
| | e) Remove grapples and back VCT out of the transfer cell | 10 | - | | | | | | | | | | | | | |
| 5a) | Secure transport cask and transfer cart seismically | 40 | | | | | | | | | | | | | | |
| | a) Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | | | | | | | |
| | b) Secure transport cask and transfer cart | 15 | - | | | | | | | | | | | | | |
| | c) QC Hold Point Inspection | 10 | - | | | | | | | | | | | | | |
| 5b) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | | | | | | | |
| | b) Safety briefing | 10 | - | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|-------------|--|--|------------|------------|---|-----|--|-----|--|-----|-----|-----|---|-----|---|
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5c) | Load lifting frame into transfer cask using jib crane | | 85 | | | | | | | | | | | | |
| | a) | Move lifting frame into position using a transfer cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rig the lifting frame onto the jib crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Hoist the lifting frame and load it into the transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift docking collar and place on top of transfer cask | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Strap docking collar to top of transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove the rigging and secure the jib crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) | Downend transfer cask on upender | | 30 | | | | | | | | | | | | |
| | a) | Secure transfer cask to upender | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Downend the transfer cask to the horizontal position | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) | Remove transport cask lid | | 100 | | | | | | | | | | | | |
| | a) | Move tools to work platform | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid including gas sampling | 15 | 1A H T L | | 2 | | | | 0 | 0 | 9.2 | 0 | 0 | 0 |
| | c) | Position jib crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local jib crane | 15 | 1A H T L | | 2 | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| | e) | Remove and store nuts | 30 | 1A H T L | 2 | | | | | 18 | 0 | 0 | 0 | 0 | 0 |
| | f) | Lift the transport cask lid and move it to the transfer fixture | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Security inspection of the interior of the transport cask | 10 | 1A H T N L | | | | 0.2 | | 0 | 0 | 0 | 0 | 5.4 | 0 |
| 7a) | Secure transport cask and transfer fixture seismically | | 40 | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7b) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) | Dock transfer sleeve on horizontal transfer cart with transport cask | | 75 | | | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move transfer sleeve into position | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Align transport cask with transfer sleeve | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock transfer sleeve to transport cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Install retaining straps on transport cask trunnions | 15 | 2A H T | | 1.5 | | | | 0 | 12 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | Push DPC into lift frame inside transfer cask | | 75 | | | | | | | | | | | | |
| | a) | Remove pushing port in base of transport cask | 15 | 5 H H | 2 | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into transfer sleeve | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) | Undock horizontal transfer cart from transport cask | | 30 | | | | | | | | | | | | |
| | a) | Remove retaining straps from transfer sleeve | 10 | 2A H T | | 0.2 | | | | 0 | 1.1 | 0 | 0 | 0 | 0 |
| | b) | Pull horizontal transfer cart back | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close shield door on transfer sleeve | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | Roll horizontal transfer cart onto turntable and rotate 180° | | 30 | | | | | | | | | | | | |
| | a) | Roll transfer cart to turntable lock wheels | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rotate turntable 180° | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | Roll horizontal transfer cart to upending cell and dock with transfer cask on upender | | 45 | | | | | | | | | | | | |
| | a) | Unlock wheels and roll transfer cart to upending cell | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Dock transfer sleeve to transfer cask on upender | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Attach retaining straps to transfer sleeve trunnions | 15 | 2A H T | | 0.5 | | | | 0 | 4 | 0 | 0 | 0 | 0 |
| 13) | Push DPC from transfer sleeve into lift frame in transfer cask | | 65 | | | | | | | | | | | | |
| | a) | Plug in hydraulic power pack on transfer cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into the lift frame in the transfer cask | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | Undock horizontal transfer cart | | 50 | | | | | | | | | | | | |
| | a) | Remove retaining straps from transfer cask | 15 | 2A H T | | 0.2 | | | | 0 | 1.6 | 0 | 0 | 0 | 0 |
| | b) | Unplug hydraulic power pack on transfer cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Undock transfer cart and remove | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | Upend transfer cask | | 30 | | | | | | | | | | | | |
| | a) | Close shield Door to upender cell | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Upend the transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Set locking mechanism on upender | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | Install lid on transfer cask | | 85 | | | | | | | | | | | | |
| | a) | Open outer shield doors to upender cell | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position VCT at transfer cask on upender | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower transfer cask lid into place using the VCT | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Stage tools on manlift | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Install bolts and torque | 20 | 2A H T | | 1.5 | | | | 16 | 0 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Move manlift away | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16a) | Secure transport cask and Transfer Fixture seismically | | 40 | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16b) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | Transfer transfer cask to vault | | 60 | | | | | | | | | | | | |
| | a) | Rig VCT to lift transfer cask | 10 | 2A V T | | 2 | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | b) | Open transfer cell shield doors and back VCT out of cell | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Move transfer cask to vault | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | Lift transfer cask and place on transfer cart | | 40 | | | | | | | | | | | | |
| | a) | Lift Transfer Cask and place on Transfer cell motorized cart | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | | | | | |
|-------------|---|--|-------------|--------|---|---|---|--|-----|--|----|-----|-----|---|----|---|-----|---|---|---|
| 13) | Remove transfer cask cover using jib crane and set down | 85 | | | | | | | | | | | | | | | | | | |
| | a) | Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid | 15 | 1A HTL | | | 2 | | | | 0 | 0 | 9.2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove and store nuts | 30 | 1A HTL | 2 | | | | | | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local jib crane | 15 | 1A HTL | | 2 | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Security inspection of the interior of the transport cask | 10 | 1A VC | | | | | 0.2 | | 0 | 0 | 0 | 0 | 0 | 0 | 8.5 | 0 | 0 | 0 |
| 15) | Roll transfer cart into transfer cell and close shield doors | 30 | | | | | | | | | | | | | | | | | | |
| | a) | Move transfer cask cart into the unloading cell | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Close the shield doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | Position shielded transfer sleeve above transfer cell | 70 | | | | | | | | | | | | | | | | | | |
| | a) | Inspect shielded transfer sleeve | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Secure in position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16a) | Secure shielded transfer sleeve and DPC seismically | 40 | | | | | | | | | | | | | | | | | | |
| | a) | Reposition seismic restraint system | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure shielded transfer sleeve | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 16b) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | Lower hoist, grapple lifting lug, and raise DPC into shield sleeve | 90 | | | | | | | | | | | | | | | | | | |
| | a) | Lower shield sleeve hoist and grapple lift frame | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Raise DPC into shield sleeve | 45 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close shield sleeve lower doors | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | Transfer DPC to vault storage location | 120 | | | | | | | | | | | | | | | | | | |
| | a) | Transfer DPC to vault storage location | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | Remove shield plug above vault storage location | 105 | | | | | | | | | | | | | | | | | | |
| | a) | Stage tools in storage vault location | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position crane in vault | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift shield plug and place on storage stand | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Disconnect rigging and return crane to cask handling area | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | Lower DPC and lift frame into storage position on vault floor | 85 | | | | | | | | | | | | | | | | | | |
| | a) | Align DPC over storage position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower DPC into vault | 45 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 21) | Replace shield plug above vault storage location | 85 | | | | | | | | | | | | | | | | | | |
| | a) | Rig the shield plug to the crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reposition the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower the shield plug into the vault | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Secure the shield plug and remove rigging | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 39.1 | | | | | | | | | | | | | | | | | |
| 21a) | Turnover to Operations | 1440 | | | | | | | | | | | | | | | | | | |
| 22) | Return crane to Operating Floor | 60 | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | Install transport cask lid | 60 | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | Lift transport cask and transfer to maintenance | 60 | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 24a) | Survey and wipedown transport cask | 60 | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | Lift transport cask and place on railcar | 60 | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 26) | Install impact limiters on transport cask | 120 | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 27) | Release railcar for shipment | 60 | | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of All Cask Handling Operations | 71.1 | | | | | | | | 94 | 75 | 59 | 0 | 20 | 0 | | | | |

4D, 5D - C-BGVd/AGVd, Below/Above Ground Vault with Separate CHB - Vertical and Horizontal Storage

| Vertical - DSCs stored vertically in vault floor | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | | | | |
|--|---|-----------------------|-------|-------------------|-----|-----|---|---|---|-----------|---|---|---|---|---|--|--|--|--|
| | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | | | | |
| 0) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | | | | | | | | | | |
| | b) Safety briefing | 10 | - | | | | | | | | | | | | | | | | |
| | c) Transportation to work site | 5 | - | | | | | | | | | | | | | | | | |
| 1) | Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | | | | | |
| | a) Identify SNF shipment brought from yard | 5 | - | | | | | | | | | | | | | | | | |
| | b) Security team sent to railbay door | 15 | - | | | | | | | | | | | | | | | | |
| | c) Send operators to railbay door | 15 | - | | | | | | | | | | | | | | | | |
| | d) Stage work team to railbay | 15 | - | | | | | | | | | | | | | | | | |
| | e) Open railbay door | 5 | - | | | | | | | | | | | | | | | | |
| | f) Position SNF shipment in the railbay | 15 | - | | | | | | | | | | | | | | | | |
| | g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | | | | | | | | | | | | |
| | h) HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | | | | | | | | | | |
| | i) Inspection of tamper proof Seals | 10 | 3 VT | | | | | | | | | | | | | | | | |
| | j) Acceptance of SNF shipment | 5 | - | | | | | | | | | | | | | | | | |
| | k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | | | | | | | | | |
| | l) Secure the railbay doors | 5 | - | | | | | | | | | | | | | | | | |
| | m) Security team leaves | 5 | - | | | | | | | | | | | | | | | | |
| | n) Operator leaves | 5 | - | | | | | | | | | | | | | | | | |
| | o) Completes paperwork for step #1 | 5 | - | | | | | | | | | | | | | | | | |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | | | | |
| | a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | | | | | | | | | |
| | b) Select and inspect rigging for impact limiters on the transport cask | 5 | - | | | | | | | | | | | | | | | | |
| | c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | | 2 | 2 | | | | | | | | | | | | | |
| | d) Position man lifts and temporary scaffolding near transport cask | 5 | 1A VT | | 2 | | | | | | | | | | | | | | |
| | e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | | 2 | | | | | | | | | | | | | | |
| | f) Remove first impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | | | | | | | | | | |
| | g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | | 1 | | | | | | | | | | | | | | |
| | h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | | | | | | | | | | |
| | i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | | 2 | | | | | | | | | | | | | | |
| | j) Remove second impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | | | | | | | | | | |
| | k) Remove and store bolts for personnel barrier | 30 | 3 VT | | 0.2 | | | | | | | | | | | | | | |
| | l) Rig the personnel barrier | 15 | 3 VT | | 1 | 1 | | | | | | | | | | | | | |
| | m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | | | | | | | | | |
| | n) Remove tie-down straps from transport cask | 10 | 3A VT | | 0.4 | | | | | | | | | | | | | | |
| | o) Rig tie-down straps and move to storage location | 5 | 3A VT | | 1 | | | | | | | | | | | | | | |
| | p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | | 2 | | | | | | | | | | | | | |
| 3) | Upend and lift transport cask off of railcar and place on unloading cell transfer cart | 120 | | | | | | | | | | | | | | | | | |
| | a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | | | | | | | | | | |
| | b) Secure lifting block to transport cask Trunnions | 10 | 2A VT | | 2 | | | | | | | | | | | | | | |
| | c) Upend transport cask | 30 | - | | | | | | | | | | | | | | | | |
| | d) Lift transport cask off railcar | 30 | - | | | | | | | | | | | | | | | | |
| | e) Reposition transport cask | 30 | - | | | | | | | | | | | | | | | | |
| | f) Place transport cask on unloading cell transfer cart | 15 | - | | | | | | | | | | | | | | | | |
| 3a) | Remove railcar from railbay | 60 | | | | | | | | | | | | | | | | | |
| | a) Open railbay door | 5 | - | | | | | | | | | | | | | | | | |
| | b) Railyard tug connects to railcar | 10 | - | | | | | | | | | | | | | | | | |
| | c) Railyard tug removes railcar from railbay | 10 | - | | | | | | | | | | | | | | | | |
| | d) Railyard tug connects to next railcar | 15 | - | | | | | | | | | | | | | | | | |
| | e) Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | | | | | | | | | | |
| | f) Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | | | | | | | | | | |
| 4) | Unbolt and remove transport cask lid using jib crane | 85 | | | | | | | | | | | | | | | | | |
| | a) Move tools to work platform | 5 | - | | | | | | | | | | | | | | | | |
| | b) HP survey of lid Including gas sampling | 15 | 2A VT | | | 1 | | | | | | | | | | | | | |
| | c) Remove and store nuts | 30 | 2A VT | | 1 | | | | | | | | | | | | | | |
| | d) Rig the lid for lifting using the local jib crane | 15 | 2A VT | | 1.5 | | | | | | | | | | | | | | |
| | e) Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | | | | | | | | | | |
| | f) Security inspection of the interior of the transport cask | 10 | 2 VT | | | | | | | | | | | | | | | | |
| 4a) | Secure transport cask and transfer cart seismically | 40 | | | | | | | | | | | | | | | | | |
| | a) Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | | | | | | | | | | |
| | b) Secure transport cask and transfer cart | 15 | - | | | | | | | | | | | | | | | | |
| | c) QC Hold Point Inspection | 10 | - | | | | | | | | | | | | | | | | |
| 4b) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | | | | | | | | | | |
| | b) Safety briefing | 10 | - | | | | | | | | | | | | | | | | |
| | c) Transportation to work site | 5 | - | | | | | | | | | | | | | | | | |
| 5) | Attach lifting lug to top of DPC | 70 | | | | | | | | | | | | | | | | | |
| | a) Rig lifting lug on storage rack | 15 | - | | | | | | | | | | | | | | | | |
| | b) Use jib crane to lift lifting lug into position | 15 | 2A VT | | 0.5 | | | | | | | | | | | | | | |
| | c) Bolt lifting lug to canister | 20 | 2 VT | | 0.5 | | | | | | | | | | | | | | |
| | d) QC Hold Point Inspection | 10 | 2 VT | | | | | | | | | | | | | | | | |
| | e) Clear workspace and remove all tools | 10 | - | | | | | | | | | | | | | | | | |
| 6) | Position transport cask transfer cart in unloading cell and close shield doors | 60 | | | | | | | | | | | | | | | | | |
| | a) Move transport cask cart into the unloading cell | 50 | - | | | | | | | | | | | | | | | | |
| | b) Close the shield doors | 10 | - | | | | | | | | | | | | | | | | |
| 7) | Stage empty transfer cask on receiving cell transfer cart | 90 | | | | | | | | | | | | | | | | | |
| | a) Prepare an empty transfer cask for use | 15 | - | | | | | | | | | | | | | | | | |
| | b) Place the empty transfer cask on the transfer cart using VCT | 15 | - | | | | | | | | | | | | | | | | |
| | c) Stage tools on top of the transfer cask | 10 | - | | | | | | | | | | | | | | | | |
| | d) Unbolt transfer cask lid | 30 | - | | | | | | | | | | | | | | | | |
| | e) Rig the cask lid to the VCT hoist | 10 | - | | | | | | | | | | | | | | | | |
| | f) Hoist lid and retain on VCT | 10 | - | | | | | | | | | | | | | | | | |
| 8) | Position empty transfer cask in receiving cell using motorized cart | 45 | | | | | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|-------------|----|--|------------|--------|-----|--|--|--|----|-----|----|----|---|---|---|
| | a) | Open receiving cell shield doors | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Transfer empty transfer cask into receiving cell using motorized cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close the shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | | Position shielded transfer sleeve cart over unloading cell | 35 | | | | | | | | | | | | |
| | a) | Inspect transfer sleeve cart | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) | | Lower shield sleeve hoist and grapple DPC lifting lug | 50 | | | | | | | | | | | | |
| | a) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower shield sleeve hoist and grapple DPC lifting lug | 50 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | | Raise DPC into shield sleeve | 60 | | | | | | | | | | | | |
| | a) | Raise DPC into shield sleeve | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | | Position shielded transfer sleeve cart over transfer cask in receiving cell | 70 | | | | | | | | | | | | |
| | a) | Position shielded transfer sleeve cart over transfer cask in receiving cell | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Lower DPC into empty transfer cask, release grapple, and retract hoist | 60 | | | | | | | | | | | | |
| | a) | Lower DPC into empty transfer cask, release grapple, and retract hoist | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | | Open receiving cell shield doors and transfer transfer cask out of receiving cell | 35 | | | | | | | | | | | | |
| | a) | HP survey | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open receiving cell shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer transfer cask out of receiving cell using motorized cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Install transfer cask lid | 60 | | | | | | | | | | | | |
| | a) | Position VCT with transfer cask lid at transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower transfer cask lid into position | 10 | - | | | | | | | | | | | |
| | c) | Install bolts and torque | 20 | 2A V T | 1.5 | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15a) | | Secure seismic restraints | 40 | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Pick up transport cask and transfer to vault using VCT | 55 | | | | | | | | | | | | |
| | a) | Rig VCT to lift transfer cask | 10 | 2A V T | 2 | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| | b) | Grapple the transport cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Move the transfer cask to the vault | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | | Place transfer cask on transfer cart | 15 | | | | | | | | | | | | |
| | a) | Place transfer cask on unloading cell transfer cart in vault | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | | Remove transfer cask lid | 75 | | | | | | | | | | | | |
| | a) | Move tools to work platform | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid | 15 | 2A V T | 2 | | | | | 0 | 0 | 10 | 0 | 0 | 0 |
| | c) | Remove and store nuts | 30 | 2A V T | 1 | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local jib crane | 15 | 2A V T | 2 | | | | | 0 | 10 | 0 | 0 | 0 | 0 |
| | e) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | | Position transport cask transfer cart in unloading cell and close shield doors | 60 | | | | | | | | | | | | |
| | a) | Move transport cask cart into the unloading cell | 50 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Close the shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20) | | Position shielded transfer sleeve on bridge crane above transfer cell | 30 | | | | | | | | | | | | |
| | a) | Inspect shielded transfer sleeve | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20a) | | Secure transfer sleeve seismically | 40 | | | | | | | | | | | | |
| | a) | Reposition transfer cart near seismic restraint system | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure transport cask and transfer cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 20b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 21) | | Lower hoist, grapple lifting lug, and raise DPC into shield sleeve | 100 | | | | | | | | | | | | |
| | a) | Lower shield sleeve hoist and grapple DPC lifting lug | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Raise DPC into shield sleeve | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | HP survey | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | | Transfer DPC to vault storage location | 120 | | | | | | | | | | | | |
| | a) | Transfer DPC to vault storage location | 120 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 23) | | Remove shield plug above vault storage location | 60 | | | | | | | | | | | | |
| | a) | Position crane over storage location in vault | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rig the shield plug | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lift shield plug and place on storage stand | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | | Lower DPC into storage position on vault floor | 70 | | | | | | | | | | | | |
| | a) | Align DPC over storage position | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower DPC into vault | 45 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | | Replace shield plug above vault storage location | 85 | | | | | | | | | | | | |
| | a) | Rig the shield plug to the crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reposition the shield plug | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower the shield plug into the vault | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Secure the shield plug and remove rigging | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |


| | | | | | | | | | | | | | | | |
|--|---|-------------|---|--|--|--|--|--|--|----|----|----|---|----|-----|
| f) | HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Hours of Canister Handling Operations | | 35.8 | | | | | | | | | | | | | |
| 25a) | Turnover to Operations | 1440 | | | | | | | | | | | | | |
| 26) | Return crane to operating floor | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 27) | Remove transport cask from transfer cell | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 28) | Install transport cask lid | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 29) | Lift transport cask and transfer to maintenance | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 29a) | Survey and wipedown transport cask | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 29b) | Reposition empty railcar to railbay | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 30) | Lift transport cask, place on railcar, and downend | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 31) | Install impact limiters on transport cask | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 32) | Release railcar for shipment | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| Total Hours of All Cask Handling Operations | | 70.3 | | | | | | | | 92 | 58 | 56 | 0 | 11 | 2.5 |

| Horizontal -DSCs stored horizontally in racks in vault | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | |
|--|---|-----------------------|---------|-------------------|-----|---|---|-----|---|-----------|-----|-----|---|-----|---|---|
| | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | |
| 0) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | | |
| a) | Identify SNF shipment brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Security team sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Send operators to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Position SNF shipment in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| g) | Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 | 0 |
| h) | HP survey of SNF shipment | 15 | 3 VT | | 0.5 | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 | 0 |
| i) | Inspection of tamper proof seals | 10 | 3 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 | 0 |
| j) | Acceptance of SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| k) | Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) | Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| m) | Security team leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| n) | Operator leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| o) | Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Rig the lifting devices to the first impact limiter | 5 | 1A VT | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 | 0 |
| d) | Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A VT | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| e) | Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Remove first impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| g) | Remove rigging and reposition on second impact limiter | 5 | 1A VT | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| h) | Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| i) | Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| j) | Remove second impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| k) | Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) | Rig the personnel barrier | 15 | 3 VT | 1 | 1 | | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| m) | Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| n) | Remove tie-down straps from SNF shipment | 10 | 3A VT | 0.4 | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| o) | Rig tie-down straps and move to storage location | 5 | 3A VT | 1 | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| p) | Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | 2 | | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) | Upend and lift transport cask off of railcar and place on transfer fixture | 120 | | | | | | | | | | | | | | |
| a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Secure lifting block to transport cask trunnions | 10 | 2A VT | 2 | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| c) | Upend transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Lift transport cask off railcar | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Move transport cask to transfer fixture | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Downend transport cask on transfer fixture | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Remove railcar from railbay | 60 | | | | | | | | | | | | | | |
| a) | Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Railyard tug connects to railcar | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Railyard tug removes railcar from railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Railyard tug connects to next railcar | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4a) | Secure transport cask and transfer fixture seismically | 40 | | | | | | | | | | | | | | |
| a) | Position seismic restraints | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Secure seismic restraints | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | Remove transport cask lid | 85 | | | | | | | | | | | | | | |
| a) | Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | HP survey of lid including gas sampling | 15 | 1A HTL | | 2 | | | | | 0 | 0 | 9.2 | 0 | 0 | 0 | 0 |
| c) | Rig the lid for lifting using the local jib crane | 15 | 1A HTL | 2 | | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 | 0 |
| d) | Remove and store nuts | 30 | 1A HTL | 2 | | | | | | 18 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Lift the transport cask lid and move it to the transfer fixture | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Security inspection of the interior of the transport cask | 10 | 1A HTNL | | | | | 0.2 | | 0 | 0 | 0 | 0 | 5.4 | 0 | 0 |
| 6) | Dock transfer sleeve on horizontal transfer cart with transport cask | 75 | | | | | | | | | | | | | | |
| a) | Position spotters | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Move transfer sleeve into position | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | |
|-------------|----|---|-----------|----------|-----|--|--|--|-----|-----|-----|-----|---|-----|---|
| | c) | Align transport cask with transfer sleeve | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock transfer sleeve to transport cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Install retaining straps on transport cask trunnions | 15 | 2A H T | 1.5 | | | | | 0 | 12 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) | | Push DPC into transfer cask | 75 | | | | | | | | | | | | |
| | a) | Remove pushing port in base of transport cask | 15 | 5 H H | 2 | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into transfer sleeve | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) | | Undock horizontal transfer cart from transport cask | 30 | | | | | | | | | | | | |
| | a) | Remove retaining straps from transport cask | 10 | 2A H T | 0.2 | | | | | 0 | 1.1 | 0 | 0 | 0 | 0 |
| | b) | Pull horizontal transfer cart back | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close shield door on transfer sleeve | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | | Install transport cask lid | 60 | | | | | | | | | | | | |
| 10) | | Lift transport cask and transfer to maintenance | 60 | | | | | | | | | | | | |
| 10a) | | Secure transport cask and transfer fixture seismically | 40 | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | | Stage transfer cask on transfer fixture using HCT | 35 | | | | | | | | | | | | |
| | a) | Move the HCT with a transfer cask next to the transfer fixture | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rig the transfer cask for hoisting | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Pick the transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Downend the transfer cask on the transfer fixture | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | | Unbolt and hoist transfer cask lid using jib crane | 50 | | | | | | | | | | | | |
| | a) | Rig transfer cask lid to jib crane | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Unbolt transfer cask lid | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Hoist lid and remove | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Dock horizontal transfer cart with transfer cask on transfer fixture | 45 | | | | | | | | | | | | |
| | a) | Unlock wheels and position transfer cart at transfer fixture | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Dock transfer sleeve to transfer cask on transfer fixture | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Attach retaining straps to transfer cask trunnions | 15 | 2A H T | 0.5 | | | | | 0 | 4 | 0 | 0 | 0 | 0 |
| 14) | | Push DPC from transfer sleeve into transfer cask | 65 | | | | | | | | | | | | |
| | a) | Plug in hydraulic power pack on transfer cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Engage ram and push DPC into the lift frame in the transfer cask | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Withdraw the ram | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Undock horizontal transfer cart | 50 | | | | | | | | | | | | |
| | a) | Remove retaining straps from transfer cask | 15 | 2A H T | 0.2 | | | | | 0 | 1.6 | 0 | 0 | 0 | 0 |
| | b) | Unplug hydraulic power pack on transfer cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Undock transfer cart and remove | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Install lid on transfer cask | 70 | | | | | | | | | | | | |
| | a) | Hoist transfer cask lid into place using jib crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Stage tools on manlift | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Install bolts and torque | 30 | 2A H T | 2 | | | | | 32 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Move manlift away | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | | Transfer transfer cask to vault | 60 | | | | | | | | | | | | |
| | a) | Rig VCT to lift transfer cask | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | b) | Open transfer cell shield doors and back VCT out of cell | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Move transfer cask to vault | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | | Lift transfer cask and place on transfer cart | 40 | | | | | | | | | | | | |
| | a) | Lift Transfer Cask and place on Transfer cell motorized cart | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18a) | | Secure transport cask and Transfer Fixture seismically | 40 | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 19) | | Remove transfer cask cover using jib crane and set down | 85 | | | | | | | | | | | | |
| | a) | Move tools to work platform | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid | 15 | 1A H T L | 2 | | | | | 0 | 0 | 9.2 | 0 | 0 | 0 |
| | c) | Remove and store nuts | 30 | 1A H T L | 2 | | | | | 18 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local jib crane | 15 | 1A H T L | 2 | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| | e) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Security inspection of the interior of the transport cask | 10 | 1C V C | | | | | 0.2 | 0 | 0 | 0 | 0 | 3.9 | 0 |
| 20) | | Roll transfer cart into transfer cell and close shield doors | 30 | | | | | | | | | | | | |
| | a) | Move transfer cask cart into the unloading cell | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Close the shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 21) | | Position shielded transfer sleeve above transfer cell | 70 | | | | | | | | | | | | |
| | a) | Inspect shielded transfer sleeve | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Secure in position | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 22) | | Lower hoist, grapple lifting lug, and raise DPC into shield sleeve | 90 | | | | | | | | | | | | |
| | a) | Lower shield sleeve hoist and grapple lift frame | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Raise DPC into shield sleeve | 45 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close shield sleeve lower doors | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | HP survey | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | | | | | |
|-------------|--|-------------|---|--|--|--|--|--|--|-----|----|----|---|----|---|---|---|---|---|---|
| 23) | Transfer DPC to vault storage location | 120 | | | | | | | | | | | | | | | | | | |
| | a) Transfer DPC to vault storage location | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 23a) | Secure shielded transfer sleeve and DPC seismically | 40 | | | | | | | | | | | | | | | | | | |
| | a) Reposition seismic restraint system | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Secure shielded transfer sleeve | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 23b) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 24) | Remove shield plug above vault storage location | 105 | | | | | | | | | | | | | | | | | | |
| | a) Stage tools in storage vault location | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Position crane in vault | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Rig the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Lift shield plug and place on storage stand | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Disconnect rigging and return crane to cask handling area | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | Lower DPC and lift frame into storage position on vault floor | 85 | | | | | | | | | | | | | | | | | | |
| | a) Align DPC over storage position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Lower DPC into vault | 45 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 26) | Replace shield plug above vault storage location | 85 | | | | | | | | | | | | | | | | | | |
| | a) Rig the shield plug to the crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Reposition the shield plug | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Lower the shield plug into the vault | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Secure the shield plug and remove rigging | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) HP survey | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of Canister Handling Operations | 36.3 | | | | | | | | | | | | | | | | | | |
| 26a) | Turnover to Operations | 1440 | | | | | | | | | | | | | | | | | | |
| 27) | Return crane to Operating Floor | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 28) | Install transport cask lid | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 29) | Lift transport cask and transfer to maintenance | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 29a) | Survey and wipedown transport cask | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 30) | Lift transport cask and place on railcar | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 31) | Install impact limiters on transport cask | 120 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 32) | Release railcar for shipment | 60 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of All Cask Handling Operations | 68.3 | | | | | | | | 110 | 75 | 59 | 0 | 16 | 0 | | | | | |

Container Doses



Notes:

| | | | | | |
|------------|----|---|---|-------|------------------------------|
| 1 V C | 1 | V | C | 512 | transport cask lid removed |
| 1A H T L | 1A | H | T | 18.4 | transport cask lid installed |
| 1A H T N L | 1A | H | T | 163.2 | transport cask lid removed |
| 1A V C | 1A | V | C | 254 | no transfer cask lid |
| 1A V T | 1A | V | T | 15 | impact limiters installed |
| 1B V C | 1B | V | C | 134 | no transfer cask lid |
| 1C V C | 1C | V | C | 117 | no transfer cask lid |
| 1D V C | 1D | V | C | 62 | no transfer cask lid |
| 2 V T | 2 | V | T | 150 | transport cask lid removed |
| 2A H T | 2A | H | T | 31.8 | transport cask lid installed |
| 2A V T | 2A | V | T | 20 | transport cask lid installed |
| 2B V X | 2B | V | X | 125 | |
| 2C H T L | 2C | H | T | 1.5 | transport cask lid installed |
| 2C H T N L | 2C | H | T | 7.1 | transport cask lid removed |
| 3 V T | 3 | V | T | 44 | |
| 3A V T | 3A | V | T | 34 | |
| 3B V C | 3B | V | C | 146 | |
| 4 H T | 4 | H | T | 31.8 | |
| 4 V S | 4 | V | S | 111 | |
| 4 V X | 4 | V | X | 177 | |
| 4A H H | 4A | H | H | 2.5 | port cover installed |
| 5 H H | 5 | H | H | 8.5 | port cover installed |
| 5A H H | 5A | H | H | 3.2 | port cover installed |

| Study #1 Storage Alternative | Worker Category: No. of Workers: | Dose per DPC to Worker by Category* (person-mrem/DPC) | | | | | | | Annual Dose to Unit Worker by Category** (rem/yr) | | | | | | | Number of Workers by Category at 500 mrem/worker | | | | | | | Total Hours | |
|-----------------------------------|-------------------------------------|--|---------|----------------|-----------|----------|---------|-------|--|---------|----------------|-----------|----------|---------|-------|---|---------|----------------|-----------|----------|---------|-------|-------------------|---------------|
| | | Mechanics | Riggers | Health Physics | Operators | Security | Quality | Total | Mechanics | Riggers | Health Physics | Operators | Security | Quality | Total | Mechanics | Riggers | Health Physics | Operators | Security | Quality | Total | Canister Transfer | Cask Handling |
| App A1 - C-PAD | Vertical | 126 | 60 | 51 | 0 | 11 | 3 | 251 | 15.8 | 7.5 | 6.4 | 0.0 | 2.8 | 0.7 | 33.2 | 32 | 16 | 13 | 0 | 6 | 2 | 69 | 26 | 61 |
| | Horizontal | 80 | 47 | 51 | 0 | 11 | 8 | 198 | 10.0 | 5.8 | 6.4 | 0.0 | 2.8 | 2.0 | 27.1 | 21 | 12 | 13 | 0 | 6 | 5 | 57 | 21 | 55 |
| App A2 - C-STDa | Vertical | 126 | 60 | 51 | 0 | 11 | 3 | 251 | 15.8 | 7.5 | 6.4 | 0.0 | 2.8 | 0.7 | 33.2 | 32 | 16 | 13 | 0 | 6 | 2 | 69 | 26 | 61 |
| | Horizontal | 69 | 60 | 50 | 0 | 13 | 0 | 192 | 8.6 | 7.4 | 6.3 | 0.0 | 3.3 | 0.0 | 25.6 | 18 | 15 | 13 | 0 | 7 | 0 | 53 | 31 | 55 |
| App A2 - C-STDb | Vertical | 126 | 60 | 51 | 0 | 11 | 3 | 251 | 15.8 | 7.5 | 6.4 | 0.0 | 2.8 | 0.7 | 33.2 | 32 | 16 | 13 | 0 | 6 | 2 | 69 | 26 | 61 |
| | Horizontal | 80 | 47 | 51 | 0 | 11 | 8 | 198 | 10.0 | 5.8 | 6.4 | 0.0 | 2.8 | 2.0 | 27.1 | 21 | 12 | 13 | 0 | 6 | 5 | 57 | 21 | 55 |
| App A2 - C-STDc | Vertical | 167 | 91 | 64 | 0 | 18 | 11 | 351 | 20.8 | 11.4 | 7.9 | 0.0 | 4.5 | 2.8 | 47.5 | 42 | 23 | 16 | 0 | 10 | 6 | 97 | 37 | 70 |
| | Horizontal | 80 | 47 | 51 | 0 | 11 | 8 | 198 | 10.0 | 5.8 | 6.4 | 0.0 | 2.8 | 2.0 | 27.1 | 21 | 12 | 13 | 0 | 6 | 5 | 57 | 21 | 55 |
| App A3 - C-UGS | Vertical | 176 | 68 | 54 | 0 | 11 | 3 | 313 | 22.0 | 8.5 | 6.8 | 0.0 | 2.8 | 0.7 | 40.8 | 45 | 18 | 14 | 0 | 6 | 2 | 85 | 35 | 71 |
| | Horizontal | 197 | 91 | 50 | 0 | 12 | 0 | 350 | 24.7 | 11.4 | 6.3 | 0.0 | 2.9 | 0.0 | 45.2 | 50 | 23 | 13 | 0 | 6 | 0 | 92 | 38 | 74 |
| App A4 - C-BGVa, App A5 - C-AGVa, | Vertical | 72 | 42 | 46 | 0 | 11 | 3 | 173 | 9.0 | 5.2 | 5.8 | 0.0 | 2.8 | 0.6 | 23.4 | 18 | 11 | 12 | 0 | 6 | 2 | 49 | 21 | 54 |
| | Horizontal | 53 | 66 | 50 | 0 | 9 | 0 | 178 | 6.6 | 8.3 | 6.3 | 0.0 | 2.2 | 0.0 | 23.4 | 14 | 17 | 13 | 0 | 5 | 0 | 49 | 30 | 62 |
| App A4 - C-BGVb, App A5 - C-AGVb, | Vertical | 72 | 42 | 46 | 0 | 11 | 3 | 173 | 9.0 | 5.2 | 5.8 | 0.0 | 2.8 | 0.6 | 23.4 | 18 | 11 | 12 | 0 | 6 | 2 | 49 | 21 | 54 |
| | Horizontal | 56 | 38 | 42 | 0 | 3 | 1 | 141 | 7.0 | 4.8 | 5.3 | 0.0 | 0.7 | 0.4 | 18.2 | 15 | 10 | 11 | 0 | 2 | 1 | 39 | 16 | 49 |
| App A4 - C-BGVc, App A5 - C-AGVc, | Vertical | 92 | 58 | 56 | 0 | 11 | 3 | 220 | 11.5 | 7.3 | 7.0 | 0.0 | 2.8 | 0.6 | 29.2 | 23 | 15 | 14 | 0 | 6 | 2 | 60 | 36 | 70 |
| | Horizontal | 94 | 75 | 59 | 0 | 20 | 0 | 249 | 11.7 | 9.4 | 7.4 | 0.0 | 5.0 | 0.0 | 33.6 | 24 | 19 | 15 | 0 | 11 | 0 | 69 | 39 | 71 |
| App A4 - C-BGVd, App A5 - C-AGVd, | Vertical | 92 | 58 | 56 | 0 | 11 | 3 | 220 | 11.5 | 7.3 | 7.0 | 0.0 | 2.8 | 0.6 | 29.2 | 23 | 15 | 14 | 0 | 6 | 2 | 60 | 36 | 70 |
| | Horizontal | 110 | 75 | 59 | 0 | 16 | 0 | 260 | 13.7 | 9.4 | 7.4 | 0.0 | 3.9 | 0.0 | 34.4 | 28 | 19 | 15 | 0 | 8 | 0 | 70 | 36 | 68 |

Vertical: DPC/Year 250
 Horizontal: DPC/Year 250

* Dose/DPC = (time in rad zone) * (# workers in rad zone) * (dose in rad zone)
 ** Annual Dose = (Total dose to worker by category) * (# DPC's per year) / (# workers in rad zone)

NOTES AND ASSUMPTIONS:

1. The data in these spreadsheets are approximate intended to support occupational exposure estimates only. They are neither definitive nor precise enough to support detailed operational decision.
2. The occupational exposure calculations only consider the scope of activities required to place SNF shipments into storage. Ongoing site monitoring activities are not included.
3. These crew sizes and durations are based on commercial nuclear plant ISFSI operations. Durations are based on real world experience, thus include real world worker efficiencies. Work scope is consistent with C-OPS and has been extrapolated to address the other alternates.
4. Duration fractions incorporate both the number of workers of each category performing the activity and the percentage of time that each worker is occupying the radiation zone.
5. Mechanics are responsible for bolting and unbolting connections to the various SNF containers, other than rigging.
6. Riggers are responsible for attaching and removing rigging to and from the various SNF containers. They are also responsible for observing and guiding heavy lift operations.
7. Health physicists are responsible for measuring the radiation fields and contamination associated with the SNF containers. They are also responsible for decontamination activities and for certifying equipment that enters the radiation zone for release.
8. Operators have overall responsibility for the entire facility. Their activities with respect to SNF processing include opening and closing facility doors, operating the machinery used in SNF container processing, and overseeing the acceptance of the SNF container into the facility.
9. Security personnel are responsible for keeping the facility secure while the CHB railbay doors are open and for verifying that no contraband is introduced to the facility inside of SNF containers.
10. Quality Assurance/Control personnel are responsible to assure that the chain of custody paperwork is properly filled out and for observing hold points in the process to assure proper fitment and placement of SNF containers.
11. Mechanics, riggers, and health physicists (i.e. radiation protection technicians, or radiation control technicians) are assumed to work in pairs. They typically are only near the waste package when needed. If remote monitoring is utilized, the number of health physicists can be reduced in the work area.
12. Duration fractions are only assigned to workers who are in the radiation zone adjacent to the SNF container. Other people may be in the vicinity, but they will remain outside of the radiation zone in accordance with ALARA principles.
13. Although all personnel in the vicinity are accumulating dose, the dose rate for the general area is low and accumulated doses to personnel in the vicinity are insignificant when determined on an individual DPC basis.

1 - C-OPS, Current Canister Transfer Operations Using Cask Handling Building (Base Case)

| Vertical DPCs - DPCs in storage casks on pad | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | |
|--|-----------------------|-------|-------------------|---|-----|---|-----|---|-----------|-----|-----|---|-----|-----|---|
| | | | M | R | H | O | S | Q | M | R | H | O | S | Q | |
| 0) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) Receive transport cask on railcar at Cask Handling Building | 125 | | | | | | | | | | | | | | |
| a) Identify transport cask brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Operators and Security team sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Position transport cask in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Security inspection of the transport cask and tug | 15 | 3 VT | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 | 0 |
| g) HP survey of transport cask | 15 | 3 VT | | | 0.5 | | | | 0 | 0 | 5.5 | 0 | 0 | 0 | 0 |
| h) Inspection of tamper proof Seals | 10 | 3 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0 | 0.7 | 0 |
| i) Acceptance of transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| j) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| k) Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Operators and Security team leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| m) Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Select and inspect rigging for impact limiters on the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 | 0 |
| d) Position man lifts and temporary scaffolding near transport cask | 5 | 1A VT | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Remove first impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| j) Remove second impact limiter and place on storage stand | 10 | 1A VT | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| k) Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Rig the personnel barrier | 15 | 3 VT | 1 | 1 | | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Remove tie-down straps from transport cask | 10 | 3A VT | 0.4 | | | | | | 2.27 | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Rig tie-down straps and move to storage location | 5 | 3A VT | 1 | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | 2 | | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) Upend and lift transport cask off of railcar and place on unloading cell transfer cart | 120 | | | | | | | | | | | | | | |
| a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure lifting block to transport cask trunnions | 10 | 2A VT | 2 | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 | 0 |
| c) Upend transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Lift transport cask off railcar | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Reposition transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Place transport cask in canister transfer cell | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) Secure seismic restraints to Transport Cask | 95 | | | | | | | | | | | | | | |
| a) Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Attach Struts to CHB | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig and Lift Seismic Struts 1&2 into position | 30 | 3 VT | 0.2 | | | | | | 0 | 4.4 | 0 | 0 | 0 | 0 | 0 |
| d) Rig and lift Struts 3&4 into position | 30 | 3 VT | 0.2 | | | | | | 0 | 4.4 | 0 | 0 | 0 | 0 | 0 |
| e) Bolt Seismic collar together around Transport Cask. | 10 | 3 VT | 2 | | | | | | 14.7 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) Stage empty Storage Cask into Transfer Cell using VCT | 75 | | | | | | | | | | | | | | |
| a) Transporter places storage overpack in canister transfer cell | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Crews mobilize to top of storage overpack | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Unbolt storage overpack lid | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Rig storage overpack lid and lift | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) Retract VCT from transfer cell and close shield doors | 30 | | | | | | | | | | | | | | |
| a) Back the VCT out of the Receiving Cell | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Close the canister transfer cell shield doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) Secure seismic restraints to storage overpack | 95 | | | | | | | | | | | | | | |
| a) Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Attach Struts to CHB | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig and Lift Seismic Struts 1&2 into position | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Rig and lift Struts 3&4 into position | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Bolt Seismic collar together around storage overpack | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) Mount adaptor plates to storage overpack | 75 | | | | | | | | | | | | | | |
| a) Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Rig and lift adapter plate 1 to top of Storage Cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Bolt Adapter plate 1 to top of cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Rig and lift adapter plate 2 into position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Bolt Adapter plate 2 to top of cask | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| f) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety Briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) Unbolt and remove transport cask lid using jib crane | 60 | | | | | | | | | | | | | | |
| a) Stage tools on top of the transfer cask | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Unbolt transport cask lid | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig the cask lid to the stick crane | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Lift lid and place it on the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) Attach lifting lug to top of DPC | 70 | | | | | | | | | | | | | | |
| a) Rig lifting lug on storage rack | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Use Jib crane to lift lifting lug into position | 15 | 2A VT | 0.5 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| c) Bolt Lifting lug to canister | 20 | 2 VT | 0.5 | | | | | | 25 | 0 | 0 | 0 | 0 | 0 | 0 |
| d) QC Hold Point Inspection | 10 | 2 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0 | 2.5 | 0 |
| e) Clear workspace and remove all tools | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | | |
|-------------|--|--|-------------|--------|---|--|--|--|--|--|-----|----|----|---|-----|-----|---|
| | c) | Unbolt Seismic collar around Storage overpack | 15 | 3 V T | 1 | | | | | | 11 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift the Seismic struts | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove pins from CBH support stations | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Move Strut assemblies to storage location | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Place Strut assemblies into storage | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | Dock VCT with Storage overpack and bolt on lid | | 65 | | | | | | | | | | | | | | |
| | a) | Position VCT | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move forward and grapple Storage overpack | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Move Storage overpack lid into position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Bolt Lid onto Storage overpack | 15 | 2A V T | 2 | | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 26) | Transport Storage overpack to Pad using VCT | | 120 | | | | | | | | | | | | | | |
| | a) | Lift the Storage overpack | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Drive to storage pad location | 70 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the storage overpack on the Pad | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Bolt storage overpack to the Pad | 20 | 4 V S | 1 | | | | | | 37 | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 35.8 | | | | | | | | | | | | | | |
| 26a) | Turnover to Operations | | 1440 | | | | | | | | | | | | | | |
| 27) | Return VCT to CHB | | 120 | | | | | | | | | | | | | | |
| 28) | Remove adapter plates from Transport Cask | | 60 | | | | | | | | | | | | | | |
| 29) | Install transport cask lid | | 60 | | | | | | | | | | | | | | |
| 30) | Lift transport cask and transfer to maintenance | | 60 | | | | | | | | | | | | | | |
| 30a) | Survey and wipedown Transport Cask | | 60 | | | | | | | | | | | | | | |
| 31) | Lift transport cask and place on railcar | | 60 | | | | | | | | | | | | | | |
| 32) | Install impact limiters on transport cask | | 120 | | | | | | | | | | | | | | |
| 33) | Release railcar for shipment | | 60 | | | | | | | | | | | | | | |
| | | Total Hours of Cask Handling Operations | 69.8 | | | | | | | | 241 | 87 | 53 | 0 | 6.2 | 2.5 | |

| Horizontal DPCs - DPCs in Horizontal Storage Modules on pad | | | Dose | Duration Fraction | | | | | | Task Dose | | | | | | | |
|---|--|--|------------|-------------------|-----|-----|-----|-----|---|-----------|------|-----|-----|---|-----|---|---|
| | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | | |
| 0) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at Cask Handling Building | | 125 | | | | | | | | | | | | | | |
| | a) | Identify SNF shipment brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Security and operator teams sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position SNF shipment in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Security inspection of the SNF shipment and tug | 15 | 3 V T | | | | 0.5 | | | 0 | 0 | 0 | 0 | 5.5 | 0 | 0 |
| | g) | HP survey of SNF shipment | 15 | 3 V T | | 0.5 | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 | 0 |
| | h) | Inspection of tamper proof seals | 10 | 3 V T | | | 0.1 | | | | 0 | 0 | 0 | 0 | 0.7 | 0 | 0 |
| | i) | Acceptance of SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | j) | Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | k) | Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) | Operator and Security teams leave | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | m) | Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | | 195 | | | | | | | | | | | | | | |
| | a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig the lifting devices to the first impact limiter | 5 | 1A V T | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 | 0 |
| | d) | Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A V T | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove and store bolts holding on the first impact limiter | 30 | 1A V T | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove first impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | g) | Remove rigging and reposition on second impact limiter | 5 | 1A V T | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 | 0 |
| | h) | Reposition manlift and scaffolding | 5 | 1A V T | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | Remove and store bolts holding on the second impact limiter | 30 | 1A V T | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 | 0 |
| | j) | Remove second impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 | 0 |
| | k) | Remove and store bolts for personnel barrier | 30 | 3 V T | 0.2 | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) | Rig the personnel barrier | 15 | 3 V T | 1 | 1 | | | | | 0 | 11 | 11 | 0 | 0 | 0 | 0 |
| | m) | Lift personnel barrier and move to storage location | 10 | 3 V T | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) | Remove tie-down straps from SNF shipment | 10 | 3A V T | 0.4 | | | | | | 2.27 | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) | Rig Tie-Down straps and move to storage location | 5 | 3A V T | 1 | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| | p) | Inspect transport cask for damage and conduct HP survey | 15 | 3 V T | | 2 | | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| 3) | Stage Horizontal Cask Transporter (HCT) in truck bay | | 60 | | | | | | | | | | | | | | |
| | a) | Open truck bay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position HCT in truck bay | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close truck bay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Upend and lift transport cask off of railcar and downend on HCT | | 75 | | | | | | | | | | | | | | |
| | a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure lifting block to transport cask trunnions | 5 | 2A V T | 2 | | | | | | 0 | 3.3 | 0 | 0 | 0 | 0 | 0 |
| | c) | Upend transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift transport cask off railcar | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Move transport cask to HCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Downend transport cask on HCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4a) | Remove railcar from railbay | | 60 | | | | | | | | | | | | | | |
| | a) | Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Railyard tug connects to railcar | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Railyard tug removes railcar from railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Railyard tug connects to next railcar | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) | Secure transport cask on HCT | | 40 | | | | | | | | | | | | | | |
| | a) | Position HCT near seismic restraint tie-downs | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Install seismic restraint tie-downs | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 4c) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | |
|-------------|----|--|-------------|-------------|--|---|-----|-----|--|--|------|-----|-----|---|-----|-----|
| | b) | Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | | Transfer transport cask to HSM on pad via HCT | 120 | | | | | | | | | | | | | |
| | a) | QC Hold Point Inspection | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open the truck bay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer the transport cask to HSM on the pad via HCT | 90 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5a) | | Preparation of Horizontal Storage Module (HSM) | 120 | | | | | | | | | | | | | |
| | a) | Stage equipment near HSM | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Place and align Theodolite heads | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig crane to HSM port cover | 15 | 2 C H T L | | 2 | | | | | 0 | 0.8 | 0 | 0 | 0 | 0 |
| | d) | Use manlift to remove nuts on mounting studs | 15 | 1 A H T L | | 2 | | | | | 9.2 | 0 | 0 | 0 | 0 | 0 |
| | e) | Post radiation zone signs and barriers | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove HSM port cover and place in storage location | 20 | 1 A H T L | | 1 | | | | | 0 | 6.1 | 0 | 0 | 0 | 0 |
| | g) | HP survey to verify dose rates | 15 | 1 A H T L | | | 1.5 | | | | 0 | 0 | 6.9 | 0 | 0 | 0 |
| 6) | | Remove transport cask lid | 90 | | | | | | | | | | | | | |
| | a) | Move tools to work platform | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid including gas sampling | 10 | 1 A H T L | | | 2 | | | | 0 | 0 | 6.1 | 0 | 0 | 0 |
| | c) | Position stick crane | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local stick crane | 15 | 1 A H T L | | 2 | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| | e) | Remove and store nuts | 20 | 1 A H T L | | 2 | | | | | 12.3 | 0 | 0 | 0 | 0 | 0 |
| | f) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Security inspection of the interior of the transport cask | 5 | 1 A H T N L | | | | 0.5 | | | 0 | 0 | 0 | 0 | 6.8 | 0 |
| 7) | | Dock HCT with HSM and push DPC into module | 145 | | | | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move HCT into position | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Check alignment | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock HCT to HSM | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove pushing port in base of transport cask | 15 | 5 H H | | 2 | | | | | 4.25 | 0 | 0 | 0 | 0 | 0 |
| | f) | Engage ram and push DPC into module | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Withdraw the ram | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Back the HCT away from the module | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | QC Hold Point Inspection | 10 | 1 A H T N L | | | | 0.2 | | | 0 | 0 | 0 | 0 | 0 | 5.4 |
| 8) | | Install seismic restraints and HSM port cover | 90 | | | | | | | | | | | | | |
| | a) | Retrieve the seismic restraints from HCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reach into module and install the seismic restraints | 5 | 1 A H T N L | | 1 | | | | | 13.6 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 5 | 1 A H T N L | | | | 0.2 | | | 0 | 0 | 0 | 0 | 0 | 2.7 |
| | d) | Pick the HSM port cover still attached to the lifting rig | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position the HSM port cover over the port in the module | 15 | 5 H H | | 1 | | | | | 0 | 2.1 | 0 | 0 | 0 | 0 |
| | f) | Install the nuts on the studs and torque to spec | 15 | 5 H H | | 2 | | | | | 4.25 | 0 | 0 | 0 | 0 | 0 |
| | g) | HP survey of area | 15 | 5 H H | | | 0.5 | | | | 0 | 0 | 1.1 | 0 | 0 | 0 |
| | h) | Remove radiation zone markers and remove all materials | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | | Install transport cask lid | 60 | | | | | | | | | | | | | |
| | a) | Pick the transport cask cover from the still attached to the lifting rig | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position the transport cask cover on the transport cask | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Install the nuts on the studs and torque to spec | 20 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 20.7 | | | | | | | | | | | | | |
| 9a) | | Turnover to Operations | 1440 | | | | | | | | | | | | | |
| 10) | | Return transport cask to Cask Handling Building via HCT | 120 | | | | | | | | | | | | | |
| 10a) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| 11) | | Lift transport cask and transfer to maintenance | 60 | | | | | | | | | | | | | |
| 11a) | | survey and wipedown transport cask | 60 | | | | | | | | | | | | | |
| 11b) | | Reposition empty railcar | 60 | | | | | | | | | | | | | |
| 12) | | Lift transport cask and place on railcar | 60 | | | | | | | | | | | | | |
| 13) | | Install impact limiters on transport cask | 120 | | | | | | | | | | | | | |
| 14) | | Release railcar for shipment | 60 | | | | | | | | | | | | | |
| | | Total Hours of Cask Handling Operations | 54.2 | | | | | | | | 80 | 47 | 55 | 0 | 13 | 8.2 |

2 - A-OPS, Automated Canister Transfer Operations Using Cask Handling Building

| Vertical DPCs - DPCs in storage casks on pad | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | |
|--|-----------------------|-------|-------------------|-----|-----|---|-----|---|-----------|-----|-----|---|-----|-----|
| | | | M | R | H | O | S | Q | M | R | H | O | S | Q |
| 0) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | |
| a) Identify SNF shipment brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Security team sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Send operators to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Position SNF shipment in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 |
| h) HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | 0 | 0 | 5.5 | 0 | 0 | 0 |
| i) Inspection of tamper proof Seals | 10 | 3 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| j) Acceptance of SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| l) Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| m) Security team leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Operator leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| o) Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | |
| a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Select and inspect rigging for impact limiters on the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Rig the lifting devices to the first impact limiter | 5 | 1A VT | | 2 | 2 | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| d) Position man lifts and temporary scaffolding near transport cask | 5 | 1A VT | | 2 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| e) Remove and store bolts holding on the first impact limiter | 30 | 1A VT | | 2 | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| f) Remove first impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| g) Remove rigging and reposition on second impact limiter | 5 | 1A VT | | 1 | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 |
| h) Reposition manlift and scaffolding | 5 | 1A VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| i) Remove and store bolts holding on the second impact limiter | 30 | 1A VT | | 2 | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| j) Remove second impact limiter and place on storage stand | 10 | 1A VT | | 1 | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| k) Remove and store bolts for personnel barrier | 30 | 3 VT | | 0.2 | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| l) Rig the personnel barrier | 15 | 3 VT | | 1 | 1 | | | | 0 | 11 | 11 | 0 | 0 | 0 |
| m) Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) Remove tie-down straps from transport cask | 10 | 3A VT | | 0.4 | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| o) Rig tie-down straps and move to storage location | 5 | 3A VT | | 1 | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| p) Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | | 2 | | | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) Upend and lift transport cask off of railcar and place on unloading cell transfer cart | 120 | | | | | | | | | | | | | |
| a) Select the appropriate lifting block for the transport cask | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure lifting block to transport cask Trunnions | 10 | 2A VT | | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| c) Upend transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Lift transport cask off railcar | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Reposition transport cask | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Place transport cask on unloading cell transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 3a) Remove railcar from railbay | 60 | | | | | | | | | | | | | |
| a) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Railyard tug connects to railcar | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Railyard tug removes railcar from railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Railyard tug connects to next railcar | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) Unbolt and remove transport cask lid using jib crane | 85 | | | | | | | | | | | | | |
| a) Move tools to work platform | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) HP survey of lid including gas sampling | 15 | 2A VT | | | 1 | | | | 0 | 0 | 5 | 0 | 0 | 0 |
| c) Remove and store nuts | 30 | 2A VT | | 1 | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| d) Rig the lid for lifting using the local jib crane | 15 | 2A VT | | 1.5 | | | | | 0 | 7.5 | 0 | 0 | 0 | 0 |
| e) Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Security inspection of the interior of the transport cask | 10 | 2 VT | | | | | 0.2 | | 0 | 0 | 0 | 0 | 5 | 0 |
| 4a) Secure transport cask and transfer cart seismically | 40 | | | | | | | | | | | | | |
| a) Reposition transfer cart near seismic restraint system | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Secure transport cask and transfer cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) QC Hold Point Inspection | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) Attach lifting lug to top of DPC | 70 | | | | | | | | | | | | | |
| a) Rig lifting lug on storage rack | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Use Jib crane to lift lifting lug into position | 15 | 2A VT | | | 0.5 | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| c) Bolt Lifting lug to canister | 20 | 2 VT | | 0.5 | | | | | 25 | 0 | 0 | 0 | 0 | 0 |
| d) QC Hold Point Inspection | 10 | 2 VT | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0 | 2.5 |
| e) Clear workspace and remove all tools | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) Position transport cask transfer cart in unloading cell and close shield doors | 60 | | | | | | | | | | | | | |
| a) Move transport cask cart into the unloading cell | 50 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Close the shield doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) Stage empty storage overpack on receiving cell transfer cart | 195 | | | | | | | | | | | | | |
| a) Prepare an empty storage overpack for use | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Place the empty storage overpack on the transfer cart using VCT | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Stage tools on top of the storage overpack | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) Unbolt storage overpack lid | 30 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) Rig the overpack lid to the VCT hoist | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) Hoist lid and retain on VCT | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) Position empty storage overpack in receiving cell using motorized cart | 60 | | | | | | | | | | | | | |
| a) Open receiving cell shield doors | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) Transfer empty storage overpack into receiving cell using motorized cart | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) Close the shield doors | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) QC Hold Point Inspection | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) Position shielded transfer sleeve cart over unloading cell | 35 | | | | | | | | | | | | | |

| | | | | | | | | | | | | | | | |
|-------------|----|---|-------------|--------|-----|-----|--|--|-----|-----|-----|----|---|----|-----|
| | a) | Inspect transfer sleeve cart | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move shielded transfer sleeve cart over unloading cell | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) | | Lower shield sleeve hoist and grapple DPC lifting lug | 50 | | | | | | | | | | | | |
| | a) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower shield sleeve hoist and grapple DPC lifting lug | 50 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 12) | | Raise DPC into shield sleeve | 190 | | | | | | | | | | | | |
| | a) | Raise DPC into shield sleeve | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Position shielded transfer sleeve cart over storage overpack in receiving cell | 60 | | | | | | | | | | | | |
| | a) | Position shielded transfer sleeve cart over storage overpack in receiving cell | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | | Lower DPC into empty storage overpack, release grapple, and retract hoist | 60 | | | | | | | | | | | | |
| | a) | Lower DPC into empty storage overpack, release grapple, and retract hoist | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey | 0 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Remove lifting lug from DPC | 35 | | | | | | | | | | | | |
| | a) | HP survey | 10 | 2 V T | | 0.2 | | | | 0 | 0 | 5 | 0 | 0 | 0 |
| | b) | Stage tools on top of the storage overpack | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove bolts and rig lifting lug | 10 | 2 V T | 0.3 | 0.2 | | | | 7.5 | 5 | 0 | 0 | 0 | 0 |
| | d) | Remove the lifting lug from the DPC using the jib crane | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Open receiving cell shield doors and transfer storage overpack out of receiving cell | 35 | | | | | | | | | | | | |
| | a) | HP survey | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open receiving cell shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer storage overpack out of receiving cell using motorized cart | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | | Install storage overpack lid | 60 | | | | | | | | | | | | |
| | a) | Position VCT with storage cask lid at storage overpack | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower storage overpack lid into position | 10 | - | | | | | | | | | | | |
| | c) | Install bolts and torque | 20 | 2A V T | 1.5 | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | 2A V T | | | | | 0.1 | 0 | 0 | 0 | 0 | 0 | 0.3 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17a) | | Secure seismic restraints | 40 | | | | | | | | | | | | |
| | a) | Position seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure seismic restraints | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17b) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 18) | | Pick up storage overpack and transfer to pad using VCT | 120 | | | | | | | | | | | | |
| | a) | Rig VCT to lift storage overpack | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | b) | Drive to storage pad location | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the storage overpack on the pad | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | De-rig storage cask from VCT | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | e) | Bolt storage overpack to the pad | 20 | 4 V S | 1 | | | | | 37 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 30.1 | | | | | | | | | | | | |
| 18a) | | Turnover to Operations | 1440 | | | | | | | | | | | | |
| 19) | | Return VCT to CHB | 60 | | | | | | | | | | | | |
| 20) | | Open unloading cell shield doors and position transfer cart under jib crane | 120 | | | | | | | | | | | | |
| 21) | | Install transport cask lid | 60 | | | | | | | | | | | | |
| 22) | | Lift transport cask and transfer to maintenance | 60 | | | | | | | | | | | | |
| 22a) | | Reposition the railcar to the railbay | 60 | | | | | | | | | | | | |
| 22b) | | Survey and wipedown transport cask | 60 | | | | | | | | | | | | |
| 23) | | Lift transport cask and place on railcar | 60 | | | | | | | | | | | | |
| 24) | | Install impact limiters on transport cask | 120 | | | | | | | | | | | | |
| 25) | | Release railcar for shipment | 60 | | | | | | | | | | | | |
| | | Total Hours of Cask Handling Operations | 65.1 | | | | | | | 126 | 60 | 51 | 0 | 11 | 2.8 |

| Horizontal DPCs - DPCs in Horizontal Storage Modules (HSMs) on pad | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | |
|--|---|--------------------|--------|-------------------|---|-----|-----|---|---|-----------|-----|-----|---|-----|---|
| | | | | M | R | H | O | S | Q | M | R | H | O | S | Q |
| 0) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | |
| | a) Plan of the Day Meeting | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Safety briefing | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Transportation to work site | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at Cask Handling Building | 145 | | | | | | | | | | | | | |
| | a) Identify SNF shipment brought from yard | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Security team sent to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Send operators to railbay door | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) Stage work team to railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) Open railbay door | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) Position SNF shipment in the railbay | 15 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) Security inspection of the SNF shipment and tug | 15 | 3 V T | | | | 0.5 | | | 0 | 0 | 0 | 0 | 3.7 | 0 |
| | h) HP survey of SNF shipment | 15 | 3 V T | | | 0.5 | | | | 0 | 0 | 1.8 | 0 | 0 | 0 |
| | i) Inspection of tamper proof seals | 10 | 3 V T | | | | 0.1 | | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| | j) Acceptance of SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | k) Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | l) Secure the railbay doors | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | m) Security team leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) Operator leaves | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | o) Completes paperwork for step #1 | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | |
| | a) Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) Rig the lifting devices to the first impact limiter | 5 | 1A V T | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| | d) Position manlifts and temporary scaffolding near SNF shipment | 5 | 1A V T | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| | e) Remove and store bolts holding on the first impact limiter | 30 | 1A V T | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| | f) Remove first impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| | g) Remove rigging and reposition on second impact limiter | 5 | 1A V T | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 |
| | h) Reposition manlift and scaffolding | 5 | 1A V T | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) Remove and store bolts holding on the second impact limiter | 30 | 1A V T | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| | j) Remove second impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | |
|-------------|----|--|-------------|---------|-----|---|-----|-----|-----|-----|-----|---|-----|-----|
| | k) | Remove and store bolts for personnel barrier | 30 | 3 VT | 0.2 | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| | l) | Rig the personnel barrier | 15 | 3 VT | | 1 | 1 | | 0 | 11 | 11 | 0 | 0 | 0 |
| | m) | Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | n) | Remove tie-down straps from SNF shipment | 10 | 3A VT | 0.4 | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| | o) | Rig Tie-Down straps and move to storage location | 5 | 3A VT | | 1 | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| | p) | Inspect transport cask for damage and conduct HP survey | 15 | 3 VT | | | 2 | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) | | Stage Horizontal Cask Transporter (HCT) in truck bay | 60 | | | | | | | | | | | |
| | a) | Open truck bay door | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position HCT in truck bay | 30 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Close truck bay door | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | | Upend and lift transport cask off of railcar and downend on HCT | 75 | | | | | | | | | | | |
| | a) | Select the appropriate lifting block for the transport cask | 5 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Secure lifting block to transport cask trunnions | 5 | 2A VT | | 2 | | | 0 | 3.3 | 0 | 0 | 0 | 0 |
| | c) | Upend transport cask | 30 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift transport cask off railcar | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Move transport cask to HCT | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Downend transport cask on HCT | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4a) | | Remove railcar from railbay | 60 | | | | | | | | | | | |
| | a) | Open railbay door | 5 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Railyard tug connects to railcar | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Railyard tug removes railcar from railbay | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Railyard tug connects to next railcar | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Railyard tug repositions next railcar in railbay | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4b) | | Secure transport cask on HCT | 40 | | | | | | | | | | | |
| | a) | Position HCT near seismic restraint tie-downs | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Install seismic restraint tie-downs | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4c) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety briefing | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | | Transfer transport cask to HSM on pad via HCT | 120 | | | | | | | | | | | |
| | a) | QC Hold Point Inspection | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open the truck bay door | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transfer the transport cask to HSM on the pad via HCT | 90 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5a) | | Preparation of Horizontal Storage Module (HSM) | 120 | | | | | | | | | | | |
| | a) | Stage equipment near HSM | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Place and align Theodolite heads | 30 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig crane to HSM port cover | 15 | 2C HTL | | 2 | | | 0 | 0.8 | 0 | 0 | 0 | 0 |
| | d) | Use manlift to remove nuts on mounting studs | 15 | 1A HTL | | 2 | | | 9.2 | 0 | 0 | 0 | 0 | 0 |
| | e) | Post radiation zone signs and barriers | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove HSM port cover and place in storage location | 20 | 1A HTL | | 1 | | | 0 | 6.1 | 0 | 0 | 0 | 0 |
| | g) | HP survey to verify dose rates | 15 | 1A HTL | | | 1.5 | | 0 | 0 | 6.9 | 0 | 0 | 0 |
| 6) | | Remove transport cask lid | 90 | | | | | | | | | | | |
| | a) | Move tools to work platform | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | HP survey of lid including gas sampling | 10 | 1A HTL | | 2 | | | 0 | 0 | 6.1 | 0 | 0 | 0 |
| | c) | Position stick crane | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lid for lifting using the local stick crane | 15 | 1A HTL | | 2 | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| | e) | Remove and store nuts | 20 | 1A HTL | | 2 | | | 12 | 0 | 0 | 0 | 0 | 0 |
| | f) | Lift the transport cask lid and move it to the storage stand | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Security inspection of the interior of the transport cask | 5 | 1A HTNL | | | 0.5 | | 0 | 0 | 0 | 0 | 6.8 | 0 |
| 7) | | Dock HCT with HSM and push DPC into module | 145 | | | | | | | | | | | |
| | a) | Position spotters | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Move HCT into position | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Check alignment | 20 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Dock HCT to HSM | 30 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove pushing port in base of transport cask | 15 | 5 HH | | 2 | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | f) | Engage ram and push DPC into module | 20 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Withdraw the ram | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Back the HCT away from the module | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | QC Hold Point Inspection | 10 | 1A HTNL | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 5.4 |
| 8) | | Install seismic restraints and HSM port cover | 90 | | | | | | | | | | | |
| | a) | Retrieve the seismic restraints from HCT | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reach into module and install the seismic restraints | 5 | 1A HTNL | | 1 | | | 14 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 5 | 1A HTNL | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 2.7 |
| | d) | Pick the HSM port cover still attached to the lifting rig | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position the HSM port cover over the port in the module | 15 | 5 HH | | 1 | | | 0 | 2.1 | 0 | 0 | 0 | 0 |
| | f) | Install the nuts on the studs and torque to spec | 15 | 5 HH | | 2 | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| | g) | HP survey of area | 15 | 5 HH | | | 0.5 | | 0 | 0 | 1.1 | 0 | 0 | 0 |
| | h) | Remove radiation zone markers and remove all materials | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | | Install transport cask lid | 70 | | | | | | | | | | | |
| | a) | Security inspection of transport cask to verify lack of contraband | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Pick the transport cask cover from the still attached to the lifting rig | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the transport cask cover on the transport cask | 15 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Install the nuts on the studs and torque to spec | 20 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 21.2 | | | | | | | | | | | |
| 9a) | | Turnover to Operations | 1440 | | | | | | | | | | | |
| 10) | | Return transport cask to Cask Handling Building via HCT | 120 | | | | | | | | | | | |
| 10a) | | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | |
| 11) | | Lift transport cask and transfer to maintenance | 60 | | | | | | | | | | | |
| 11a) | | survey and wipedown transport cask | 60 | | | | | | | | | | | |
| 11b) | | Reposition empty railcar | 60 | | | | | | | | | | | |
| 12) | | Lift transport cask and place on railcar | 60 | | | | | | | | | | | |
| 13) | | Install impact limiters on transport cask | 120 | | | | | | | | | | | |
| 14) | | Release railcar for shipment | 60 | | | | | | | | | | | |
| | | Total Hours of Cask Handling Operations | 43.9 | | | | | | 80 | 47 | 51 | 0 | 11 | 8.2 |

3 - R-OPS, Remote Canister Transfer Operations Using Cask Handling Building

| Vertical DPCs - DPCs in storage casks on pad | | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | | |
|--|--|--|-----------------------|-------|-------------------|---|-----|---|---|-----|-----------|-----|-----|-----|---|---|-----|-----|
| | | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | | |
| 0) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | | | | | | | | | |
| | b) | Safety briefing | 10 | - | | | | | | | | | | | | | | |
| | c) | Transportation to work site | 5 | - | | | | | | | | | | | | | | |
| 1) | Receive transport cask on railcar at Cask Handling Building | | 145 | | | | | | | | | | | | | | | |
| | a) | Identify SNF shipment from yard | 5 | - | | | | | | | | | | | | | | |
| | b) | Security team sent to railbay door | 15 | - | | | | | | | | | | | | | | |
| | c) | Send operators to railbay door | 15 | - | | | | | | | | | | | | | | |
| | d) | Stage work team to railbay | 15 | - | | | | | | | | | | | | | | |
| | e) | Open railbay door | 5 | - | | | | | | | | | | | | | | |
| | f) | Position SNF shipment in the railbay | 15 | - | | | | | | | | | | | | | | |
| | g) | Security inspection of the SNF shipment and tug | 15 | 3 VT | | | | | | 0.5 | | | | | | | 5.5 | |
| | h) | HP survey of SNF shipment | 15 | 3 VT | | | 0.5 | | | | | | | | | | | |
| | i) | Inspection of tamper proof Seals | 10 | 3 VT | | | | | | 0.1 | | | | | | | 0.7 | |
| | j) | Acceptance of SNF shipment | 5 | - | | | | | | | | | | | | | | |
| | k) | Decoupling of railcar and removal of the tug from the railbay | 10 | - | | | | | | | | | | | | | | |
| | l) | Secure the railbay doors | 5 | - | | | | | | | | | | | | | | |
| | m) | Security team leaves | 5 | - | | | | | | | | | | | | | | |
| | n) | Operator leaves | 5 | - | | | | | | | | | | | | | | |
| | o) | Completes paperwork for step #1 | 5 | - | | | | | | | | | | | | | | |
| 2) | Remove impact limiters and place in temporary storage | | 195 | | | | | | | | | | | | | | | |
| | a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | | | | | | | |
| | b) | Select and inspect rigging for impact limiters on the SNF shipment | 5 | - | | | | | | | | | | | | | | |
| | c) | Rig the lifting devices to the first impact limiter | 5 | 1A VT | | | 2 | 2 | | | | | | | | | | |
| | d) | Position man lifts and temporary scaffolding near SNF shipment | 5 | 1A VT | | | 2 | | | | | | | | | | | |
| | e) | Remove and store bolts holding on the first Impact Limiter | 30 | 1A VT | | | 2 | | | | | 15 | | | | | | |
| | f) | Remove first Impact limiter and place on storage stand | 10 | 1A VT | | | 1 | | | | | 0 | 2.5 | | | | | |
| | g) | Remove rigging and reposition on Impact Limiter #2 | 5 | 1A VT | | | 1 | | | | | 0 | 1.3 | | | | | |
| | h) | Reposition Manlift and Scaffolding | 5 | 1A VT | | | | | | | | 0 | 0 | | | | | |
| | i) | Remove and store bolts holding on the Second Impact Limiter | 30 | 1A VT | | | 2 | | | | | 15 | | | | | | |
| | j) | Remove second Impact Limiter and place on storage stand | 10 | 1A VT | | | 1 | | | | | 0 | 2.5 | | | | | |
| | k) | Remove and store bolts for SNF shipment cover | 30 | 3 VT | | | 0.2 | | | | | 4.4 | | | | | | |
| | l) | Rig the personnel barrier | 15 | 3 VT | | | 1 | 1 | | | | 0 | 11 | 11 | | | | |
| | m) | Lift personnel barrier and move to storage location | 10 | 3 VT | | | | | | | | 0 | 0 | | | | | |
| | n) | Remove Tie-Down Straps from transport cask | 10 | 3A VT | | | 0.4 | | | | | 2.3 | | | | | | |
| | o) | Rig Tie-Down straps and move to storage location | 5 | 3A VT | | | 1 | | | | | 0 | 2.8 | | | | | |
| | p) | Inspect Transport Cask for damage and conduct HP survey | 15 | 3 VT | | | | 2 | | | | 0 | 0 | 22 | | | | |
| 3) | Upend and lift transport cask off of railcar and place on remote cell transfer cart | | 120 | | | | | | | | | | | | | | | |
| | a) | Select the appropriate lifting block for the Transport Cask | 5 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | Secure lifting block to Transportation Cask Trunnions | 10 | 2A VT | | | 2 | | | | | 0 | 6.7 | | | | | |
| | c) | Upend Transportation Cask | 30 | - | | | | | | | | 0 | 0 | | | | | |
| | d) | Lift Transportation Cask off railcar | 30 | - | | | | | | | | 0 | 0 | | | | | |
| | e) | Reposition Transportation Cask | 30 | - | | | | | | | | 0 | 0 | | | | | |
| | f) | Place Transportation Cask on remote cell Transfer Cart | 15 | - | | | | | | | | 0 | 0 | | | | | |
| 3a) | Remove railcar from railbay | | 120 | | | | | | | | | | | | | | | |
| | a) | Open railbay door | 5 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | Railyard tug connects to railcar | 10 | - | | | | | | | | 0 | 0 | | | | | |
| | c) | Railyard tug removes railcar from railbay | 10 | - | | | | | | | | 0 | 0 | | | | | |
| | d) | Railyard tug connects to next railcar | 15 | - | | | | | | | | 0 | 0 | | | | | |
| | e) | Railyard tug repositions next railcar in railbay | 10 | - | | | | | | | | 0 | 0 | | | | | |
| | f) | Railyard tug leaves railbay and railbay door is closed | 10 | - | | | | | | | | 0 | 0 | | | | | |
| 4) | Unbolt and remove transport cask lid using jib crane | | 75 | | | | | | | | | | | | | | | |
| | a) | Move tools to work platform | 5 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | HP survey of lid | 5 | 2A VT | | | 1 | | | | | 0 | 0 | 1.7 | | | | |
| | c) | Remove and store Nuts | 30 | 2A VT | | | 1 | | | | | 10 | | | | | | |
| | d) | Rig the Lid for lifting using the local jib crane | 15 | 2A VT | | | 1.5 | | | | | 0 | 7.5 | | | | | |
| | e) | Lift the Transport Cask Lid and move it to the storage stand | 10 | - | | | | | | | | 0 | 0 | | | | | |
| | f) | Security inspection of the interior of the Transport Cask | 10 | 2 VT | | | | | | 0.2 | | 0 | 0 | | | | 5 | |
| 5) | Attach lifting lug to top of DPC | | 70 | | | | | | | | | | | | | | | |
| | a) | Rig lifting lug on storage rack | 15 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | Use Jib crane to lift lifting lug into position | 15 | 2A VT | | | 0.5 | | | | | 0 | 2.5 | | | | | |
| | c) | Bolt Lifting lug to canister | 20 | 2 VT | | | 0.5 | | | | | 25 | | | | | | |
| | d) | QC Hold Point Inspection | 10 | 2 VT | | | | | | 0.1 | | 0 | 0 | | | | 0 | 2.5 |
| | e) | Clear workspace and remove all tools | 10 | - | | | | | | | | 0 | 0 | | | | | |
| 6) | Position transport cask transfer cart in remote cell and close shield doors | | 15 | | | | | | | | | | | | | | | |
| | a) | Move Transport cask cart into the remote cell | 10 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | Close the shield doors | 5 | - | | | | | | | | 0 | 0 | | | | | |
| 7) | Stage empty storage overpack in remote cell using a transfer cart | | 25 | | | | | | | | | | | | | | | |
| | a) | Open remote cell shield doors | 5 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | Transfer empty storage overpack into remote cell | 15 | - | | | | | | | | 0 | 0 | | | | | |
| | c) | QC Hold Point Inspection | 5 | - | | | | | | | | 0 | 0 | | | | | |
| 8) | Unbolt empty storage overpack lid and hoist on VCT | | 60 | | | | | | | | | | | | | | | |
| | a) | Stage tools on top of the storage overpack | 10 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | Unbolt storage overpack lid | 30 | - | | | | | | | | 0 | 0 | | | | | |
| | c) | Rig the cask lid to the VCT hoist | 10 | - | | | | | | | | 0 | 0 | | | | | |
| | d) | Lift lid to the storage position of the VCT | 10 | - | | | | | | | | 0 | 0 | | | | | |
| 9) | Retract VCT from remote cell and close shield doors | | 15 | | | | | | | | | | | | | | | |
| | a) | Back the VCT out of the remote cell | 20 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | Close the shield doors | 10 | - | | | | | | | | 0 | 0 | | | | | |
| 10) | Lower remote cell hoist and grapple DPC lifting lug | | 45 | | | | | | | | | | | | | | | |
| | a) | Position remote cell crane over transport cask in remote cell | 15 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | Lower remote cell hoist and grapple DPC Lifting Lug | 15 | - | | | | | | | | 0 | 0 | | | | | |
| | c) | Verify grapple engages | 15 | - | | | | | | | | 0 | 0 | | | | | |
| 11) | Lift the DPC from the Transport Cask | | 70 | | | | | | | | | | | | | | | |
| | a) | Raise DPC out of Transport Cask as HP monitors doses outside cell | 60 | - | | | | | | | | 0 | 0 | | | | | |
| | b) | QC Hold Point Inspection | 10 | - | | | | | | | | 0 | 0 | | | | | |
| 12) | Reposition and lower the DPC into the Storage overpack | | 120 | | | | | | | | | | | | | | | |
| | a) | Position remote cell crane over storage overpack in remote cell | 60 | - | | | | | | | | 0 | 0 | | | | | |

| | | | | | | | | | | | | | | | |
|-------------|----|---|-------------|--------|-----|-----|--|--|-----|-----|-----|----|---|----|-----|
| | b) | Lower remote cell hoist and place DPC in storage overpack | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 13) | | Release grapple, and retract hoist | 15 | | | | | | | | | | | | |
| | a) | Release grapple, and retract hoist | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 14) | | Open remote cell shield doors and position VCT at storage overpack | 70 | | | | | | | | | | | | |
| | a) | HP survey | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Open remote cell shield doors | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the VCT at the Storage overpack | 50 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 15) | | Remove lifting lug from DPC | 40 | | | | | | | | | | | | |
| | a) | HP survey | 10 | 2 V T | | 0.2 | | | | 0 | 0 | 5 | 0 | 0 | 0 |
| | b) | Stage tools on top of the storage overpack | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Remove bolts and rig lifting lug | 10 | 2 V T | 0.3 | 0.2 | | | | 7.5 | 5 | 0 | 0 | 0 | 0 |
| | d) | Remove the lifting lug from the DPC using the jib crane | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 16) | | Install storage cask lid | 60 | | | | | | | | | | | | |
| | a) | Position VCT with storage overpack lid at storage cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Lower storage overpack lid into position | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Install bolts and torque | 20 | 2A V T | 1.5 | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | 2A V T | | | | | 0.1 | 0 | 0 | 0 | 0 | 0 | 0.3 |
| | e) | Clean out tools and leave the top of the DPC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 17) | | Pick up storage overpack and transfer to pad using VCT | 120 | | | | | | | | | | | | |
| | a) | Rig VCT to lift storage overpack | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | b) | Drive to storage pad location | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Position the storage overpack on the pad | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | De-rig storage overpack from VCT | 10 | 2A V T | 2 | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| | e) | Bolt storage overpack to the pad | 20 | 4 V S | 1 | | | | | 37 | 0 | 0 | 0 | 0 | 0 |
| | | Total Hours of Canister Handling Operations | 23.5 | | | | | | | | | | | | |
| 17a) | | Turnover to Operations | 1440 | | | | | | | | | | | | |
| 18) | | Return VCT to CHB | 60 | | | | | | | | | | | | |
| 20) | | Open remote cell shield doors and position transfer cart under jib crane | 120 | | | | | | | | | | | | |
| 20) | | Install transport cask lid | 60 | | | | | | | | | | | | |
| 21) | | Lift transport cask and transfer to maintenance | 60 | | | | | | | | | | | | |
| 21a) | | Survey and wipedown Transport Cask | 60 | | | | | | | | | | | | |
| 21b) | | Reposition empty railcar | 60 | | | | | | | | | | | | |
| 22) | | Lift transport cask and place on railcar | 60 | | | | | | | | | | | | |
| 23) | | Install impact limiters on transport cask | 120 | | | | | | | | | | | | |
| 24) | | Release railcar for shipment | 60 | | | | | | | | | | | | |
| | | Total Hours of Cask Handling Operations | 58.5 | | | | | | | 126 | 60 | 48 | 0 | 11 | 2.8 |

4 - S-OPS, Simplified Canister Transfer Operations Without Cask Handling Building

| Vertical DSCs - DSCs in storage casks on pad | | | Duration (Minutes) | Dose | Duration Fraction | | | | | | Task Dose | | | | | | |
|---|--|--|-----------------------|-------|-------------------|-----|-----|---|---|-----|-----------|-----|-----|-----|---|-----|-----|
| | | | | | M | R | H | O | S | Q | M | R | H | O | S | Q | |
| 0) Plan of the Day and Safety Meeting | | | 30 | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Safety Briefing | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Transportation to work site | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) Receive transport cask on railcar at the siding | | | 100 | | | | | | | | | | | | | | |
| a) | Identify Transport Cask in yard | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Stage work team at siding | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Position Waste Package under gantry crane | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Security inspection of the Transport Cask | | 15 | 3 VT | | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 |
| e) | HP Survey of Transport Cask | | 15 | 3 VT | | | 0.5 | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 |
| f) | Inspection of Tamper proof Seals | | 10 | 3 VT | | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| g) | Acceptance of Package | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| h) | Decoupling of railcar and removal of the tug from the siding | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| i) | Security team leaves | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| j) | Completes paperwork for step #1 | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) Remove impact limiters and place in temporary storage using the gantry crane | | | 195 | | | | | | | | | | | | | | |
| a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Select and inspect rigging for impact limiters on the Transport Cask | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Rig the lifting devices to the first impact limiter | | 5 | 1A VT | | 2 | 2 | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| d) | Position man lifts and temporary scaffolding near Transport Cask | | 5 | 1A VT | | 2 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| e) | Remove and store bolts holding on the first Impact Limiter | | 30 | 1A VT | | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| f) | Remove first Impact limiter and place on storage stand | | 10 | 1A VT | | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| g) | Remove rigging and reposition on Impact Limiter #2 | | 5 | 1A VT | | 1 | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 |
| h) | Reposition Manlift and Scaffolding | | 5 | 1A VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| i) | Remove and store bolts holding on the Second Impact Limiter | | 30 | 1A VT | | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| j) | Remove second Impact Limiter and place on storage stand | | 10 | 1A VT | | 1 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| k) | Remove and store bolts for package cover | | 30 | 3 VT | | 0.2 | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| l) | Rig the package cover | | 15 | 3 VT | | 1 | 1 | | | | | 0 | 11 | 11 | 0 | 0 | 0 |
| m) | Lift package cover and move to storage location | | 10 | 3 VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) | Remove Tie-Down Straps from Transport Cask | | 10 | 3A VT | | 0.4 | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| o) | Rig Tie-Down straps and move to storage location | | 5 | 3A VT | | 1 | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| p) | Inspect Transport Cask for damage and conduct HP Survey | | 15 | 3 VT | | | 2 | | | | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) Upend and lift transport cask off of railcar and place on the pad | | | 120 | | | | | | | | | | | | | | |
| a) | Select the appropriate lifting block for the Transport Cask | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Secure lifting block to Transportation Cask Trunnions | | 10 | 2A VT | | 2 | | | | | | 0 | 6.7 | 0 | 0 | 0 | 0 |
| c) | Upend Transportation Cask | | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Lift Transportation Cask off railcar | | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Reposition Transportation Cask | | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Place Transportation Cask on the "spot" | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) Install seismic/stack-up struts on Transport Cask using stick crane | | | 95 | | | | | | | | | | | | | | |
| a) | Move tools to work platform | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Attach Struts to Stantions on pad | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Rig and Lift Seismic Struts 1&2 into position | | 30 | 3 VT | | 0.2 | | | | | | 0 | 4.4 | 0 | 0 | 0 | 0 |
| d) | Rig and lift Struts 3&4 into position | | 30 | 3 VT | | 0.2 | | | | | | 0 | 4.4 | 0 | 0 | 0 | 0 |
| e) | Bolt Seismic collar together around Transport Cask. | | 10 | 3 VT | | 2 | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| f) | QC Hold Point Inspection | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) Transporter moves storage overpack into position and removes lid | | | 75 | | | | | | | | | | | | | | |
| a) | Transporter places Storage overpack on "spot" | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Crews mobilize to top of Storage overpack | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Unbolt storage overpack lid | | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Rig Storage overpack Lid and lift | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | QC Hold Point Inspection | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 6) Mount adapter plates to top of storage overpack using stick crane | | | 75 | | | | | | | | | | | | | | |
| a) | Move tools to work platform | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Rig and lift adapter plate 1 to top of Storage Cask | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Bolt Adapter plate 1 to top of cask | | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Rig and lift adapter plate 2 into position | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Bolt Adapter plate 2 to top of cask | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | QC Hold Point Inspection | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7) Install seismic stack-up struts on storage overpack and weather cover using stick crane | | | 85 | | | | | | | | | | | | | | |
| a) | Move tools to work platform | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Attach Struts to Stantions on pad | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Rig and Lift Seismic Struts 1&2 into position | | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Rig and lift Struts 3&4 into position | | 15 | 2A VT | | 0.5 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| e) | Bolt Seismic collar together around Transport Cask. | | 10 | 2 VT | | 0.5 | | | | | | 13 | 0 | 0 | 0 | 0 | 0 |
| f) | QC Hold Point Inspection | | 10 | 2 VT | | | | | | | 0.1 | 0 | 0 | 0 | 0 | 0 | 2.5 |
| g) | Install Weather cover | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 7a) Plan of the Day and Safety Meeting | | | 30 | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Safety Briefing | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Transportation to work site | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 8) Unbolt and remove transport cask lid | | | 60 | | | | | | | | | | | | | | |
| a) | Stage tools on top of the transport cask | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Unbolt transport cask lid | | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Rig the cask lid to the stick crane | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Lift lid and place it on the storage stand | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) Attach lifting lug to top of DSC | | | 70 | | | | | | | | | | | | | | |
| a) | Rig lifting lug on storage rack | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Use stick crane to lift lifting lug into position | | 15 | 2A VT | | 0.5 | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| c) | Bolt Lifting lug to canister | | 20 | 2 VT | | 0.5 | | | | | | 25 | 0 | 0 | 0 | 0 | 0 |
| d) | QC Hold Point Inspection | | 10 | 2 VT | | | | | | | | 0 | 0 | 0 | 0 | 0 | 2.5 |
| e) | Clear workspace and remove all tools | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 10) Mount adapter plates to top of Transport Cask using stick crane | | | 85 | | | | | | | | | | | | | | |
| a) | Move tools to work platform | | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Rig and lift adapter plate 1 to top of Transport Cask | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Bolt Adapter plate 1 to top of cask | | 20 | 2A VT | | 1.5 | | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| d) | Rig and lift adapter plate 2 into position | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Bolt Adapter plate 2 to top of cask | | 20 | 2A VT | | 1.5 | | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| f) | QC Hold Point Inspection | | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 11) Install the Transfer Cask on Transport Cask using the gantry crane | | | 75 | | | | | | | | | | | | | | |
| a) | Rig Transport Cask using the Gantry crane | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Lift Transport Cask to upper position | | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |


| | | | | | | | | | | | | | | | | |
|--|---|--|------------|-------|-----|-----|--|--|-----|-----|-----|-----|---|---|-----|-----|
| | c) | Reposition the Gantry crane | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lower Transport cask onto alignment lugs | 15 | 2A VT | 1 | | | | | 0 | 5 | 0 | 0 | 0 | 0 | 0 |
| | e) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 12) Bolt Transfer Cask to adapter plate | | 70 | | | | | | | | | | | | | |
| | a) | Position Man Lifts with bolts and tools | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Bolt Transfer cask to adapter plate | 15 | 2A VT | 2 | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Torque bolts | 20 | 2A VT | 2 | | | | | 13 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clear workspace and remove all tools | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 13) Raise canister from transport cask up into transfer cask | | 105 | | | | | | | | | | | | | |
| | a) | Release Lifting block and reposition gantry crane hoist | 10 | 2 VT | 0.3 | 0.2 | | | | 7.5 | 5 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position auxiliary hoist over Transfer Cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower grapple and grapple DSC | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift DSC into transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Engage locking mechanism | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Release grapple and withdraw hoist | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 13a) Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety Briefing | 10 | 2A VT | 1.5 | | | | | 5 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | 2A VT | | | | | 0.1 | 0 | 0 | 0 | 0 | 0 | 0 | 0.2 |
| | 14) Unbolt Transfer Cask from adapter plate | | 80 | | | | | | | | | | | | | |
| | a) | Position Man Lifts with tools | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position Gantry crane over transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Engage Lifting Block onto Transfer Cask Trunnions | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Unbolt Transfer Cask bolts and remove | 20 | 2A VT | 2 | | | | | 13 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clear workspace and remove all tools | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 15) Move Transfer Cask from Transport Cask to Storage Cask | | 60 | | | | | | | | | | | | | |
| | a) | Lift the Transfer Cask off the Transport Cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reposition Gantry Crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower Transfer Cask onto Storage cask alignment blocks | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 16) Install weather cover to Transport Cask | | 105 | | | | | | | | | | | | | |
| | a) | Retrieve Weather Cover from Storage box | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position Man Lifts on either side of Transport Cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Install Weather cover | 20 | 4 VS | 1 | | | | | 37 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 17) Bolt Transfer Cask to adapter plate | | 70 | | | | | | | | | | | | | |
| | a) | Position Man Lifts with bolts and tools | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Bolt Transfer cask to adapter plate | 15 | 2A VT | 2 | | | | | 10 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Torque bolts | 20 | 2A VT | 2 | | | | | 13 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clear workspace and remove all tools | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 18) Lower canister from Transfer Cask into Storage overpack | | 10 | | | | | | | | | | | | | |
| | a) | Release Lifting block and reposition gantry crane hoist | 60 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position auxiliary hoist over Transfer Cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower grapple and grapple DSC | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift DSC to clear locking mechanism | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Lower Canister into Storage overpack | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Release grapple and withdraw hoist | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | HP Survey | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 19) Unbolt Transfer Cask from adapter plate | | 70 | | | | | | | | | | | | | |
| | a) | Reposition gantry crane hoist over Transfer Cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Grapple the Transfer cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | a) | Position Man Lifts with tools | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Unbolt Transfer cask from adapter plate | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Clear workspace and remove all tools | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 20) Remove Transfer Cask and place into storage | | 60 | | | | | | | | | | | | | |
| | a) | Lift Transfer Cask off of Storage overpack adaptor plates | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reposition Gantry Crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Lower Transfer Cask onto location | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Release Lifting block and raise gantry crane hoist | 10 | 3 VT | | | | | 0.5 | 0 | 0 | 0 | 0 | 0 | 3.7 | 0 |
| | 21) Remove adapter plates | | 115 | | | | | | | | | | | | | |
| | a) | Move tools to Man Lift | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Attach rigging to Adapter Plate 2 | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Unbolt Adaptor plate 2 | 30 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Lift Adaptor Plate 2 and place in storage location using stick crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Attach rigging to Adapter Plate 1 | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Unbolt Adaptor Plate 1 | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Lift Adaptor Plate 1 and place in storage location using stick crane | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Install Weather cover | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | Clear workspace and remove all tools | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 21a) Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | |
| | a) | Plan of the Day Meeting | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Safety Briefing | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Transportation to work site | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 22) Remove lifting lug from DSC | | 55 | | | | | | | | | | | | | |
| | a) | HP Survey | 10 | 2 VT | | 0.2 | | | | 0 | 0 | 5 | 0 | 0 | 0 | 0 |
| | b) | Remove the Weather Cover | 15 | 1A VT | 1 | | | | | 3.8 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Stage tools on top of the storage cask | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | Rig the lifting lug assembly to the stick crane and remove the bolts | 10 | 2 VT | 1 | | | | | 0 | 25 | 0 | 0 | 0 | 0 | 0 |
| | e) | Remove the lifting lug from the DSC | 10 | 3 VT | 1 | 1 | | | | 0 | 7.3 | 7.3 | 0 | 0 | 0 | 0 |
| | f) | Clean out tools and leave the top of the DSC | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 23) Remove seismic/stack-up struts on Storage Cask | | 75 | | | | | | | | | | | | | |
| | a) | Reposition Man Lifts | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Rig Seismic Struts 1&2 | 5 | 3A VT | 1 | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 | 0 |
| | c) | Rig seismic struts 3&4 | 10 | 3 VT | 1 | | | | | 0 | 7.3 | 0 | 0 | 0 | 0 | 0 |
| | d) | Unbolt Seismic collar around Transport Cask | 15 | 3 VT | | 2 | | | | 0 | 0 | 22 | 0 | 0 | 0 | 0 |
| | e) | Lift the Seismic struts | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | f) | Remove pins from support stantions on the pad | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | Move Strut assemblies to storage location | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | h) | Place Strut assemblies into storage | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | i) | Reposition Man Lifts | 5 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | 24) Dock VCT with Storage Cask and bolt on lid | | 65 | | | | | | | | | | | | | |
| | a) | Position VCT | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | |
|-------------|---|-------------|--------|---|--|--|--|--|--|--|-----|----|----|---|-----|-----|
| b) | Move forward and grapple Storage Overpack | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Move Storage Cask lid into position | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Bolt Lid onto Storage Overpack | 15 | 2A V T | 2 | | | | | | | 10 | 0 | 0 | 0 | 0 | 0 |
| e) | QC Hold Point Inspection | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 25) | Pick up storage overpack and transfer to pad using VCT | 110 | | | | | | | | | | | | | | |
| a) | Lift the Storage overpack | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Drive to storage pad location | 60 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Position the storage overpack on the Pad | 20 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Bolt storage overpack to the Pad | 20 | 4 V S | 1 | | | | | | | 37 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of Canister Handling Operations | 36.8 | | | | | | | | | | | | | | |
| 26) | Turnover to Operations | 1440 | | | | | | | | | | | | | | |
| 27) | Return VCT to siding | 120 | | | | | | | | | | | | | | |
| 28) | Install transport cask lid | 60 | | | | | | | | | | | | | | |
| 29) | Remove seismic/stack-up struts from Transport Cask | 60 | | | | | | | | | | | | | | |
| 30) | Lift Transport Cask and Transfer to Maintenance | 60 | | | | | | | | | | | | | | |
| 30a) | Survey and wipedown Transport Cask | 60 | | | | | | | | | | | | | | |
| 31) | Lift transport cask and place on railcar | 60 | | | | | | | | | | | | | | |
| 32) | Install impact limiters on transport cask | 120 | | | | | | | | | | | | | | |
| 33) | Release railcar for shipment | 60 | | | | | | | | | | | | | | |
| | Total Hours of Cask Handling Operations | 70.8 | | | | | | | | | 269 | 98 | 75 | 0 | 9.9 | 5.2 |

| Horizontal DSCs - DSCs in Horizontal Storage Modules on pad | | | Duration (Min) | Top of DSC | Duration Fraction | | | | | | Task Dose | | | | | |
|---|---|------------|----------------|------------|-------------------|-----|---|-----|-----|---|-----------|-----|-----|---|-----|---|
| | | | | | M | R | H | O | S | Q | M | R | H | O | S | Q |
| | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Safety Briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 1) | Receive transport cask on railcar at site | 100 | | | | | | | | | | | | | | |
| a) | Identify Transport Cask to bring in from yard | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Stage work team to siding | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Position Transport Cask under the gantry crane | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Security inspection of the Transport Cask and tug | 15 | 3 V T | | | | | | 0.5 | | 0 | 0 | 0 | 0 | 5.5 | 0 |
| e) | HP Survey of Transport Cask | 15 | 3 V T | | | 0.5 | | | | | 0 | 0 | 5.5 | 0 | 0 | 0 |
| f) | Inspection of Tamper proof Seals | 10 | 3 V T | | | | | | 0.1 | | 0 | 0 | 0 | 0 | 0.7 | 0 |
| g) | Acceptance of Package Paperwork | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| h) | Decoupling of railcar and removal of the tug from the siding | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| i) | Security team leaves | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| j) | Completes paperwork for step #1 | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 2) | Remove impact limiters and place in temporary storage | 195 | | | | | | | | | | | | | | |
| a) | Mobilize crew (mechanics, riggers, crane operator, etc.) | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Select and inspect rigging for impact limiters on the Transport Cask | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Rig the lifting devices to the first impact limiter | 5 | 1A V T | 2 | 2 | | | | | | 0 | 2.5 | 2.5 | 0 | 0 | 0 |
| d) | Position man lifts and temporary scaffolding near Transport Cask | 5 | 1A V T | 2 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| e) | Remove and store bolts holding on the first Impact Limiter | 30 | 1A V T | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| f) | Remove first Impact limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| g) | Remove rigging and reposition on Impact Limiter #2 | 5 | 1A V T | 1 | | | | | | | 0 | 1.3 | 0 | 0 | 0 | 0 |
| h) | Reposition Manlift and Scaffolding | 5 | 1A V T | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| i) | Remove and store bolts holding on the Second Impact Limiter | 30 | 1A V T | 2 | | | | | | | 15 | 0 | 0 | 0 | 0 | 0 |
| j) | Remove second Impact Limiter and place on storage stand | 10 | 1A V T | 1 | | | | | | | 0 | 2.5 | 0 | 0 | 0 | 0 |
| k) | Remove and store bolts for package cover | 30 | 3 V T | 0.2 | | | | | | | 4.4 | 0 | 0 | 0 | 0 | 0 |
| l) | Rig the package cover | 15 | 3 V T | 1 | 1 | | | | | | 0 | 11 | 11 | 0 | 0 | 0 |
| m) | Lift package cover and move to storage location | 10 | 3 V T | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| n) | Remove Tie-Down Straps from Transport Cask | 10 | 3A V T | 0.4 | | | | | | | 2.3 | 0 | 0 | 0 | 0 | 0 |
| o) | Rig Tie-Down straps and move to storage location | 5 | 3A V T | 1 | | | | | | | 0 | 2.8 | 0 | 0 | 0 | 0 |
| p) | Inspect Transport Cask for damage and conduct HP Survey | 15 | 3 V T | | | | 2 | | | | 0 | 0 | 22 | 0 | 0 | 0 |
| 3) | Upend and lift transport cask off of railcar and downend on HCT | 75 | | | | | | | | | | | | | | |
| a) | Select the appropriate lifting block for the Transport Cask | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Secure lifting block to Transport Cask Trunnions | 5 | 2A V T | 2 | | | | | | | 0 | 3.3 | 0 | 0 | 0 | 0 |
| c) | Upend Transport Cask | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Lift Transport Cask off railcar | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Reposition Transport Cask | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Place Transport Cask on HCT | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 4) | Plan of the Day and Safety Meeting | 30 | | | | | | | | | | | | | | |
| a) | Plan of the Day Meeting | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Safety Briefing | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Transportation to work site | 5 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5) | Transfer transport cask to Horizontal Storage Module on pad via HCT | 105 | | | | | | | | | | | | | | |
| a) | QC Hold Point Inspection | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Transfer the transport cask to Horizontal Storage Module on the pad via HCT | 90 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| 5a) | Preparation of Module | 120 | | | | | | | | | | | | | | |
| a) | Stage equipment near Horizontal Storage Module | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Place and align Theodolite heads | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Rig crane to Horizontal Storage Module (HSM) port cover | 15 | 2CH T L | 2 | | | | | | | 0 | 0.8 | 0 | 0 | 0 | 0 |
| d) | Use man lift to remove nuts on mounting studs | 15 | 1A H T L | 2 | | | | | | | 9.2 | 0 | 0 | 0 | 0 | 0 |
| e) | Post Radiation Zone signs and barriers | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| f) | Remove HSM Port cover and place in storage location | 20 | 1A H T L | 1 | | | | | | | 0 | 6.1 | 0 | 0 | 0 | 0 |
| g) | HP Survey to verify Dose Rates | 15 | 1A H T L | | | 1.5 | | | | | 0 | 0 | 6.9 | 0 | 0 | 0 |
| 6) | Remove transport cask lid | 90 | | | | | | | | | | | | | | |
| a) | Move tools to work platform | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | HP Survey of lid | 10 | 1A H T L | | | 2 | | | | | 0 | 0 | 6.1 | 0 | 0 | 0 |
| c) | Position Stick Crane | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Rig the Lid for lifting using the local stick crane | 15 | 1A H T L | 2 | | | | | | | 0 | 9.2 | 0 | 0 | 0 | 0 |
| e) | Remove and store Nuts | 20 | 1A H T L | 2 | | | | | | | 12 | 0 | 0 | 0 | 0 | 0 |
| f) | Lift the Transport Cask Lid and move it to the storage stand | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) | Security inspection of the interior of the Transport Cask | 5 | 1A H T NL | | | | | 0.5 | | | 0 | 0 | 0 | 0 | 6.8 | 0 |
| 7) | Dock HCT with HSM and push DSC into module | 145 | | | | | | | | | | | | | | |
| a) | Position spotters | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| b) | Move HCT into position | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| c) | Check alignment | 20 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| d) | Dock HCT to HSM | 30 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| e) | Remove pushing port in base of transport cask | 15 | 5 H H | 2 | | | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 |
| f) | Engage ram and push DPC into module | 20 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| g) | Withdraw the ram | 15 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |
| h) | Back the HCT away from the module | 10 | - | | | | | | | | 0 | 0 | 0 | 0 | 0 | 0 |

| | | | | | | | | | | | | | | | | |
|-------------|--|--|-------------|-----------|---|---|-----|--|-----|-----|-----|-----|---|----|-----|-----|
| | i) | QC Hold Point Inspection | 10 | 1A H T NL | | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 0 | 5.4 |
| 8) | Install seismic restraints and HSM port cover | | 90 | | | | | | | | | | | | | |
| | a) | Retrieve the seismic restraints from HCT | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Reach into module and install the seismic restraints | 5 | 1A H T NL | 1 | | | | | 14 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | QC Hold Point Inspection | 5 | 1A H T NL | | | | | 0.2 | 0 | 0 | 0 | 0 | 0 | 0 | 2.7 |
| | d) | Pick the HSM port cover still attached to the lifting rig | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | e) | Position the HSM port cover over the port in the module | 15 | 5 H H | | 1 | | | | 0 | 2.1 | 0 | 0 | 0 | 0 | 0 |
| | f) | Install the nuts on the studs and torque to spec | 15 | 5 H H | 2 | | | | | 4.3 | 0 | 0 | 0 | 0 | 0 | 0 |
| | g) | HP survey of area | 15 | 5 H H | | | 0.5 | | | 0 | 0 | 1.1 | 0 | 0 | 0 | 0 |
| | h) | Remove radiation zone markers and remove all materials | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| 9) | Install transport cask lid | | 60 | | | | | | | | | | | | | |
| | a) | Pick the Transport Cask Cover from the still attached to the Lifting Rig | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | b) | Position the Transport Cask Cover on the Transport Cask | 15 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | c) | Install the nuts on the studs and torque to spec | 20 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | d) | QC Hold Point Inspection | 10 | - | | | | | | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | Total Hours of Canister Handling Operations | | 17.3 | | | | | | | | | | | | | |
| 9a) | Turnover to Operations | | 1440 | | | | | | | | | | | | | |
| 10) | Return transport cask to rail siding | | 120 | | | | | | | | | | | | | |
| 10a) | Plan of the Day and Safety Meeting | | 30 | | | | | | | | | | | | | |
| 11) | Lift transport cask and transfer to maintenance | | 60 | | | | | | | | | | | | | |
| 11a) | Survey and wipedown Transport Cask | | 60 | | | | | | | | | | | | | |
| 11b) | Reposition empty railcar | | 60 | | | | | | | | | | | | | |
| 12) | Lift transport cask and place on railcar | | 60 | | | | | | | | | | | | | |
| 13) | Install impact limiters on transport cask | | 120 | | | | | | | | | | | | | |
| 14) | Release railcar for shipment | | 60 | | | | | | | | | | | | | |
| | Total Hours of Cask Handling Operations | | 50.8 | | | | | | | 80 | 47 | 55 | 0 | 13 | 8.2 | |

Container Doses



| | | | | | |
|------------|----|---|---|-------|------------------------------|
| 1 V C | 1 | V | C | 512 | transport cask lid removed |
| 1A H T L | 1A | H | T | 18.4 | transport cask lid installed |
| 1A H T N L | 1A | H | T | 163.2 | transport cask lid removed |
| 1A V C | 1A | V | C | 254 | no transfer cask lid |
| 1A V T | 1A | V | T | 15 | impact limiters installed |
| 1B V C | 1B | V | C | 134 | no transfer cask lid |
| 1C V C | 1C | V | C | 117 | no transfer cask lid |
| 1D V C | 1D | V | C | 62 | no transfer cask lid |
| 2 V T | 2 | V | T | 150 | transport cask lid removed |
| 2A H T | 2A | H | T | 31.8 | transport cask lid installed |
| 2A V T | 2A | V | T | 20 | transport cask lid installed |
| 2B V X | 2B | V | X | 125 | |
| 2C H T L | 2C | H | T | 1.5 | transport cask lid installed |
| 2C H T N L | 2C | H | T | 7.1 | transport cask lid removed |
| 3 V T | 3 | V | T | 44 | |
| 3A V T | 3A | V | T | 34 | |
| 3B V C | 3B | V | C | 146 | |
| 4 H T | 4 | H | T | 31.8 | |
| 4 V S | 4 | V | S | 111 | |
| 4 V X | 4 | V | X | 177 | |
| 4A H H | 4A | H | H | 2.5 | port cover installed |
| 5 H H | 5 | H | H | 8.5 | port cover installed |
| 5A H H | 5A | H | H | 3.2 | port cover installed |

Total Dose to Worker by Category*

Annual Dose to Unit Worker by Category**

Number of Workers by Category

| Storage Alternative | Worker Category: # of Workers: | Total Dose to Worker by Category* | | | | | | | Annual Dose to Unit Worker by Category** | | | | | | | Number of Workers by Category | | | | | | |
|---------------------|-----------------------------------|-----------------------------------|---------|----------------|-----------|----------|---------|-------|--|---------|----------------|-----------|----------|---------|-------|-------------------------------|---------|----------------|-----------|----------|---------|-------|
| | | Mechanics | Riggers | Health Physics | Operators | Security | Quality | Total | Mechanics | Riggers | Health Physics | Operators | Security | Quality | Total | Mechanics | Riggers | Health Physics | Operators | Security | Quality | Total |
| App B1 - C-OPS | Vertical | 241 | 87 | 53 | 0 | 6 | 3 | 391 | 30.2 | 10.9 | 6.7 | 0.0 | 1.6 | 0.6 | 49.9 | 61 | 22 | 14 | 0 | 4 | 2 | 103 |
| | Horizontal | 80 | 47 | 55 | 0 | 13 | 8 | 203 | 10.0 | 5.8 | 6.9 | 0.0 | 3.3 | 2.0 | 28.0 | 21 | 12 | 14 | 0 | 7 | 5 | 59 |
| App B2 - A-OPS | Vertical | 126 | 60 | 51 | 0 | 11 | 3 | 251 | 15.8 | 7.5 | 6.4 | 0.0 | 2.8 | 0.7 | 33.2 | 32 | 16 | 13 | 0 | 6 | 2 | 69 |
| | Horizontal | 80 | 47 | 51 | 0 | 11 | 8 | 198 | 10.0 | 5.8 | 6.4 | 0.0 | 2.8 | 2.0 | 27.1 | 21 | 12 | 13 | 0 | 6 | 5 | 57 |
| App B3 - R-OPS | Vertical | 126 | 60 | 48 | 0 | 11 | 3 | 248 | 15.8 | 7.5 | 6.0 | 0.0 | 2.8 | 0.7 | 32.8 | 32 | 16 | 12 | 0 | 6 | 2 | 68 |
| | Horizontal | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| App B4 - S-OPS | Vertical | 269 | 98 | 75 | 0 | 10 | 5 | 458 | 33.6 | 12.3 | 9.4 | 0.0 | 2.5 | 1.3 | 59.1 | 68 | 25 | 19 | 0 | 5 | 3 | 120 |
| | Horizontal | 80 | 47 | 55 | 0 | 13 | 8 | 203 | 10.0 | 5.8 | 6.9 | 0.0 | 3.3 | 2.0 | 28.0 | 21 | 12 | 14 | 0 | 7 | 5 | 59 |

Vertical: DPC/Year 250 * Dose/DPC = (time in rad zone) * (# workers in rad zone) * (dose in rad zone)
 Horizontal: 250 ** Annual Dose = (Total dose to worker by category) * (# DPC's per year) / (# workers in rad zone)